

טלפון

תיכון מס'

מדינת ישראל משרד המשפטים מנהל המבחנים	
שם תיק: לשכת חברות וכלכלה - שבח - שיטת סלבין	
מזהה כיוז: 6044/6-ג	
מזהה פריט: 000p41j	
כתובת: 2-107-9-6-8	
תאריך הדפסה: 10/12/2017	

מסלול

מסלול

שם תיק: לשכת חברות וכלכלה - שבח - שיטת סלבין
מזהה כיוז: 6044/6-ג
מזהה פריט: 000p41j
כתובת: 2-107-9-6-8
תאריך הדפסה: 10/12/2017

07 01 01

Handwritten notes and signatures in the top left corner, including the word "Informal" and various initials.

ש א ל ו ן

בניה טרומית לפי שיטת סלבין

על מנת שנוכל לספק אומדנים מהאימים על הוצאות הקמת דירות לפי שיטת סלבין נודה לך אם חוכל לספק לנו אינפורמציה על תנאי השוק בפרט לפי הפירוט הבא:

1. שכר עבודה (כולל זכויות סוציאליות)

- א. פועל בנין פשוט
- ב. פועל בנין מקצועי
- ג. חשמלאי בבנין
- ד. שרברבית בבנין
- ה. מנהלי עבודה בבנין
- ו. פועלי אחזקה
- ז. טכנאים
- ח. מהנדסים
- ט. מקידיים
- י. מנהלי משרד

כמו כן נבקשך לציין מהוא שוק העבודה של כל אחד מטובי העובדים המפורטים. מה המצב כאשר להשגת עובדים אלו.

2. מחירי חומרים (בשערי המפעל, במידה שהמחיר הוא על הספק - נא לציין מחירי הובלה)

- א. מלט - טונה
- ב. ברזל בעובי של 18 - 6 מ"מ
- ג. חצץ בגודל שונה
- ד. חול

האם ניתן להשיג חומרים אלו, ודרגה הקושי של השגתם, מועדי ותנאי הספקה ותנאי תשלום.

3. מחירי עבודות מקצועיות (כולל חומרים)

- א. אינסטלציה חשמלית (נא לציין את יחידת התשלום
- ב. אינסטלציה מים (נקודה, אורך, כמות חומרים, עבודה וכו')
- ג. אינסטלציה טניטרית
- ד. צבעות - למטר מרובע
- ה. הריצוף - איזה ריצוף מקובל, מחירו למס"ר - עבודה וחומרים

THE NEW YORK PUBLIC LIBRARY

ASTOR LENOX TILDEN FOUNDATION
155 E. 42ND STREET, NEW YORK 17, N.Y.

THE NEW YORK PUBLIC LIBRARY

1. THE NEW YORK PUBLIC LIBRARY
2. THE NEW YORK PUBLIC LIBRARY
3. THE NEW YORK PUBLIC LIBRARY
4. THE NEW YORK PUBLIC LIBRARY
5. THE NEW YORK PUBLIC LIBRARY
6. THE NEW YORK PUBLIC LIBRARY
7. THE NEW YORK PUBLIC LIBRARY
8. THE NEW YORK PUBLIC LIBRARY
9. THE NEW YORK PUBLIC LIBRARY
10. THE NEW YORK PUBLIC LIBRARY

THE NEW YORK PUBLIC LIBRARY
ASTOR LENOX TILDEN FOUNDATION
155 E. 42ND STREET, NEW YORK 17, N.Y.

THE NEW YORK PUBLIC LIBRARY
ASTOR LENOX TILDEN FOUNDATION
155 E. 42ND STREET, NEW YORK 17, N.Y.

1. THE NEW YORK PUBLIC LIBRARY
2. THE NEW YORK PUBLIC LIBRARY
3. THE NEW YORK PUBLIC LIBRARY
4. THE NEW YORK PUBLIC LIBRARY
5. THE NEW YORK PUBLIC LIBRARY

THE NEW YORK PUBLIC LIBRARY
ASTOR LENOX TILDEN FOUNDATION
155 E. 42ND STREET, NEW YORK 17, N.Y.

THE NEW YORK PUBLIC LIBRARY

1. THE NEW YORK PUBLIC LIBRARY
2. THE NEW YORK PUBLIC LIBRARY
3. THE NEW YORK PUBLIC LIBRARY
4. THE NEW YORK PUBLIC LIBRARY
5. THE NEW YORK PUBLIC LIBRARY
6. THE NEW YORK PUBLIC LIBRARY
7. THE NEW YORK PUBLIC LIBRARY
8. THE NEW YORK PUBLIC LIBRARY
9. THE NEW YORK PUBLIC LIBRARY
10. THE NEW YORK PUBLIC LIBRARY

4. אפשרות שימוש בגורמים מקצועיים, תנאים מקובלים ומחירים

- א. עבודות ברזל כמו מעקה של סדרגות וכדומה. האם קיימים בתי מלאכה שמקבלים עבודות כאלו בקבלנות או שיש לבצע אותם ישירות בעזרת פועלים.
- ב. האם קיימים מרכזי הספקת בטון. מחיר לטונה.
- ג. מה גודל מקסימלי של מובילי בטון ומהם התנאים המקובלים.

5. ביטוי חוץ לבית

- א. מה מקובל לכיטוי חיצוני
 - (1) צבע סיד
 - (2) צבע שמן
 - (3) צבע פלאסטי
 - (4) שפריץ, פרופיל עם תוספות של אבנים קטנות.
 - ב. מה המחירים המקובלים למס"ר של כל סוג צבע (ואם מקובל לפי משקל - מחיר ליחידת משקל).
- אם המחירים מקובלים לחומר לחוד ולעבודה לחוד, נא לציין בנפרד.

6. שאלות כלליות

- א. מהם עבודות הפיתוח המקובלות בשטח הבניה: כבישים, סדרכות, גינות, חניה וכו'. האם נוהגים לכלול אותם במחיר הבניה ומה המחירים המקובלים.
- ב. מהם מחירי הפגריים לבניה באזורים הרלוונטיים. אחוזי בניה מקובלים (מספר יחידות לשטח ומידת הריכוז של הבנינים).
- ג. כמה קומות מקובל לבנות ומה מספר הקומות המבוקש. לצרכי בניה מתועשת מתאים ביותר 4 קומות. אצלנו אין צורך במעלית למבנה כזה. באם צריך מעלית למבנה כזה, מה המחירים והתנאים המקובלים.

2. RESEARCH DESIGN AND METHODS

- a. The study was designed to determine the effect of the independent variable on the dependent variable.
- b. The study was conducted in a laboratory setting.
- c. The study was conducted in a field setting.
- d. The study was conducted in a natural setting.

3. RESULTS

- a. The results of the study are as follows:
 - (1) The first result is that the independent variable had a significant effect on the dependent variable.
 - (2) The second result is that the independent variable had a significant effect on the dependent variable.
 - (3) The third result is that the independent variable had a significant effect on the dependent variable.
- b. The results of the study are as follows:
 - (1) The first result is that the independent variable had a significant effect on the dependent variable.
 - (2) The second result is that the independent variable had a significant effect on the dependent variable.
 - (3) The third result is that the independent variable had a significant effect on the dependent variable.
- c. The results of the study are as follows:
 - (1) The first result is that the independent variable had a significant effect on the dependent variable.
 - (2) The second result is that the independent variable had a significant effect on the dependent variable.
 - (3) The third result is that the independent variable had a significant effect on the dependent variable.

4. CONCLUSIONS

- a. The study has shown that the independent variable has a significant effect on the dependent variable.
- b. The study has shown that the independent variable has a significant effect on the dependent variable.
- c. The study has shown that the independent variable has a significant effect on the dependent variable.
- d. The study has shown that the independent variable has a significant effect on the dependent variable.

- ד. האם אפשר לקבל שירותים של דירה צפופה מקובלת. אצלנו דירה כזאת היא בגבולות של 70 מ"ר ברוטו וכוללת 2 חדרי שינה, חדר מגורים, מטבח, שירותים, מרפסת וחלק יחסי בחדר המדרגות. נא לציין מה כולל השטח אצלכם לפי הפירוט הנ"ל.
- ה. מה הסטנדרט המקובל לדירה כזאת ומה הוא כולל (אביזרים וכד').
- ו. מה מחיר השוק של דירה כזאת בבניה קונבנציונלית ומה עלותה לבונה, תוך פירוט המרכיבים השונים.
- ז. במידה האפשרי נא לציין מרכיבי מחיר מקובלים, כל פרט חשוב לנו.
- ח. האם קיימות במקום הבניה ובמקום המפעל תחנות השמל או קוי השמל מרכזיים אשר יספקו השמל לצרכי בניה ומאור ולצרכי המפעל. כנ"ל הספקת מים.
- ט. נא לציין מחירים ותנאים.
- מיסים
- ט. (1) מה המיסים המקובלים בבניה, כגון - מיסי בניה, מיס, ביוב וכד'.
- (2) מיסי הכנה ומיסי חברות, שיעורים מקובלים הנהגות וכד'.
- י. שיעורי פחת מקובלים, לצידוד מכנים וכד'.
- יא. תנאי כימון מקובלים, מקורות האשראי, תנאי חשלוט וכד'.
- יב. הוצאות נוספות אפשריות כגון: חיבור לרשת החשמל, מס עסקים וכד'.
- האינפורמציה הנדרשת הינה חיונית ביותר כדי שנוכל לענות בצורה מפורטת על כל השאלות הקשורות בנושא ולעשות תחשיבים והערכות.
- נודה לכם מאד על כל פירוט שיוגש לנו ונבקשכם במידת האפשר לזרז את מתן החשובות.

07 01 01 / 126 nre - 22000 23P.
QUESTIONNAIRE 6.972

Pre-fabricated Building by Selbin System

In order to enable us to supply you with adequate estimates for the construction of apartments by the ~~SL~~AVIN system, we should appreciate your letting us have some data on the market in Iran, based on the following details:

1. LABOUR (including social benefits)

- a. Unskilled building worker
- b. Specialized building worker
- c. Building electricians
- d. Building plumbers
- e. Building foremen
- f. Maintenance staff
- g. Mechanics
- h. Engineers
- i. Clerical staff
- j. Office managers

Please also inform us how the labour market is for each of the above categories, as well as their availability.

2. PRICE OF MATERIALS (on the site. If prices are by suppliers, please mention transportation costs)

- a. Cement - per ton
- b. Iron - 6 to 18 mm thickness
- c. Gravel - in various sizes
- d. Sand

Are these materials available, difficulties in obtaining same, delays and conditions of supply, terms of payment.

3. PRICES OF PROFESSIONAL WORKS (including materials)

- a. Electrical installation)
- b. Water installation) (please mention unit of payment,
- c. Sanitary installation) point, length, quantity of materials, labour etc.)

DISCUSSION

1. The Role of the Teacher

The teacher is the central figure in the classroom. He is the one who guides the students, who provides the knowledge, and who creates the learning environment. The teacher's role is to facilitate the learning process, to encourage the students to think critically, and to help them to develop their own learning strategies.

2. The Role of the Student

The student is the active participant in the learning process. He is the one who takes responsibility for his own learning, who seeks out the knowledge, and who applies it to his own life.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

The student's role is to learn, to think, and to act. He is the one who takes the knowledge that the teacher provides and makes it his own.

3. The Role of the Parent

The parent is the first teacher of the child. He is the one who provides the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

The parent's role is to provide the child with the basic knowledge and skills that he needs to survive in the world.

- d. Painting - per square meter
- e. Flooring - what are the usual floors, price per m^2 , labour and materials.

4. POSSIBILITY OF USING PROFESSIONAL FACILITIES, CONDITIONS, PRICES

- a. Iron work, such as staircase railings etc. Are there workshops accepting such orders on contract, or have they to be executed by own staff.
- b. Are there supply centers for concrete? Price per ton.
- c. What is the largest size of concrete transporters, and what are the customary conditions.

5. FAÇADE COATING

- a. What is used for the façade:
 - (1) whitewash
 - (2) oil paint
 - (3) plastic paint
 - (4) *sprayed plaster*, profile with small stones added
- b. What are the customary prices per m^2 for each category of paint (if quotations are per weight, price per unit of weight).
If it is customary to quote materials and labour separately, please do so.

6. GENERAL QUESTIONS

- a. What are the customary development works on the building site: roads, sidewalks, gardens, parking lots etc. Are these usually included in the price of building, and what are the customary prices.
- b. What are the prices of building plots in the relevant districts
Percentage of building space (number of units per area and rate of density of buildings).
- c. How many stories are usually built, and what is the number of stories preferred. For industrialized building, 4 stories are best suited. In Israel, there is no need for lifts in buildings of such size. If lifts are needed in Iran, what are prices and conditions.

1. General - The purpose of this

2. Object - This is a study of the

3. Method - The method used is

4. Results - The results of the

5. Conclusion - The conclusion is

6. References - The references are

7. Appendix - The appendix is

8. Summary - The summary is

9. Acknowledgments - The acknowledgments

10. Bibliography - The bibliography

11. Index - The index is

12. Glossary - The glossary is

13. List of Figures - The list of figures

14. List of Tables - The list of tables

15. List of Abbreviations - The list of abbreviations

16. List of Symbols - The list of symbols

17. List of Equations - The list of equations

18. List of Figures - The list of figures

19. List of Tables - The list of tables

20. List of Abbreviations - The list of abbreviations

21. List of Symbols - The list of symbols

22. List of Equations - The list of equations

23. List of Figures - The list of figures

24. List of Tables - The list of tables

25. List of Abbreviations - The list of abbreviations

26. List of Symbols - The list of symbols

27. List of Equations - The list of equations

28. List of Figures - The list of figures

29. List of Tables - The list of tables

30. List of Abbreviations - The list of abbreviations

31. List of Symbols - The list of symbols

32. List of Equations - The list of equations

- d. Is it possible to receive blueprints of a popular apartment. Here, such an apartment measures around 70 m² gross containing 2 bedrooms, living room, kitchen, conveniences, terraces and proportional part of the staircase. Please inform us how an apartment in your country compares to the above.
- e. What is the customary standard of such an apartment and what does it include (accessories, etc.)
- f. What is the market price of such an apartment in conventional building and what is its costprice. Please give breakdown.
- g. As far as possible, give components of usual calculation. Every detail is important to us.
- h. Are there a power station or power lines available at the building site or at the plant, supplying power and light. The same as regards the supply of water. Prices and conditions.
- i. Taxes
- (1) What are the usual taxes on building, such as building taxes, water, canalization etc.
- (2) Company taxes, rates, reductions, etc.
- j. Usual depreciation on equipment, buildings, etc.
- k. Usual financing conditions, sources of credit, terms of payment, etc.
- l. Possible additional expenses, such as connection to the electricity supply, business tax, etc.

The requested information is essential so that we may reply in detail on all questions connected with the subject and prepare estimates and calculations .

We shall be most grateful for every other/detail, and are looking forward to your early reply.

Journal of Management Education 30(6)p.789-804

QUESTIONNAIRE

Pre-fabricated Building by Selbin System

In order to enable us to supply you with adequate estimates for the construction of apartments by the Selbin system, we should appreciate your letting us have some data on the market in Iran, based on the following details:

1. LABOUR (including social benefits)

- a. Unskilled building worker
- b. Specialized building worker
- c. Building electricians
- d. Building plumbers
- e. Building foremen
- f. Maintenance staff
- g. Mechanics
- h. Engineers
- i. Clerical staff
- j. Office managers

Please also inform us how the labour market is for each of the above categories, as well as their availability.

2. PRICE OF MATERIALS (on the site. If prices are by suppliers, please mention transportation costs)

- a. Cement - per ton
- b. Iron - 6 to 18 mm thickness
- c. Gravel - in various sizes
- d. Sand

Are these materials available, difficulties in obtaining same, delays and conditions of supply, terms of payment.

3. PRICES OF PROFESSIONAL WORKS (including materials)

- a. Electrical installation)
- b. Water installation) (please mention unit of payment,
- c. Sanitary installation) point, length, quantity of materials, labour etc.)

- d. Painting - per square meter
- e. Flooring - what are the usual floors, price per m^2 , labour and materials.

4. POSSIBILITY OF USING PROFESSIONAL FACILITIES, CONDITIONS, PRICES

- a. Iron work, such as staircase railings etc. Are there workshops accepting such orders on contract, or have they to be executed by own staff.
- b. Are there supply centers for concrete? Price per ton.
- c. What is the largest size of concrete transporters, and what are the customary conditions.

5. FAÇADE COATING

- a. What is used for the façade:
 - (1) whitewash
 - (2) oil paint
 - (3) plastic paint
 - (4) spray plaster, profile with small stones added
- b. What are the customary prices per m^2 for each category of paint (if quotations are per weight, price per unit of weight).

If it is customary to quote materials and labour separately, please do so.

6. GENERAL QUESTIONS

- a. What are the customary development works on the building site: roads, sidewalks, gardens, parking lots etc. Are these usually included in the price of building, and what are the customary prices.
- b. What are the prices of building plots in the relevant districts Percentage of building space (number of units per area and rate of density of buildings).
- c. How many stories are usually built, and what is the number of stories preferred. For industrialized building, 4 stories are best suited. In Israel, there is no need for lifts in buildings of such size. If lifts are needed in Iran, what are prices and conditions.

- d. Is it possible to receive blueprints of a popular apartment. Here, such an apartment measures around 70 m² gross containing 2 bedrooms, living room, kitchen, conveniences, terraces and proportional part of the staircase. Please inform us how an apartment in your country compares to the above.
- e. What is the customary standard of such an apartment and what does it include (accessories, etc.)
- f. What is the market price of such an apartment in conventional building and what is its costprice. Please give breakdown.
- g. As far as possible, give components of usual calculation. Every detail is important to us.
- h. Are there a power station or power lines available at the building site or at the plant, supplying power and light. The same as regards the supply of water. Prices and conditions.
- i. Taxes
 - (1) What are the usual taxes on building, such as building taxes, water, canalization etc.
 - (2) Company taxes, rates, reductions, etc.
- j. Usual depreciation on equipment, buildings, etc.
- k. Usual financing conditions, sources of credit, terms of payment, etc.
- l. Possible additional expenses, such as connection to the electricity supply, business tax, etc.

The requested information is essential so that we may reply in detail on all questions connected with the subject and prepare estimates and calculations .

We shall be most grateful for every other/detail, and are looking forward to your early reply.

QUESTIONNAIRE

Pre-fabricated Building by Selbin System

In order to enable us to supply you with adequate estimates for the construction of apartments by the ~~SL~~AVin system, we should appreciate your letting us have some data on the market in Iran, based on the following details:

1. LABOUR (including social benefits)

- a. Unskilled building worker
- b. Specialized building worker
- c. Building electricians
- d. Building plumbers
- e. Building foremen
- f. Maintenance staff
- g. Mechanics
- h. Engineers
- i. Clerical staff
- j. Office managers

Please also inform us how the labour market is for each of the above categories, as well as their availability.

2. PRICE OF MATERIALS (on the site. If prices are by suppliers, please mention transportation costs)

- a. Cement - per ton
- b. Iron - 6 to 18 mm thickness
- c. Gravel - in various sizes
- d. Sand

Are these materials available, difficulties in obtaining same, delays and conditions of supply, terms of payment.

3. PRICES OF PROFESSIONAL WORKS (including materials)

- a. Electrical installation)
- b. Water installation) (please mention unit of payment,
- c. Sanitary installation) point, length, quantity of materials, labour etc.)

- d. Painting - per square meter
- e. Flooring - what are the usual floors, price per m², labour and materials.

4. POSSIBILITY OF USING PROFESSIONAL FACILITIES, CONDITIONS, PRICES

- a. Iron work, such as staircase railings etc. Are there workshops accepting such orders on contract, or have they to be executed by own staff.
- b. Are there supply centers for concrete? Price per ton.
- c. What is the largest size of concrete transporters, and what are the customary conditions.

5. FAÇADE COATING

- a. What is used for the façade:
 - (1) whitewash
 - (2) oil paint
 - (3) plastic paint
 - (4) spray plaster, profile with small stones added
- b. What are the customary prices per m² for each category of paint (if quotations are per weight, price per unit of weight).

If it is customary to quote materials and labour separately, please do so.

6. GENERAL QUESTIONS

- a. What are the customary development works on the building site: roads, sidewalks, gardens, parking lots etc. Are these usually included in the price of building, and what are the customary prices.
- b. What are the prices of building plots in the relevant districts Percentage of building space (number of units per area and rate of density of buildings).
- c. How many stories are usually built, and what is the number of stories preferred. For industrialized building, 4 stories are best suited. In Israel, there is no need for lifts in buildings of such size. If lifts are needed in Iran, what are prices and conditions.

- d. Is it possible to receive blueprints of a popular apartment. Here, such an apartment measures around 70 m² gross containing 2 bedrooms, living room, kitchen, conveniences, terraces and proportional part of the staircase. Please inform us how an apartment in your country compares to the above.
- e. What is the customary standard of such an apartment and what does it include (accessories, etc.)
- f. What is the market price of such an apartment in conventional building and what is its costprice. Please give breakdown.
- g. As far as possible, give components of usual calculation. Every detail is important to us.
- h. Are there a power station or power lines available at the building site or at the plant, supplying power and light. The same as regards the supply of water. Prices and conditions.
- i. Taxes
 - (1) What are the usual taxes on building, such as building taxes, water, canalization etc.
 - (2) Company taxes, rates, reductions, etc.
- j. Usual depreciation on equipment, buildings, etc.
- k. Usual financing conditions, sources of credit, terms of payment, etc.
- l. Possible additional expenses, such as connection to the electricity supply, business tax, etc.

The requested information is essential so that we may reply in detail on all questions connected with the subject and prepare estimates and calculations .

We shall be most grateful for every other/detail, and are looking forward to your early reply.

QUESTIONNAIRE

Pre-fabricated Building by Selbin System

In order to enable us to supply you with adequate estimates for the construction of apartments by the Selbin system, we should appreciate your letting us have some data on the market in Iran, based on the following details:

1. LABOUR (including social benefits)

- a. Unskilled building worker
- b. Specialized building worker
- c. Building electricians
- d. Building plumbers
- e. Building foremen
- f. Maintenance staff
- g. Mechanics
- h. Engineers
- i. Clerical staff
- j. Office managers

Please also inform us how the labour market is for each of the above categories, as well as their availability.

2. PRICE OF MATERIALS (on the site. If prices are by suppliers, please mention transportation costs)

- a. Cement - per ton
- b. Iron - 6 to 18 mm thickness
- c. Gravel - in various sizes
- d. Sand

Are these materials available, difficulties in obtaining same, delays and conditions of supply, terms of payment.

3. PRICES OF PROFESSIONAL WORKS (including materials)

- a. Electrical installation)
- b. Water installation) (please mention unit of payment,
- c. Sanitary installation) point, length, quantity of materials, labour etc.)

- d. Painting - per square meter
- e. Flooring - what are the usual floors, price per m^2 , labour and materials.

4. POSSIBILITY OF USING PROFESSIONAL FACILITIES, CONDITIONS, PRICES

- a. Iron work, such as staircase railings etc. Are there workshops accepting such orders on contract, or have they to be executed by own staff.
- b. Are there supply centers for concrete? Price per ton.
- c. What is the largest size of concrete transporters, and what are the customary conditions.

5. FAÇADE COATING

- a. What is used for the façade:
 - (1) whitewash
 - (2) oil paint
 - (3) plastic paint
 - (4) spray plaster, profile with small stones added
- b. What are the customary prices per m^2 for each category of paint (if quotations are per weight, price per unit of weight).

If it is customary to quote materials and labour separately, please do so.

6. GENERAL QUESTIONS

- a. What are the customary development works on the building site: roads, sidewalks, gardens, parking lots etc. Are these usually included in the price of building, and what are the customary prices.
- b. What are the prices of building plots in the relevant districts
Percentage of building space (number of units per area and rate of density of buildings).
- c. How many stories are usually built, and what is the number of stories preferred. For industrialized building, 4 stories are best suited. In Israel, there is no need for lifts in buildings of such size. If lifts are needed in Iran, what are prices and conditions.

- d. Is it possible to receive blueprints of a popular apartment. Here, such an apartment measures around 70 m² gross containing 2 bedrooms, living room, kitchen, conveniences, terraces and proportional part of the staircase. Please inform us how an apartment in your country compares to the above.
- e. What is the customary standard of such an apartment and what does it include (accessories, etc.)
- f. What is the market price of such an apartment in conventional building and what is its costprice. Please give breakdown.
- g. As far as possible, give components of usual calculation. Every detail is important to us.
- h. Are there a power station or power lines available at the building site or at the plant, supplying power and light. The same as regards the supply of water. Prices and conditions.
- i. Taxes
 - (1) What are the usual taxes on building, such as building taxes, water, canalization etc.
 - (2) Company taxes, rates, reductions, etc.
- j. Usual depreciation on equipment, buildings, etc.
- k. Usual financing conditions, sources of credit, terms of payment, etc.
- l. Possible additional expenses, such as connection to the electricity supply, business tax, etc.

The requested information is essential so that we may reply in detail on all questions connected with the subject and prepare estimates and calculations .

We shall be most grateful for every other/detail, and are looking forward to your early reply.

QUESTIONNAIRE

Pre-fabricated Building by Selbin System

In order to enable us to supply you with adequate estimates for the construction of apartments by the Selbin system, we should appreciate your letting us have some data on the market in Iran, based on the following details:

1. LABOUR (including social benefits)

- a. Unskilled building worker
- b. Specialized building worker
- c. Building electricians
- d. Building plumbers
- e. Building foremen
- f. Maintenance staff
- g. Mechanics
- h. Engineers
- i. Clerical staff
- j. Office managers

Please also inform us how the labour market is for each of the above categories, as well as their availability.

2. PRICE OF MATERIALS (on the site. If prices are by suppliers, please mention transportation costs)

- a. Cement - per ton
- b. Iron - 6 to 18 mm thickness
- c. Gravel - in various sizes
- d. Sand

Are these materials available, difficulties in obtaining same, delays and conditions of supply, terms of payment.

3. PRICES OF PROFESSIONAL WORKS (including materials)

- a. Electrical installation)
- b. Water installation) (please mention unit of payment,
- c. Sanitary installation) point, length, quantity of materials, labour etc.)

- d. Painting - per square meter
- e. Flooring - what are the usual floors, price per m², labour and materials.

4. POSSIBILITY OF USING PROFESSIONAL FACILITIES, CONDITIONS, PRICES

- a. Iron work, such as staircase railings etc. Are there workshops accepting such orders on contract, or have they to be executed by own staff.
- b. Are there supply centers for concrete? Price per ton.
- c. What is the largest size of concrete transporters, and what are the customary conditions.

5. FAÇADE COATING

- a. What is used for the façade:
 - (1) whitewash
 - (2) oil paint
 - (3) plastic paint
 - (4) spray plaster, profile with small stones added
- b. What are the customary prices per m² for each category of paint (if quotations are per weight, price per unit of weight).

If it is customary to quote materials and labour separately, please do so.

6. GENERAL QUESTIONS

- a. What are the customary development works on the building site: roads, sidewalks, gardens, parking lots etc. Are these usually included in the price of building, and what are the customary prices.
- b. What are the prices of building plots in the relevant districts Percentage of building space (number of units per area and rate of density of buildings).
- c. How many stories are usually built, and what is the number of stories preferred. For industrialized building, 4 stories are best suited. In Israel, there is no need for lifts in buildings of such size. If lifts are needed in Iran, what are prices and conditions.

- d. Is it possible to receive blueprints of a popular apartment. Here, such an apartment measures around 70 m² gross containing 2 bedrooms, living room, kitchen, conveniences, terraces and proportional part of the staircase. Please inform us how an apartment in your country compares to the above.
- e. What is the customary standard of such an apartment and what does it include (accessories, etc.)
- f. What is the market price of such an apartment in conventional building and what is its costprice. Please give breakdown.
- g. As far as possible, give components of usual calculation. Every detail is important to us.
- h. Are there a power station or power lines available at the building site or at the plant, supplying power and light. The same as regards the supply of water. Prices and conditions.
- i. Taxes
 - (1) What are the usual taxes on building, such as building taxes, water, canalization etc.
 - (2) Company taxes, rates, reductions, etc.
- j. Usual depreciation on equipment, buildings, etc.
- k. Usual financing conditions, sources of credit, terms of payment, etc.
- l. Possible additional expenses, such as connection to the electricity supply, business tax, etc.

The requested information is essential so that we may reply in detail on all questions connected with the subject and prepare estimates and calculations .

We shall be most grateful for every other/detail, and are looking forward to your early reply.

07 01 01

QUESTIONNAIRE

Pre-fabricated Building by Selbin System

In order to enable us to supply you with adequate estimates for the construction of apartments by the SLAVIN system, we should appreciate your letting us have some data on the market in Iran, based on the following details:

1. LABOUR (including social benefits)

- a. Unskilled building worker
- b. Specialized building worker
- c. Building electricians
- d. Building plumbers
- e. Building foremen
- f. Maintenance staff
- g. Mechanics
- h. Engineers
- i. Clerical staff
- j. Office managers

Please also inform us how the labour market is for each of the above categories, as well as their availability.

2. PRICE OF MATERIALS (on the site. If prices are by suppliers, please mention transportation costs)

- a. Cement - per ton
- b. Iron - 6 to 18 mm thickness
- c. Gravel - in various sizes
- d. Sand

Are these materials available; difficulties in obtaining same, delays and conditions of supply, terms of payment.

3. PRICES OF PROFESSIONAL WORKS (including materials)

- a. Electrical installation)
- b. Water installation) (please mention unit of payment,
- c. Sanitary installation) point, length, quantity of materials, labour etc.)

- d. Painting - per square meter
- e. Flooring - what are the usual floors, price per m^2 , labour and materials.

4. POSSIBILITY OF USING PROFESSIONAL FACILITIES, CONDITIONS, PRICES

- a. Iron work, such as staircase railings etc. Are there workshops accepting such orders on contract, or have they to be executed by own staff.
- b. Are there supply centers for concrete? Price per ton.
- c. What is the largest size of concrete transporters, and what are the customary conditions.

5. FAÇADE COATING

- a. What is used for the façade:
 - (1) whitewash
 - (2) oil paint
 - (3) plastic paint
 - (4) spray plaster, profile with small stones added
- b. What are the customary prices per m^2 for each category of paint (if quotations are per weight, price per unit of weight).

If it is customary to quote materials and labour separately, please do so.

6. GENERAL QUESTIONS

- a. What are the customary development works on the building site: roads, sidewalks, gardens, parking lots etc. Are these usually included in the price of building, and what are the customary prices.
- b. What are the prices of building plots in the relevant districts Percentage of building space (number of units per area and rate of density of buildings).
- c. How many stories are usually built, and what is the number of stories preferred. For industrialized building, 4 stories are best suited. In Israel, there is no need for lifts in buildings of such size. If lifts are needed in Iran, what are prices and conditions.

- d. Is it possible to receive blueprints of a popular apartment. Here, such an apartment measures around 70 m² gross containing 2 bedrooms, living room, kitchen, conveniences, terraces and proportional part of the staircase. Please inform us how an apartment in your country compares to the above.
- e. What is the customary standard of such an apartment and what does it include (accessories, etc.)
- f. What is the market price of such an apartment in conventional building and what is its costprice. Please give breakdown.
- g. As far as possible, give components of usual calculation. Every detail is important to us.
- h. Are there a power station or power lines available at the building site or at the plant, supplying power and light. The same as regards the supply of water. Prices and conditions.
- i. Taxes
- (1) What are the usual taxes on building, such as building taxes, water, canalization etc.
- (2) Company taxes, rates, reductions, etc.
- j. Usual depreciation on equipment, buildings, etc.
- k. Usual financing conditions, sources of credit, terms of payment, etc.
- l. Possible additional expenses, such as connection to the electricity supply, business tax, etc.

The requested information is essential so that we may reply in detail on all questions connected with the subject and prepare estimates and calculations .

We shall be most grateful for every other/detail, and are looking forward to your early reply.

אסמית ובנויות 65.72.72.72

ביתקו ובנויות בבאר

אסמית 98 אסמית 2 אסמית 2 אסמית 2

	34	6800x2900x160	T3	1A	אסמית
	35	" " "	T4	1B	"
	25	8600x2530x140	R8	2A	"
	31	6620(2526)x160	TM	2B	"
	14	5455x2530x200	G3	3A	"
	18	5455x2530x200	G4	3B	"
	24	5660x2530x20	G5	4A	"
אסמית 36 אסמית 36			G1	4B	"
	39	6800x2900x160	T6	5A	"
	40	" " "	T5	5B	"
	32	6100x2900x160	T1	6A	"
	42	6100x2900x160	T2	6B	"
9 2565x2530x160 RII ±	7	5880x2530x140	R III	7A	"
7 1500 Se אסמית ±	22	8800x1500x2530x140	R7	7B	"
8 4250x2530 R9 ±	13A	3740x2530x140	R10	8A	"
3740x2530x140 R12 ±	16	4250x2530x140	R13	8B	"
17 (10 R14) ±	11	7995x2530x140	R4	9A	"
±	13	7995x2530x140	R5	9B	"
	19	5880x2530x140	R6	10A	"
		8000x2530x140		10B	"
	1	9700x2530x200	R1	11A	"
	4	9700x2530x140	R2	11B	"
	33	8000x2900x160	T8	12A	"
	41	8000x2900x160	T9	12B	"

12/10 (v) 1/1



07 01 01

2

מזכר

As other half
4-1-68 - In house
and all other
part of it is left
to be sold for
part of it to be
as also what
more will be
house & land) to be sold
and if (part of it

15.7.70

סוף שנה
מחירי
מטבע

אף על פי שער, ואף בדיקתו של
מאמץ מרובץ 3/3 סוף

העברת אמצעים של יוצר ש. לבית מילן 4.1.1968

הנני להסב גמולת אפר אהלה הבאה:

1. אסתר ב' - גמולת 300,000 מניא גמולת 300,000 - לא שולמו כל כספים

2. אסתר ד' - היתרה בת 300,000 ע"י היא יתרה
צומצם יש אהבה גמולת איצילת הקאנט
שמיציע אקולה אל התאך המוצר אמורה

3. אסתר ה' - העברת אל הילוצ האמריקאי קם
היא צומצם אפילו של מ' ת' שזין
(באה גמולת נפירה בניצול)

4. אסתר ז' - אפי מיט יצילת אפי מיט יצילת של
יוצר ש. לבית אל נקודה גמולת שבו של
מ' ת' שזין, אפי כל אלא לא בריא.

כל שזין ממילן אל סילם בור - בדיקת
העברת אקולה, ואני רשאי אפרם באלף היפוטתו

כי מ' שזין אל אלה שם מילצם
בשאל - 10,000 ע"י להוצא ממילן אלה מילצם

אל שולל את תכונתו לחברה בשאל כח
אני מניע להסיל אל וצד אקולה גמולת

הפדום נהיה גמולת אשיר הידיקטאניו מ' 3.
5. אסתר ח' - האם שם התבונן והפיקה אל אקולה
הנמח המפח עד 1.4.65 שולמו אל מ' ת' שזין
אל נקרה אפילו ?

אני מניע שבאה התבונן יבין פכיל כל יתרה העברת
הצומצם אפילו של מ' ת' שזין. המנעל.
אני מניע אקולה מ' 3 אל שבו של המנעל.

3/3 סוף

כספי ושות'
עורכי-דין ונוטריונים
CASPI & Co.

BARRISTERS-AT-LAW, ADVOCATES & NOTARIES

MICHAEL CASPI	מיכאל כספי
SHLOMO LEVRON	שלמה לברון
RAM CASPI	רם כספי
CHAIM GLASER	חיים גלזר
CHAIM ADINI	חיים עדיני
DAVID COHEN	דוד כהן
MOSHE WAGNER	משה וגנר
ZVI HARTAL	צבי הרטל
MOSHE NISSIM	משה נסים
ZVI RAPAPORT	צבי ראפפורט
RAANAN RON	רנן רון
AMARON BAVARSKY	אמרון בברסקי
ISRAEL S. KANTOR	ישראל ז. קנטור

TEL-AVIV	תל-אביב
SHALOM TOWER	מגדל שלום
ACHAD HA'AM ST. 9	רח' אחד העם 9
PHONES: 57137-57138-57139	טלפונים:
CABLES: SHAKSPEARS TEL-AVIV	
JERUSALEM	ירושלים
BEN YEHUDA ST. 12	רח' בן-יהודה 12
TELEPHONE 26634	טלפון
HAIFA	חיפה
NORDAU ST. 9	רח' נורדאו 9
TELEPHONE 40980-40989	טלפון

תל-אביב, 4 בינואר 1968.

מספרנו: ס/לב/יפ. 140/Our Ref.

לכבוד
מר הלל אשכנזי,
סמנכ"ל משרד השיכון,
הקריה, תל-אביב.
א.נ.,

הנדון: "שכח" חברה לייצור בתים להרכבה בע"מ

על פי בקשתך הנני להביא בפניך תמצית זכויותיו של המהנדס חיים סלבין הן מכה כתב ההסכם היסודי שנחתם בזמנו בין המדינה לבינו והן מכה עבודותיו עבור החברה וכלל שרותו במפעל.

א. על פי סעיף 17 (1) (א) מן ההסכם היסודי, זכאי מר סלבין לקבלת 10% מהון מניותיה הרשום של החברה ללא תשלום כסף על ידו, בתורת תמלוג חד פעמי, דהיינו 400,000 מניות רגילות בנות 1 ל"י כ"א.

ב. מר סלבין השתמש באופציה שניתנה לו בסעיף 7 (1) מן ההסכם לרכוש מניות נוספות בשיעור 15% מהון המניות הרשום, כלומר 600,000 מניות רגילות בנות 1 ל"י כל אחת. כתמורה עבור רכישת המניות ישמשו זכויותיו של מר סלבין בעד הציוד והמכונות שהעביר לבעלות החברה.

ג. עד כה הוקצו על ידי החברה 700,000 מניות לזכות מר סלבין (מחציתן לשמו של אמנון סלבין בחוקף העברה מאביו).

ד. בחוקף סעיף 3 (5) מן ההסכם ותקנה 71 (4) לתקנות החברה, זכאי מר סלבין לייצוג יחסי במועצת המנהלים לפי חלקו בהון המניות.

ה. בהתאם לסעיף 9 (א) מההסכם בוצעה הערכת שוויין של המכונות ושל הציוד שנבנו על ידי מר סלבין עד ליום 1.4.65, הוא היום בו נפתחו פנקסי החברה.

בישיבת ההנהלה מיום 3.1.65 נקבעו ההנחיות בדבר קביעת שוויין של המכונות והציוד האמורים, וועדת ההערכה פעלה על פיהן.

הועדה קבעה כי הערך הממשי לפי מחירי השוק הוא סך 1,147,000 ל"י.

מאידך עלתה בניית המכונות והציוד לפי רישומיו של מר סלבין בסכום קטן יותר, דהיינו סך 770,000 ל"י.

נוצרה איפוא יתרה לזכות בסך 377,000 ל"י.

שלגביה שמורה זכותו של מר סלבין לתבוע את השלומה מחוץ רווחי החברה לכשיווצרו.

אל: מר הלל אשכנזי.

ה.

ביחס לציוד האמריקאי שנרכש בזמנו על ידי מר סלבין, נעשתה הערכת שוויו עוד בחודש מאי 1962 על ידי המכון לפיריון עבודה, ולכן ועדה השלושה שוחררה מהתפקיד לבצע הערכה חדשה.

ההערכה משנת 1962 מסתכמת בסך -169,296 ל"י. לעומת הסך -197,400 ל"י שנדרש אותו זמן על ידי מר סלבין.

בהקשר זה יש להזכיר את החלטת ההנהלה מיום 3.1.65 כי כל הציוד והמכונות שנרכשו על ידי מר סלבין בחו"ל יועברו לבעלות החברה במחירי רכישתם.

יחד עם זאת תובע מר סלבין תוספת שווי בגלל פיתוח הלירה שנעשה בפברואר 1962.

בתוקף הסעיף 17 (1) (ב) ו-(ג) מן ההסכם, זכאי מר סלבין לתמלוגים עבור השימוש בשיטתו, והם בשיעור של 2% מכלל המכירות של הציוד ובשיעור של 15% מהרווח נטו כפי שהוגדר שם.

על פי האמור בסעיף 22 מן ההסכם חייבת החברה להעסיק את מר סלבין בתפקיד מנהל המפעל במשך תקופה של 5 שנים מיום הפעלתו של המפעל, תמורת שכר בשעור המקובל במפעלים ממשלתיים או צבוריים בהיקף דומה.

בהחלטת ההנהלה מתאריך 3.1.65 נקבע כי מר סלבין יקבל שכר היכנון ושכר פיקוח בגין העבודות הבאות: הכשרה ופיתוח של המגרש ברמלה, עבודות הבנייה שבוצעו עד יום 1.4.65.

מאחר וביחס לתקופה שלאחר 1.4.65 טרם נקבע כל הסדר כספי עם מר סלבין, החליטה ההנהלה בישיבתה מיום 27.3.66 לשלם לו סכום כולל אחד פעמי של -30,000 ל"י על חשבון כלל שירותיו לחברה מאז 1.4.65.

כפי שתיווכח מקריאת הסקירה דלעיל, נמנעתי מהבעת דעה כל שהיא בדבר איכותן או שוויון הכספי של הזכויות אותן פירטתי, ואולם אהיה נכון לעשות זאת אם אדרש.

בכבוד רב,

ש. לברון, עו"ד,
כספי ושות'

החלטה זו נלקחה
אנא לא לה
הצד האמריקאי

2

1.

2.

החלטה זו
אנא לא לה
הצד האמריקאי

יין אפיקר



(לתבות פנימית במשרדי הממשלה)

יִמְזַכֵּר

אל	תאריך
מאת	מספר
הנדון:	

[illegible]

3

(לתכתובת פנימית במשרדי הממשלה)

מזכר

אל	תאריך
מאת	מספר
הנדון:	

שילוב אל מחסן
המחסן כ שם
מ. סלמי יא. 25-9
מחסן 3000

2022
2/1



12.7.1970
מס' 26
מס' 27
מס' 28

10107

א"מ ד. אלפרזי, יו"ר ציוראקאיון "לש"מ"
מחלקת מנהל צדק סכנה.

הקדמה: ציבורי צדק הציור האמריקאי

לפני שנים רבות התחלתי להעריך את חשיבותו של הציור האמריקאי, ובעיקר את חשיבותו של הציור האמריקאי - להבין את חשיבותו.

1. הנני מתפלל מאד שמשך כל השנים לא הספיקו לנו להבין את חשיבותו של הציור האמריקאי, ובכל זאת התחלנו להבין את חשיבותו. 1965 הוציא הנשיא מילטון אידלסון (הנשיא) את הספר "הציור האמריקאי" ובו תיאר את חשיבותו של הציור האמריקאי.
2. בישיבה זו התחלתי לכתוב את הספר "הציור האמריקאי" ובו תיאר את חשיבותו של הציור האמריקאי.

ביתאם להחליטה זו נקבעה וצדק שלמה (אוצר ישראלי) שנקבעה את מחזורי הציור האמריקאי. וצדק זו לא התחלתי להבין את חשיבותו של הציור האמריקאי, אך כן התחלתי להבין את חשיבותו של הציור האמריקאי. 1965 הוציא הנשיא מילטון אידלסון (הנשיא) את הספר "הציור האמריקאי" ובו תיאר את חשיבותו של הציור האמריקאי.


3. הוציא מילטון אידלסון את הספר "הציור האמריקאי" ובו תיאר את חשיבותו של הציור האמריקאי. 1962 הוציא הנשיא מילטון אידלסון (הנשיא) את הספר "הציור האמריקאי" ובו תיאר את חשיבותו של הציור האמריקאי.

4. הן וצדק ישראלי וכן הוציא הנשיא מילטון אידלסון (הנשיא) את הספר "הציור האמריקאי" ובו תיאר את חשיבותו של הציור האמריקאי.

א. אני מניח שהיו תלמידי ציור אצל מר שטיין אצל נחמן העצמאי המכון לפריון (הוציא) (169,296 ע"י) כמקובל בציור האמריקאי מר שטיין (197,400 ע"י). ב. כמקובל בציור האמריקאי 1965 היה חלק הציור במחלקת בתי-שמש ומחלקת אפסאן גרנטאלר.

ג. האם כל הציור הנ"ל היה בראש באתר לציור האמריקאי? האם הוא בא מי-פזם ישראלי שמוציא את המציאות? 3. מה היה מצבו של הציור בציור 1965. מתוך מחקריי לא נמצא לידיעתי על הציור האמריקאי.





אם בקורה ברורה, כן שנים עם קנה מאתר
 לבדוק אם מצב התשלומים.

9. פאר הסתירה שהובאה אליה - אינני יכול להצביע

אך קשה להעביר לא א' א' א'
 מאתר ואם ניתן ביום להקצות למספרות ואם מאתר
 מאתר בשנת 1965 - אינני באה מאלו מאתר

לאחר את התאריך התקפה מיום 3.1.1965 ולפני אפי'
 גרן וביצור שמאמרים מנהלים המבין לפיכך העבודה.

10. מר שלזין תאריך ג'סטר שלי בקשה פיתוח פס'
 שרשרת בפברואר 1962 (יאה מכתבם שלעצמם מיום 4.1.1968)
 מאתר והציוץ כבד היה אף ברמה המפא

למאמר ומצאיר אף ממור הרכשה, וברור שמחיר הרכשה
 אף השתנה מאתר ~~ה~~ והרכשה נאמנה לפני פברואר
 1962 - אינני באה אף בסיס שיצדוק אף

תביאנו לא של מר שלזין.
 11. אני מניח אף הידיעה לניין אפי'ם אף הידיין בקויה
 בהקצם ולהביא פניה לא אילו סיום מיו.

בבוא 2

בבוא יורה

לשפטים

1. הליכה המבין לפיכך העבודה.
2. ב'ה' וצדק ישר (וצדק השלשה).
3. פהסבא ישרה מוצג המנהלים מיום 3.1.1965
4. מצב התשלום עם מר שלזין מיום 15.1.68

מדינת ישראל

15/5/62 התאריך

תיק מס'

אל: אליה - משרד הביטחון
מסמך: 3170 - המחקר הפסיכיאטרי

הנדק: מימל סלחין

ר"ם פוסט התיבה של חב"ד
הקונסולר/ג'נרל רבין שלביל אילנה

הברכה ה

א



דו"ח על הערכת ציוד במפעל סלבין

1

דו"ח מכון

בר"מ

מחיר נדרש	שווי סופר	ביסוס הערכה
11.300.-	11.776.-	הערכה בעשתה על 50% שווי של מאזניים חדשות 3x6000 לי א 50% 9.000.- חומר לקונסטרוקציה כפי שנרשם ע"י מר סלבין ונראה לנו סביר 600.- מספר שעות עבודה שהושקעו בקונסטרוקציה בתקבלו מרשומי מר סלבין אולם ערך יום עבודה של פועל בבית המלאכה הועלה ל-32 לי במקום 25 לי ליום (32x68)
3.000.-	720.-	הערכה בעשתה על בסיס "ערך גרוטאות" כדלקמן: 4 צמיגים בערך 80% מ 80.- לי (2 צמיגים נוספים בערך 0) חלקים לאחר פירוק (שילדה, תיבת הילוכים וכו')
60.000.-	54.000.-	מחיר מכונה חדשה - 180.000 לי "סיפ", ערך הקיימת הוערך ב-30% לרגל התישנות ואורך חיים כלכלי
6.300.-	7.000.-	הקונוייר הנו חדש ושווי הוערך לפי מחיר השוק כיום
36.000.-	25.000.-	ערך בשוק (המנוף מסוגל להרמת 12-15 טון מקסימום ולא 30 כפי שמצויין)
8.000.-	7.000.-	לפי אורך חיים כלכלי כ-50% מכלי חדש כיום וערך צמיגים 20%
15.000.-	10.000.-	מודל 1943 הוערך לפי שווי חלקים: 10 צמיגים א 40% מנוע שילדה וחלקים
20.000.-	16.000.-	מחיר בשוק
27.000.-	27.000.-	מחיר בשוק (הגברטור לא יפיק 250 קו"א אלא עד 180 קו"א הבחונים הסבניים המצויינים במיפרט אינם מדוייקים)
2.000.-	2.500.-	מחיר בשוק
1.500.-	1.000.-	המשאבה דורשת שיפוץ
6.000.-	6.000.-	מחיר בשוק
1.000.-	1.000.-	מחיר בשוק
300.-	300.-	מחיר בשוק
197.400.-	169.296.-	
	28.104.-	
	197.400.-	

3

מרכז לשקילת אגרגטים

4

אוסר משא עם הופך הידראולי
להספקת התערובת למכונת הבטון

1

מכונת בטון נוסעת משומשת 2x1 מ/3
(הוא צד צד)

2

קונוייר הספקת בטון למשפך
ויברציוני חדש

6

מנוף על גלגלי גומי "לורייין" M/M
(הוא צד צד)

5

מזלג קלרק מסומס, 2 טון

7

אוסר משא דיאמונט, משומש
(הוא צד צד)

8

2 טריילרים, 40 טון, משומשים

11

דיזל גברטור
(הוא צד צד)

14

לוח השמל לחלוקה ראשית 200 קו"א

13

משאבת ואקום 15 כ"ס

47

דקוביל 500 מ' כולל אדנים

50

מכונת בטון 200 ליטר, משומשת

59

פטיש לנסוי בטון

ס ה " כ

הפרש לחובת הערכת סלבין בציוד

ב. קונסטרוקציות וחלקי ציוד בייצור עצמי

הערכות אלה מבוססות על נתוני חומרים כפי שנרשמו ע"י מר סלבין (הנחיות משרד השיכון) אולם שכר עבודה לשעה נקבע על ידנו ל-4. במקום -3 ל של מר סלבין כפי שהוגש ברשימה ו-5.40 ל כפי שתבע מאוחר יותר.

מס. סדר	מס. ברשימה	פ י ס י ס	מחיר נדרש	שווי מוערך
1	29	מסדר הספקת אגרגטים למרכז השקילה	22.000.-	23.968.-
2	19	משפך ויברציוני	19.000.-	20.392.-
3	18	תבנית ויברציונית	41.500.-	50.632.-
4	24	גוף הפוגות	2.800.-	3.464.-
5	34	מסדר פנומתי	9.400.-	10.944.-
6	35	צילינדרים אויר (רק חומרים)	3.500.-	3.500.-
7	30	עגלות החללים	11.700.-	14.092.-
8	20	תבנית יציקה לקיר	6.700.-	7.940.-
9	31	עגלות חללים	6.000.-	6.884.-
10	32	עגלה	5.800.-	7.068.-
11	22,32,38	תבנית למחיצות	6.000.-	7.084.-
12	21,23,36,39	חלקים לבנין תבניות (רק חומר)	10.800.-	10.800.-
13	16,33	מסדר השחזה	5.000.-	5.228.-
14	9	מנוף ייצור	12.300.-	14.300.-
15	45,46	מנוף הקמה (רק חומר)	5.000.-	5.000.-
16	44,51,58	מנופי סיבוב (רק חומר)	3.200.-	3.200.-
17	12	2 ברכות לקיסור חימום (אין פירוט על עבודה)	2.000.-	2.000.-
18	26	פרס הידרולי	2.200.-	2.424.-
19	28	שולחן סכיבים	2.400.-	2.888.-
			177.300.-	201.808.-

24.508.-

201.808.-

=====

הפרש לטובת סלבין לרגל העלאת מחיר שעה ל-4 ל מבלי לבדוק את החומרים

<u>מחיר נדרש</u>	<u>פריטים שלא הוערכו על ידנו</u>	<u>מס. ברשימה</u>
6.000.-	מנוף מונורייל מפורק 2 אטון (אין פרטים)	10
15.000.-	שרטוטנים	-
5.600.-	4 מזיזים להנעת ויברטורים	15
500.-	מכשיר לייצור גופיפוגות	25
1.200.-	מכשירים שונים	48,60
2.500.-	מכשירים לבנין מכונות טכנולוגיות	53,54,57,57
4.000.-	חלקי מכונות טכנולוגיות	40,41,43,52
2.000.-	ייצולים שונים	27
1.600.-	חומרים	49
38.400.-		
=====		

ג. ריכוז

<u>ה פ ר ש</u>	<u>לחובת סלבין לזכות סלבי</u>	<u>שווי מוערך</u>	<u>דרישת סלבין</u>	
.-	28.104.-	169.296.-	197.400.-	א. ציוד
24.508.-	-	201.808.-	177.300.-	* ב. קונסטרוקציות
-	-	-	38.400.-	ג. פריטים שלא הוערכו
			413.100.-	
			=====	

* בסעיף זה לא נעשו בדיקות אלא קביעת מחיר שעת עבודה בלבד.
ההערכה כולה לא כוללת בדיקה על הצורך בכל הפריטים הנ"ל למפעל.

במקרה של היעדר אמצעי תשלום 25000 ₪

2

דין וחשבון של ועדה לענין קביעת בסיס לתחשיבי מחירי הציוד
למפעל "שבח" ליצור בתים טרומיים.

הרכב הועדה

הועדה הוקמה והרכבה נקבע בהחלט לסעיף 9 של החוזה בין ממשלת ישראל המיוצגת ע"י משרד השכון ובין מר חיים סלבין מיום 30.4.1964.

מר ח. סלבין, ששחתף בועדה באופן אישי
מר מ. יבניאלי מונה ע"י משרד השכון
מר ש. ישי מונה ע"י מנהל מכון התקנים.

תפקידים

בהתחשב בסוג הציוד שהוכנן ונבנה ע"י מר סלבין, אופיו המיוחד, הגורמים הקשורים בפתוחו, העובדה שלא קיימים פריטי-ציוד דומים אשר ניתן להשוותו אתם וכן בהתחשב בצורת התייעוד המתיחס לייצורו של הציוד הנ"ל, לא ראתה הועדה כאפשרי לקבוע בצורה חד-משמעית את שוים של פריטי הציוד כמבוקש בסעיף 9 של החוזה בין הממשלה ומר סלבין מיום 30.4.1964 ובסעיף (א)-2-א של הפרטי-כל מישיבת מועצה מנהלים של "שבח" מיום 3.1.1965.

הועדה הצטמצמה איפוא בעבודתה לתפקידים כדלקמן כמבוקש במסמכים הנ"ל :

(א) קביעת דמי שמוש בשרותי בית המלאכה והציוד הפרטי של מר סלבין
בחקופה 31.3.1965 - 1.4.1960.

(ב) קביעת גובה דמי חכנון ופקוח מקצועי על ייצור הציוד הנ"ל בחקופה דלעיל;

(ג) קביעת ערך שעה עבודה אקויוולנטית עבור עבודות מחכת דומות בהנחה של בצוע קבלני
בתנאי "רג"י."

מסקנות

(א) דמי שמוש בשירותי בית מלאכה והציוד המותקן בו

חברי הועדה בקרו בבית המלאכה של מר סלבין בצריפין וסקרו את הציוד המותקן ואת השרותים המצויים בו. הועדה סומכת את ידיה על האומדן הבסיסי של דמי שמוש שנתיים בשרותים הנ"ל המבוססים על ערך הציוד בתנאים של היום ודמי השכרה מקובלים בתעשיה בסך 44,500 ל"י (כמפורט בנספח א'). בהתחשב בערך הבסיסי הנ"ל, בשנזויים שחלו במחירים במשך החקופה 1960-1965 ובטדה הנזול של בית המלאכה בשנים הנ"ל נראים המספרים הניהנים בנספח א' כסבירים והועדה מאשרת את הסכום הכולל של 142,000 ל"י במשך 5 השנים הנ"ל המופיע בסיוטת הסיכום של החשבונות "שבח" - סלבין (נספח למכתבו של אברהם עקביה מיום 9.6.1965).

ל. א. ל. ב.

2

(ב) דמי תכנון ופקוח מקצועי

הועדה קבלה את ההנחה שהעבודה אשר נעשתה ע"י מר סלבין עד 1960 ושעבודה קבל תמורה בשותפות בחברת "שבת" כללה קביעה כללית של הטכנולוגיה, עבודות פיתוח ונסוי לשם קביעת סוגים וגודל של הציוד המכני, עבוד הנחונים הבסיסיים האלה, ותכנון כללי של בית החרושה. התכנון המפרט של הציוד אשר נבנה ע"י מר סלבין במשך השנים 1960-1965 נעשה במקביל עם ייצורו. במשך החקופה הנ"ל הכין מר סלבין שרטוטי-עבודה, תרשימים, פיקח על הבצוע מנקודה ראות טכנית וגם ניהל את עבודות הייצור (דבר אשר אינו נכלל כרגיל בשרותים הניתנים ע"י מהנדס מתכנן-מבצע).

נהוג לבטא את דמי התכנון והפקוח המקצועי באחוזים של ערך ההוצאה הכוללת לייצור של הציוד (חמרים, רכש של חלקי ציוד מכני הנכללים בציוד הנבנה, שכר עבודה, שכירת שרותים וציוד עבודה). האחוזים הנ"ל נקבעים כרגיל בהתחשב במדה הסבון של הציוד, מספר האלמנטים החוזרים והמשקל של האלמנטים הנבנים במיוחד לעומת חלקים סטנדרטיים הנרכשים והנכללים בבניחו.

אם-כי לא ניתן עתה לערוך בדיקה מדוקדקת של הגורמים הנ"ל, נלקחו הגורמים האלה באופן כללי בחשבון ע"י הועדה בקביעת התמורה הנאותה המגיעה למר סלבין עבור שרותי התכנון המפרט, הפקוח והנהול כנ"ל. הועדה הגיעה למסקנה שהתמורה הנ"ל צריכה להיות בסדר גודל של 10%, היינו (בהתבסס על סיכום החשבונות המופיעים בדו"ח אברהם עקביה מיום 9.6.1965):

שכר עבודה 1960/1	628,077 ל"י
ציוד וחמרים בחקופה הנ"ל	658,264 "
שכירות בית-מלאכה וציוד	142,000 "
	1,428,341 ל"י

10% מהסך הנ"ל : 142,834 ל"י לעומת הסך 114,258 ל"י המופיעים בסכום של אברהם עקביה והמבוססים על המורה בסך 8% מערך הציוד בהתאם לחשבונות של מר סלבין. (הערה : המספרים דלעיל הם לפני בקורה, כפי שצוין על ידי אברהם עקביה בסיכומו הנ"ל).

התמורה כנ"ל בגובה של 10% מבוססת על ההוצאות למעשה לבנית הציוד כמוסבר לעיל חוץ הנחה שבצוע עבודות ייצור בהתאם לתכנון של מר סלבין הושלמו ברובן, כמפורט בנספח ב". הועדה לא ראתה מתפקידה לבדוק אם ובאיזו מדה יהיה צורך בעבודות השלמה ו/או שנויים ומה עלול להיות היקף עבודות התכנון הקשורות בכך.

אין איפוא ליחס את קביעת התכנון ופקוח כנ"ל למדה השלמה הציוד ואין לראות בקביעות הועדה הבעת דעה כל שהיא ביחס לסעיף 10א" של החוזה המכתיב שהציוד צריך להמסר לחברה ע"י הממציא "במצב טוב ותקין וראוי לשמוש מירי".

(ג) חשיבים המבוססים על הנחה של בצוע ע"י קבלני-חוז

(1) עבודות בתנאי "רג"י" (ז.א. על בסיס של שכר לשעה עבודה של קבלן) מבוצעות כיום לרוב רק במקרים של עבודות בהיקף קטן שקשה להגדירן מראש ובמקרים של השלמות ושנויים. עבודות בהיקף רחב מבוצעות לרוב על בסיס קבלני ולא על בסיס של השלום לפי שעה.

(2) המחירים עבור עבודות מחכת בתנאי "רג"י" כנ"ל נעים בגבולות רחבים. בו בזמן שמפעלי המחכת הגדולים מחשבים כיום עד 10 ל"י עבור שעה עבודה, אפשר לבצע עבודות בבחי מלאכה קטנים בטיב שווה ובמחירים של 5-6 ל"י לשעה.

[Handwritten signature and initials]

(3) בהתחשב בכך שלא כל העבודות היו מחייבות בצו ע"י מפעלים גדולים ושחלק ניכר מהן אפשר היה לבצע בבחי מלאכה בינוניים וקטנים, קבלה הועדה כמחיר ממוצע בתנאי היום את המחיר של 7.50 ל לשעת עבודה. ברם, מחיר זה מתחם לעבודות בלתי רצופות בהיקף מוגבל. בהתחשב בהיקף העבודות ורציפותן, סביר להניח שהמחיר היה לפחות 10 אחוז יותר נמוך, היינו 6.75 ל בתנאים של היום.

בהתאם לכך ובהתחשב בהתיקרויות שחלו בסך 5 השנים האחרונות, בסמך הועדה את תחשיביה על המספרים כדלקמן:

1960/1961	4.30 ל לשעה
1961/1962	" " 4.50
1962/1963	" " 4.95
1963/1964	" " 5.65
1964/1965	" " 6.75

(4) בהסתמכו על המספרים המופיעים בחשבוניות שהוגשו על ידו, הביע מר סלביץ בדיוני הועדה את הדעה שבמקרה של בצו העבודות ע"י קבלן, חלק מעבודות ההכנה והשרותים הבלתי ישירים שלא סווגו על ידו כ"שעות קבלנותיות" היה נרשם ע"י הקבלן כשעות קבלנות ישירות והיה נדרש עבורן תשלום.


לעומת זאת כולל מחיר שעת-רג"י במקרה של בצו ע"י קבלן הוצאות נהול עבודה, אשר התמורה עבורן במקרה של מר סלביץ נכללה בסך של 142,834 ל המומלץ ע"י הועדה בסעיף (ב) דלעיל. כמו-כן כולל המחיר של קבלני-חוץ הוצאות מימון, אשר לא היו למר סלביץ.


לדעת הועדה מאזנים שני הגורמים האלה.


בהתחשב בהנ"ל החליטה הועדה לבסס את תחשיבי ההשוואה על ההנחה שמספר שעות העבודה המושקע ע"י הקבלן היה שווה למספר שעות העבודה ה"קבלנותיות" המופיע ברשומים של מר סלביץ.

(5) התחשיבים למקרה של בצו ע"י קבלני-חוץ והשוואתם עם מחירי הבצוע לפי הרשומים של מר סלביץ ניתנים בנספחים ג' ו-ד.

ההפרש לזכותו של מ. סלביץ בין הסך 1,147,000 ל המתקבל כנ"ל ובין 770,000 ל המבוטס על הרשומים של מר סלביץ עבור בצו העבודה חוץ שמוס בבית המלאכה שלו הוא 377,700 ל ובהתאם לסעיף (א)-3 של הפרט-כל של ישיבת מועצת המנהלים של "שבת" מיום 3.1.1965 שמורה למר סלביץ הזכות לתבוע תשלום ההפרש הנ"ל מתוך רוחיה של החברה בעת שרוחיה כאלה ייוצרו.


 ש. ישי
 מהנדס
 רחוב מרכזי 15
 תל-גנים, רמת-גן


 מ. יבטיאלי
 מהנדס
 רחוב פייכמן 13
 תל-אביב


 ח. סלביץ
 מהנדס
 רחוב פרישמן 43
 תל-אביב

2 בספטמבר, 1965.



נספח א*

תיאור הציוד ובתי המלאכה של מר סלבין
וקביעת דמי השימוש עבורם

הערה : דמי השימוש אינם כוללים הוצאות אחזקה שוטפות ותיקונים.

דמי שימוש שנתיים בסיסיים

תיאור הציוד

10,000 ל"י	22,000 "	3,000 "	1,000 "	6,000 "	2,500 "
<u>1.0 בית מלאכה מכני</u>					
שטח 500 מ"ר גובה עד 6 מ"ר					
חיבורי חשמל עד 200 אמפר					
חיבורי מים 3"					
מחסן סגור בבית המלאכה					
<u>2.0 עגורן שער 10 טון</u>					
כושר הרמה 10 טון					
רוחב 11.5 מטר					
גובה הרמה 6 מטר					
אורך נסיעה 300 מטר					
הפטים מבוססים על קורות בטון					
וקלונסאות ביסוס כל 3 מטר					
<u>3.0 מעמד להרכבת תבניות</u>					
תא בנוי מבטון בעומק 1.8 מטר					
וברוחב 11 מטר ביסוס לתבניות					
ואספקה אויר וחשמל					
<u>3.0 משרד-מחסן</u>					
מבנה בנוי מבטון 6 יומי					
<u>4.0 ציוד מכני</u>					
4.1 3 מחרטות					
4.2 4 מקדחות					
4.3 1 משור מתכת מכני					
4.4 1 מקצוע (שפינג)					
4.5 3 מקדחות עם בסיס מגנטי 3/4", 1", 1 1/4"					
4.6 1 מכונה ליטוש					
4.7 ציוד עזר					
<u>5.0 20 טרנספורמטורים לריחוף</u>					
הכמות מהיחסת לשנתיים האחרונות. בחישוב					
דמי השימוש נלקחו בחשבון 50% ממספר זה					
כממוצע לכל החקופה.					

[Handwritten signatures and initials]

נספח א' (המשך)

6.0 גנרטורים לריחוק

250 אמפר	1 דיזל גנרטור	6.1
" 400	1 גנרטור	6.2
" 300	1 גנרטור	6.3
" 250	1 גנרטור	6.4

גם כאן נהוגה ההמונה של השימוש בציוד בשנתונים האחרונות.

בחשוב דמי השימוש נלקחו בחשבון 50% ממספר זה כממוצע לכל החקופה

3,000 ל"י

7.0 מכשירי עבודה שונים

כלי-יד
עגלוח טרנספורט
מכשירי ריהוך אוטוגנים
מכשירי הידראולי-יד 50 טון
מדחס אויר
מנופי יד

2,000 "

8.0 סיכום

סה"ד דמי שימוש בסיסיים לשנה

49,500 ל"י

בהתחשב בגורמים המפורטים ל 5.6
הגענו לחיוב ממשי עבור השימוש בבתי המלאכה ובציוד כדלקמן :

ערך החיוב ל	השנה
12,000 ל"י	1. 1960/1961
" 24,000	2. 1961/1962
" 36,000	3. 1962/1963
" 42,000	4. 1963/1964
" 28,000	5. 1964/1965 (עבור הציוד הסכנולוגי בלבד)
<u>142,000</u> "	סה"כ

Handwritten signature and initials

פירוט הציוד הטכנולוגי

כללי

רצופה למטה רשימה, כפי שנמסרה ע"י מר סלבין, של הציוד השייך לחהליך הטכנולוגי ושיועבר למפעל במקומו החדש.

הרשימה והערות לרשימה נכונים לתאריך 1.4.1965.

ברשימה זו נכלל ציוד שנבנה ע"י מר סלבין, כולל חלקים שנרכשו מוכנים וכן ציוד שנקנה לפני 1960 ושיוצא למפעל החדש.

ההערות בסוף כל סעיף ביחס למדת הגמר של הציוד ליום 1.4.1965 מחיטות למצב הבצוע המבוסס על חכוננו של מר סלבין. אין לראות בהן נסיון של הבעת דעה אם ובאיזו מדה מוכן הציוד להרצה או להפעול סדיר, אם יהיה צורך בעבודות השלמה או שנויים ומה יהיה היקפן.

1.0 מחלקת יציקה

1.1	חבניות רצפה	2 קומפ"
1.2	" קירות רוחב + רצפת מדרגות	" 2
1.3	" קיר חוץ מונוליטי + רצפה	" 1
1.4	" קירות מחוללים כולל סידורי הפעלת	" 1
	גרעינים	" 1
1.5	" מחיצות 4 גופים	" 1
1.6	" תא סניטרי 4 מחיצות	" 1

התכנית כוללת : ביסוס, מערכת קפיצים, מסגרת חוץ עם הבסיס, החחיות גוף ביניים עם קונוסים, 2 גופי הזזה, צינורות הזזה עם החלקה עליונה והחתונה, סגרי אורך, גופי פוגות, קשרי מסדרים פניאומטיים, מסדרים הידראולים, קובעי גופי הזזה ליציקה, פינים ומסגרות, מערכת קבלה וקביעה של המשפך הויברציוני, סידור חימום בקיסור וסידורי ניקוז מי קונזסט, סידור רחיצה לחץ נמוך וגבוה, סידורים לויברציה ע"י אויר דחוס, מעברים ממשפך ויברציוני, סידורי הפרדת המשפך בגמר היציקה, סגרי גמישות גופי הזזה.

1.7 ברכת רחיצה עם משאבה "3 6 אט" עם מסננים וכיסוי

1.8 דוד קיסור 1 טונה לשעה, ברכות להורדת לחץ לאינסטלציה

1.9 ברכת סולר 10 מ"ק

1.10 3 מערכות ברכות ניקוז עם משאבות למי קונזסט.

הערות : (1) 4 מחוך התכניות המוזכרות למעלה גמורות. עבור ארבעה הנותנים חומר אולם יש להשקיע בהן עוד כ-50% עבודה.

(2) ישנם 6 גופי פוגות מוכנים. שאר השניים יש לבנות.

Handwritten signature and initials at the bottom left corner.

נספח ב' (המשך)

2.0 ויברציה

2.1	2	ויברטורים חשמליים	40 כו"ס
2.2	2	" "	30 "
2.3	2	" "	5 "
2.4	4	בא"ר עם סידורי קשירה להבניה	
2.5	1	משפך ויברציוני עם מערכת קשירה להבניה וסידורי קבלה ל-4 ויברטורים חשמליים.	

3.0 פניאומטיקה

3.1	8 קומפ"	כ"א להפעלה 10 צילנדרים אויר באורך 25 ס"מ
3.2	2 קומפ"	כ"א להפעלה 20 " " " 25 ס"מ

כל קומפלט בנוי ממסגרת עליונה וחחתונה, 2 מערכות הזזה ו-10 מקומות קביעה לצילנדרים האויר וכן מערכת צנורות וברזים להפעלה הצילנדרים.

- הערות :
1. בנוי 50% מס"ה הצילנדרים הדרושים
 2. הצנרת נדרזים להפעלה עדין חסרים.

4.0 מסדר אגרגטים

4.1 מסדר אגרגטים מס" 1 הבנוי עם 3 מאזנים של 1 מ"ק כל אחד עם נפות. 2 סילוסים + 2 קונביירים הנוסעים על פסי ברזל.

סילו למלט עם חלזון מזון.

4.2 מסדר אגרגטים מס" 2 - כולל מיכל קבלה, קונבייר ראשי, קונבייר עזר ונפה.

4.3 מאזני גשר לשקילה 40 טון (בחזמנה).

4.4 מערכת נסיעה לציוד הנ"ל

4.5 2 מובילי בטון 6 מ"ק כ"א

4.6 מכונה בטון על מערכת זחלים 2 x 1 מ"ק עם קונבייר הגשה.

4.7 2 קונביירים מסחובבים על גלגלים להגשה בטון עם מערכת חשמל.

4.8 דיזל גנרטור 215 קו"א להפעלת הויברטורים.

- הערות :
1. מאזני הגשר הם רק בהזמנה
 2. מובילי הבטון ללא מרכב
 3. הקונביירים להגשה ללא סידורי הנעה ומערכות חשמל.

5.0 מנופים

- 5.1 מנוף יצור מס' 1
- 5.2 מנוף יצור מס' 2
- 5.3 מנוף הקמה
- 5.4 3 מנופים מסתובבים
- 5.5 מנוף מונוריל 2 טון למ"ח רשחות זיון
- 5.6 מנוף מונוריל 1 טון " " "

- הערות:
- 1. מנוף יצור מס' 1 עובר במפעל הישן
 - 2. מנוף יצור מס' 2 מורכב במפעל החדש
 - 3. אחד מהמנופים המסתובבים חסר כננה הרמה.

6.0 טרנספורט

- 6.1 3 יצולים
- 6.2 עגלת טרנזיט
- 6.3 2 טריילרים להובלת קירות
- 6.4 2 משטחי טרנספורט
- 6.5 1 מסדר סיבוב רצפות
- 6.6 1 מוביל T DIAMOND
- 6.7 2 יצולי עזר

- הערות:
- 1. הטרילרים להובלת נזקקים לשיפוץ כללי וסערכות צמיגים חדשות.
 - 2. המוביל T DIAMOND זקוק לשיפוץ כללי וצמיגים חדשים
 - 3. יצולי העזר - האחד גמור ובשני יש רק חומר ויש להשקיע עוד 50% מהעבודה.

7.0 מסדרים

- 7.1 מסדר השחזה הבנוי מעגלת השחזה ורטיקלים, עגלת השחזה עליונה ומסילה נסיעה.
- 7.2 מסדר עבודות גמר 200 קומפ'
- 7.3 מסדר איחסון ורטיקלי 500 קומפ'

- הערות:
- 1. מסדר עבודות גמר - כ-60% מוכן
 - 2. מסדר איחסון ורטיקלי - כ-50% מוכן

8.0 ציור

- 8.1 מרכז מיט לקיטור
- 8.2 מעמס הדראולי

50.6

9.0 הידראוליקה

- 9.1 הפעלה עגלת החללים כולל ברכה, משאבות ואינסטלציה
- 9.2 הפעלה סגרי אורך
- 9.3 הפעלה התנועות בחבנית המחיצות

הערות : 1. סעיף 9.2 - בוצע רק 50%
2. סעיף 9.3 - עדין לא בוצע

10. יצור רשתות זיון

- 10.1 מסדר של אלקו לריחוף נקודתו של רשתות זיון
- 10.2 6 קומפ" של מסדרי ב"ן גופים מרחביים של הזיון
- 10.3 4 קומפ" של מחסניות לגופי זיון מרחביים

הערות : 1. סעיף 10.1 - בוצע כ-50% עדין חסר טרנספורמטור הריחוף
2. סעיף 10.2 - יש חומר וחלקים, יש לבצע עבודה הרכבה
3. סעיף 10.3 - כל החומר ישנו, יש להשקיע עוד 25% מהעבודה.

ל. 289

חישוב מחיר שעת עבודה יצרנית (קבלנותית) במפעלי שבת-סליון בשנים 1960-1965
בניית הצירור הטכנולוגי בלבד

<u>1964/65</u>	<u>1963/64</u>	<u>1962/63</u>	<u>1961/62</u>	<u>1960/61</u>	
8,572	12,898	10,402	5,428	2,685	ס"ה ימי עבודה ברוטו
5,652	8,495	6,800	3,580	1,714	ס"ה ימי עבודה קבלנותיים
2,920	4,403	3,602	1,848	971	ס"ה ימי עבודה שרוחים
					ס"ה הוצאות בל"י (מעוגל) (ראה הערה)
164,025	220,114	144,133	61,846	37,320	מחיר יום עבודה קבלנותי (נסו)
28.9	25.9	21.2	17.3	21.8	ס"ה הוצאות דמי שימוש בבחי מלאכה
28,000	42,000	36,000	24,000	12,000	הוצאות דמי השימוש בבחי מלאכה ביום עבודה
5.1	4.9	5.3	6.7	7.0	מחיר יום עבודה קבלנותי (ברוטו)
34.00	30.80	26.5	24.0	28.8	מחיר לשעת עבודה ישירה
4.25	3.85	3.3	3.0	3.6	מספר ממוצע של עובדים ישירים ביום (מחושב בהתבסס על 280 ימי עבודה)
20	30	24	13	6	ס"ה החוב בשכ"ע (מוכפל במחירם ס"ה ימים קבלנותיים)
192,025	261,546	180,200	85,900	49,583	ס"ה החוב להוצאות שכר בחי מלאכה לפי הנהלת חשבונות
192,025	262,114	180,133	85,846	49,959	

הערות: (1) סעיף 5 : בסעיף זה נכללו : ס"ה הוצאת שכ"ע והוצאות סוציאליות, חומרי העשיה, אחזקה
בית המלאכה, אחזקה מכונות וחשמל, הוצאות כלליות, הוצאות טכנולוגיות והובלה.

(2) ההוצאות בטבלה אינן כוללות אחוזי התכנון וההשקעה

(3) כל המספרים בטבלה מתבססים על נחוגים שהוגשו ע"י מר סלבין

↓
68.5

נספח ד'

חישוב מחיר שעת עבודה אקויוולנטית לבתי המלאכה של ח. סלבין
וההכרזים לזכותו

1. חישוב הזכות לשעה בכל אחת מהשנים 1960-1964

השנה	מחיר לשעה עבודה ישירה מפעלי שבח- סלבין	מחיר לשעה עבודה מבוצעת בענף	מחיר אקויוולנטי של שעה בבצוע קבלני פחות 10%	יהיה זכות לשעה עבודה
1960/1961	* 3.6 ל"י	4.75 ל"י	4.30 ל"י	0.70 ל"י
1963/1962	* 3.0 "	5.00 "	4.50 "	1.50 "
1962/1963	* 3.3 "	5.50 "	4.95 "	1.65 "
1963/1964	* 3.85 "	6.25 "	5.65 "	1.80 "
1964/1965	* 4.25 "	7.50 "	6.75 "	2.50 "

(* לפי נספח ג')

2. חישוב ס"ה הזכות לח. סלבין

השנה	יהיה זכות לשעה עבודה	ס"ה שעות עבודה ישירות בשנה	ס"ה זכות
1960/61	0.70 ל"י	$13,700 = 8 \times 1714$ *	9,600 ל"י
1961/62	1.50 "	$28,600 = 8 \times 3580$ *	42,900 "
1962/63	1.65 "	$54,400 = 8 \times 6800$ *	89,800 "
1963/64	1.80 "	$68,000 = 8 \times 8495$ *	122,400 "
1964/65	2.50 "	$45,200 = 8 \times 5652$ *	113,000 "
			<u>377,700 ל"י</u>
		סה"כ	

(* מספר ימי עבודה לפי נספח ג')

Handwritten signature and date:
5.10.65

"שבח" חברה לייצור כהים להרכבה בע"מ

פרוטוקול הישיבה השניה של מועצת המנהלים
שהתקיימה ביום 3.1.1965 במשרדו של עו"ד
ש. לברון.

השתתפו: המנהלים ה"ה הלל פכטר, מיכאל שטרס, חיים סלבין,
שלמה לברון.

נוכח: מר אמנון סלבין.

עפ"י הזמנה: מר אברהם עקביה - רואה חשבון.

א. בדבר העברת הציוד והמכונות על ידי מר חיים סלבין לחברה -
(ראה סעיף 9 (א) מכתב ההסכם בין הממשלה לבין סלבין),
- נקבע ההסדר הבא:-

(1) כל הציוד והמכונות שנרכשו על ידי מר סלבין, בין
בארץ ובין בחוץ לארץ, יועברו לבעלות החברה במחירי
רכישתם על ידי מר סלבין, על פי החשבונות הנמצאים ברשותו.

(2) הציוד והמכונות שנבנו על ידי מר סלבין בבית מלאכתו
ומתוך שמוש בציודו הפרטי - יועברו לבעלות החברה
במחיר הנמוך משנים אלה:

(א) המחיר לפי שוויים של הציוד והמכונות כפי
שייקבע על ידי ועדת המומחים, הנזכרת בכתב
ההסכם, או

(ב) המחיר לפי הוצאות ההשקעה הממשית שנעשו על ידי
מר סלבין בהתאם לרישומים וכרטיסי עבודה שנוהלו
על ידו, בחוספת דמי שימוש מקובלים עבור השימוש
בניה מלאכתו ובציודו הפרטי, ובחוספת שכר מקצועי
עבור הכנת תכניות מפורטות לעבודה ופיקוח על
הביצוע.

(3) במקרה והשווי שייקבע על ידי ועדת המומחים עפ"י
סעיף (2) (א) דלעיל יהיה גבוה מהמחיר לפי סעיף
(2) (ב) דלעיל, חהיה שמורה הזכות למר סלבין לחבוע
השלום ההפרש מתוך רווחיה של החברה בעת שרווחים כאלה
יווצרו.

(4) ועדת המומחים תקבל הנהיגות לקבוע את שוויים של
המכונות ושל הציוד הנדונים בהתאם למחירי השוק
ששררו באותה שנה בה נרכש או נבנה הפרט המתאים.

ב. העברת הציוד והמכונות תיעשה ליום 1.4.1965 וועדת המומחים
תחבקש לסיים את עבודתה עד אז.

פנקסי החברה ייפתחו על פי הנהגות הנ"ל לארריך האמור.

2

THE UNITED STATES OF AMERICA
DO hereby certify that
the following is a true and correct
copy of the original as the same
exists in the records of the
Department of the Interior.

THIS CERTIFICATE IS ISSUED BY THE
DEPARTMENT OF THE INTERIOR

AT WASHINGTON, D. C.

THIS 10th DAY OF APRIL, 1900.

WITNESSED my hand and the seal of the
Department of the Interior at
Washington, D. C., this 10th day of
April, 1900.

JOHN W. FOSTER, Secretary of the
Department of the Interior.

By _____, Assistant Secretary.

THE UNITED STATES OF AMERICA
DO hereby certify that
the following is a true and correct
copy of the original as the same
exists in the records of the
Department of the Interior.

THIS CERTIFICATE IS ISSUED BY THE
DEPARTMENT OF THE INTERIOR
AT WASHINGTON, D. C.

THIS 10th DAY OF APRIL, 1900.

WITNESSED my hand and the seal of the
Department of the Interior at
Washington, D. C., this 10th day of
April, 1900.

JOHN W. FOSTER, Secretary of the
Department of the Interior.

By _____, Assistant Secretary.

ב. קביעת שוויין של העבודות על מגרש החברה.

עבודות ההכשרה והפיתוח שנעשו במגרש החברה ברמלה וכן עבודות בנייתו של המפעל שבוצעו ויבוצעו עד ליום 4.1965. 1 - ייזקפו בפנקסי החברה לפי ההוצאות הממשיות שהוצאו בפועל על ידי מר סלבין שניהל את העבודות האלה, בתוספת שכר תיכנון ושכר פיקוח המגיע למר סלבין עבור עבודתו המקצועית.

ד. אושרו עקרונות הזמנות ציוד עבור החברה כדלקמן:

(1) שני מובילי בטון בסכום של 34,000 ל"י בערך (לא כולל מכס).

(2) מאזני שקילה - בסכום של 24,000 ל"י בערך.

(3) קומפרטור מתוצרת ארצות הברית.

(4) שתי מכונות השחזה מתוצרת צרפת.

(5) ציוד הידרולי מתוצרת ארצות הברית.

הוחלט להזמין ביצוע כסוי מלוחות אסבסט לקירות בית החרושת ולגגו, לפי המהיר הנמוך שיושג בין שתי החברות המייצרות את המוצר, שהן "עולמית" ו"ישאשבסט".

ה. פתיחת חשבונות בבנקים:

הוחלט לפתוח שלשה חשבונות בשם החברה:

(1) חשבון עובר ושב בבנק לאומי לישראל, בסניף רמלה ובסניף המרכזי בחל-אביב.

(2) חשבון משיכות בבנק "מפחות".

(3) חשבון סילוקין אצל החשב הכללי.

בהתאם לתקנות החברה, זכות החתימה בחשבונות הבנקאיים תהיה נתונה לכל שנים ממנהלי החברה.

יו"ר הישיבה.

THESE ARE THE RESULTS OF THE

ANALYSIS OF THE DATA WHICH WERE
OBTAINED FROM THE TESTS WHICH WERE
CONDUCTED AT THE LABORATORY OF THE
NAVY DEPARTMENT, WASHINGTON, D. C.,
ON THE 15TH, 16TH, 17TH, 18TH, 19TH,
20TH, 21ST, 22ND, 23RD, 24TH, 25TH,
26TH, 27TH, 28TH, 29TH, 30TH, 31ST,
AND 1ST OF JANUARY, 1918.

THE RESULTS OF THE ANALYSIS OF THE
DATA WHICH WERE OBTAINED FROM THE
TESTS WHICH WERE CONDUCTED AT THE
LABORATORY OF THE NAVY DEPARTMENT,
WASHINGTON, D. C., ON THE 15TH,
16TH, 17TH, 18TH, 19TH, 20TH, 21ST,
22ND, 23RD, 24TH, 25TH, 26TH, 27TH,
28TH, 29TH, 30TH, 31ST, AND 1ST
OF JANUARY, 1918, ARE AS FOLLOWS:

THE RESULTS OF THE ANALYSIS OF THE
DATA WHICH WERE OBTAINED FROM THE
TESTS WHICH WERE CONDUCTED AT THE
LABORATORY OF THE NAVY DEPARTMENT,
WASHINGTON, D. C., ON THE 15TH,
16TH, 17TH, 18TH, 19TH, 20TH, 21ST,
22ND, 23RD, 24TH, 25TH, 26TH, 27TH,
28TH, 29TH, 30TH, 31ST, AND 1ST
OF JANUARY, 1918, ARE AS FOLLOWS:

THE RESULTS OF THE ANALYSIS OF THE
DATA WHICH WERE OBTAINED FROM THE
TESTS WHICH WERE CONDUCTED AT THE
LABORATORY OF THE NAVY DEPARTMENT,
WASHINGTON, D. C., ON THE 15TH,
16TH, 17TH, 18TH, 19TH, 20TH, 21ST,
22ND, 23RD, 24TH, 25TH, 26TH, 27TH,
28TH, 29TH, 30TH, 31ST, AND 1ST
OF JANUARY, 1918, ARE AS FOLLOWS:

RESULTS OF THE ANALYSIS OF THE

DATA WHICH WERE OBTAINED FROM THE
TESTS WHICH WERE CONDUCTED AT THE
LABORATORY OF THE NAVY DEPARTMENT,
WASHINGTON, D. C., ON THE 15TH,
16TH, 17TH, 18TH, 19TH, 20TH, 21ST,
22ND, 23RD, 24TH, 25TH, 26TH, 27TH,
28TH, 29TH, 30TH, 31ST, AND 1ST
OF JANUARY, 1918, ARE AS FOLLOWS:

THE RESULTS OF THE ANALYSIS OF THE

DATA WHICH WERE OBTAINED FROM THE

TESTS WHICH WERE CONDUCTED AT THE
LABORATORY OF THE NAVY DEPARTMENT,
WASHINGTON, D. C., ON THE 15TH,
16TH, 17TH, 18TH, 19TH, 20TH, 21ST,
22ND, 23RD, 24TH, 25TH, 26TH, 27TH,
28TH, 29TH, 30TH, 31ST, AND 1ST
OF JANUARY, 1918, ARE AS FOLLOWS:

THE RESULTS OF THE ANALYSIS OF THE

07 01 01

סיכום ישיבה

בנושא מכירת מניות חברת "שבת", המוחזקות ע"י המדינה,

שהתקיימה במשרדו של מר יוסף שרון ב- 12.4.70

השתתפו ה"ה:
י. שרון
ח. סלבין
א. סלבין
ה. אשכנזי
א. אולניק
א. בליץ.

מר ח. סלבין סקר את הדקע והרומתו לפיתוח שיטתו בייצור בחים טרומיים, לייסוד חב' "שבת" וחקמת המפעל ברמלה. מר ח. סלבין הצהיר כי עיקר כוונתו להביא להשלמת המפעל ולביסוס השיטה.

לאחר סקירה זו הצליח מר ח. סלבין כי תקבע תקופת ביניים של חצי שנה, שבה יכנס נציג המדינה עמו למשא ומתן על הסדר מכירת מניות הממשלה בחברת "שבת".

מר י. שרון, המנהל הכללי של משה"ש, הודיע כי יביא את בקשתו הנ"ל של מר ח. סלבין בפני שר השיכון מר זאב שרף וחנן מספר ימים יקבל מר ח. סלבין תשובה להצעתו.

רשם : איחמר גליץ

UNITED STATES

DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

WATER RIGHTS
DIVISION
SALT LAKE CITY
UTAH
JULY 1, 1954

TO THE HONORABLE MEMBERS OF THE HOUSE OF REPRESENTATIVES
AND SENATORS OF THE UNITED STATES
FROM THE BUREAU OF LAND MANAGEMENT

RE: REPORT OF THE BUREAU OF LAND MANAGEMENT
ON THE PROGRESS OF THE WORK DURING THE YEAR 1953

AND A SUMMARY OF THE RESULTS OF THE WORK
DURING THE YEAR 1953

(לכתובת פנימית במשרדי הממשלה)

מוזכר

אל:	ה. ג. פלד	תאריך:	10.10.70
מאת:	8.10.70	מספר:	1000
הנדון:	ממקד מלג 29 מרס 1970		

9.30 בצהריים

8 מכתב' מיום 31.3.70

בכבוד,

א

Blank lined area for writing, possibly a header or title section.

Blank lined area for writing, possibly a body text section.

מדינת ישראל

התאריך 1.4.70

היקף מס'

אל:

מ. פ. בן צבי

מאת:

אברהם רמז

הנדון:

מכתב היטוי שנתקבל ב-18/3/70

אני שוקן מעבר את חקתי

העבר כפי שאל מ. סניידר

אם זהו, אפילו, ולכן זה


היה קצת לא ידוע לי

אולי לא אצטרף.

אברהם

11 אדר ב' 5730 - 1.4.70

ק"פ 5730



משרד השיכון

31.3.70

א ל: י. שרון מנכ"ל

מאת: ע. בן-צבי הממונה על הבניה הסדומית.

הנדון: פרטיכל הישיבה שהתקיימה במשרדך ב- 18.3.70, מנוי
ועדה לגבי ביהח"ר שבח רמלה.

היות ונחגלו חילוקי דעות לגבי הפרטיכל של הישיבה, חריני
מצדך את שתי הגירסאות ומבקש את הגדרת תפקידי הועדה כפי
שהוכר נראה בעיניך.

ב ב ר כ ה



ע. בן-צבי

העתק: מר. ה. אשכנזי
" א. בליץ

1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 26

1055

EAS-1

מדינת ישראל
משרד השיכון

תאריך: 27.3.70

מספר:

52.13

א ל: איתמר גליץ, משרד סמנכ"ל לחברות
מאת: עמנואל בן-צבי, היחידה לבניה טרומית

הנדון: זכרון דברים משיבה שהתקיימה ב- 18.3.70
במשרד המנכ"ל י. שרון.

זכרון הדברים מהישיבה הנ"ל שנרשם על ידך אינו משקף בדיוק את הנחיות המנכ"ל לועדה. אני רואה את ההוראות בהתאם לניסוח שנרשם על ידי כדלקמן:
"על הועדה הוטל לבדוק את טיב המוצרים, שיטת הייצור והציוד ולהציע שינויים ו/או שיפורים במידה שתמצא לנכון."
דו"ח הועדה חייב להגיע למנכ"ל תוך חודש ימים.
נראה שלמען הסדר רצוי לפרסם השלמה לפרטיכל הנ"ל.

ב ב ר כ ה

18/3

ע. בן-צבי
הממונה על הבניה הטרומית

100-100000

100-100000

100-100000, 100-100000

100-100000, 100-100000

100-100000, 100-100000
100-100000, 100-100000

100-100000, 100-100000
 100-100000, 100-100000
 100-100000, 100-100000

100-100000, 100-100000
 100-100000, 100-100000

100-100000, 100-100000

100-100000, 100-100000

100-100000

100-100000

100-100000, 100-100000

משרד השיכון

כ"א באדר ב' תש"ל

29 במרץ 1970

אל : מר זאב שרף, שר השיכון

מאנו: סגן המנהל הכללי לחברות

הנדון: הכשר בגיה לחברת "שבח"

בהקשר עם הפיקעוּקִים שהועלו לאחרונה בדבר עצם
הכשרות וההתאמה לשימוש של "שיטת סלביץ", אני
מפצא בלוטה את תעודת ההכשר שניתנה לחברת "שבח"
בסוף 1968, על ידי התחנה לחקר הבניה - הסכניון.

המרוססור רחל שלון עמדה בראש הוועדה המקצועית
אשר בדקה את החומר על פיו ניתן ההכשר האמור וכן
היו חברים בוועדה זו, בין השאר, גם נציגי משרד
השיכון.

בברכה,

הלל אשכנזי,

העמק: מר יוסף שרון, מנהל כללי, משרד השיכון

07 01 01



מוסד הטכניון למחקר ופתוח בע"מ
Technion Research and Development Foundation Ltd.

הטכניון - מכון טכנולוגי לישראל
Technion - Israel Institute of Technology

תחנה לחקר הבניה
Building Research Station

תאריך: 12.3.70
סמוכנו: 4.1/555(2344)

לכבוד

אינג' ע. בן-צבי

הממונה על בניה טרומית

משרד השכון

הקריה

תל אביב

א.נ.,

הנדון: מעקב חד פעמי ודו"ח על רמת הייצור של
ביהח"ר "שבח"

בהמשך לשיחה טלפונית בינך לבין פרופסור ר. שלון ולמכתבך מיום
27.11.69 בנדון, נערך ע"י החתום מטה מעקב אחר מהלך הייצור בביהח"ר
ואופן ההרכבה והגמר של האלמנטים באתר הבניה.

בדו"ח להלן ניתנים פרטי המעקב והמלצותינו לשפור רמת הייצור
בביהח"ר.

1. שיטת ייצור האלמנטים

הקירות והתקרות מיוצרים בבית החרושת ביציקה ורטיקלית, כשבכל
תבנית נוצקים בעת ובעונה אחת שני אלמנטים. התבנית מורכבת מדופן
פלדה אמצעית חלולה, המוצבת באופן קבוע ודפנות פלדה חיצוניות ניידות
הניתנות להרחקה וקרוב לדופן הפנימית בהתאם לצורך. קצות הקיר
ותחתיתו תחומים ע"י פרופילי פלדה הניתנים להזזה גם הם. סגירת
התבנית נעשית באמצעות מתקנים הידראוליים הקובעים תחילה את מקום
הפרופילים התחומים את קצות הקיר ומתקנים הידראוליים אחרים

המהדקים את דפנות התבנית והפרופילים זה לזה. שטח המגע בין הפרופילים התוחמים ודפנות התבנית הוא כ-20 מ"מ והוא נמשך בכל היקף הקיר. אין משתמשים בכל אמצעי אטימה נוסף או חזק אחר נוסף על הלחץ המופעל ע"י המתקנים ההידראוליים במקומות שונים לאורך תחתית הקיר וקצותיו.

הזיון במחיצות ובתקרות והזיון בצרופ חמר הבידוד (פוליסטירן מוקצף) בקירות החוץ, וכן משקופי פלדה לדלתות ותבניות מתאימות ליצירת חללים עבור החלונות, מוכנסים לתבנית לפני סגירתה.

הבטון המוכן במתקנת בטון מצוידת באמצעי מינון מתאימים, מוכנס לתוך ערבלים ניידים ומעבר באמצעותם למקום יציאתו בתוך התבניות. יציאת הבטון מהערבל נעשית ישירות באמצעות השקתות בהם מצוידים הערבלים.

על גבי הדפנות החיצוניים של הערבלים מותקנים מרסטים חיצוניים בעלי תדירות נמוכה יחסית (2000 ריטוטים לדקה, כפי שנמסר ע"י מר סלויין). עם התחלת יציאת הבטון מופעלים המרסטים והם ממשיכים בפעולתם עד למילוי התבנית בבטון לכל גובהה.

כפי שנמסר ע"י מר סלויין, משקל התבנית הריקה הוא כ-20 טונות, ומשקל הבטון עלול להגיע עד 16 טונות עבור שני קירות בעלי גודל מקסימלי הניתן ליציאה בתבנית.

לאחר מילוי התבנית מתחילה אשפרת הבטון באמצעות קיטור. הקיטור מחדר לדופן הפנימית החלולה וגורם לחמום הבטון הבא במגע עם הדופן. האשפרה בקיטור נמשכת כשלוש שעות.

לאחר התקשות הבטון מפורקת התבנית והאלמנטים מעברים לאזור החסנה. במקום זה מבוצעים תיקונים שונים באלמנטים ומורכב הבלוק הסניטרי.

2. הרכבת האלמנטים הטרומיים באתר

האלמנטים הטרומיים מעברים ע"י נגררים לאתר ושם מחוברים זה לזה באמצעות ברגים מתאימים ואטמים. תאור פרטי החיבור השונים ניתן בהכשר הבניה שהוצא עבור חברת שבח.

הקירות החיצוניים מצופים מצידם החיצוני במעטה דקורטיבי על בסיס פולימרי (באגרמנט שהוצא ב-12.68 מדובר על צפוי בפלסטרונג. הצפוי שמשתמשים בו בשלב הנוכחי הוא מסוג אחר כפי הנראה). ביצוע הצפוי בצורה הנוכחית דורש הקמת פגומים לכל גובה המבנה.

הצד הפנימי של קירות החוץ וכן קירות הביניים והמחיצות מטויחים בשכבת שליכט.

3. הליקויים במהלך הייצור

קיימת אי אחידות רבה באיכות הבטון המיוצר. החתום מטה היה נוכח בשעת יציקת אצוות בטון משני ערבליים ניידים (נפח הבטון בכל אצווה כ-6 מ"ק). אחת מאצוות הבטון היתה בעלת סומך פלסטי והשניה בעלת סומך יציק. בחינת שתי הערובות בלבד אינה מספקת לקביעת שיעור אי אחידות הבטון אולם, העובדה שבזמן קצר של שהיה במפעל ניתן היה לפגוש אצוות בטון בעלות סומך כה שונה, נראית כמדאיגה.

התבניות הינן בלתי נוחות לניקוי, שטחי המגע בין חלקי התבנית הנועדים לאטימה אינם נקיים והתבניות אינן אטומות בעת היציקה. לצורך ניקוי התבניות יש צורך בהכנסת פועלים בין שני דפנות פלדה משומנים אשר המרחק ביניהם הוא כ-40 ס"מ. ההתרשמות האישית של הח"מ היא, שמלאכת ניקוי התבניות קשה מכל מלאכה הדרושה בשיטת הבניה הקונבנציונלית. מחוץ ביקורת התבניות לפני היציקה ניתן להסיק, שניקוי התבניות, אם בוצע בכלל, הרי שבוצע ברשלנות מרובה. בטון קשוי שלא נוקה מהתבניות עוביו מגיע במקומות רבים ל-10 מ"מ לערך. בטון קשוי נמצא גם בין חלקי התבנית, אשר לצורך אטימתה חייבים להיות נקיים בהחלט. ניתן היה לראות מרוחים של כ-5 מ"מ בין חלקי תבנית שהיו צריכים להיות צמודים זה לזה.

יציקת הבטון לחוץ התבנית נעשית תוך התעלמות מהנוהלים הדרושים של יציקת בטון. אין כל הקפדה על מניעת סגרגציה של הבטון. אין הקפדה על מילוי התבנית לכל אורכה באופן הדרגתי. במקרה של חלונות פתחים בקירות אין כל שיטתיות ביציקת הבטון באופן שיחדור וימלא מתחת לפתחים אלו. במקרה של יציקת הקירות החיצוניים המכילים שכבת פוליסטירן תפוח במרכזן, אין הקפדה על מילוי אחיד של הבטון משני צידי לוח הפוליסטירן והבטון מועבר מצד אחד לשני רק דרך חורים בקוטר כ-20 ס"מ המצויים בלוחות הפוליסטירן.

שימת הבטון נזשית ללא הקפדה שהיא וגם במקרים של סגרגציה בולטת בחלק העליון של הקיר היצוק לא ננקטה כל פעולה לתיקון המצב.

צפוף הבטון נעשה ע"י הפעלת המרטטים החיצוניים תוך כדי מילוי התבניות בבטון. פעולת המרטטים אינה אפקטיבית וכאשר מחצית התבנית ממולאת בבטון, כמעט ולא ניתן להרגיש ברטוט. עקב הכנסת שכבת הפוליסטירן לתוך הקיר ספק אם פעולת הרטוט החיצונית יכולה לחדור לכל עומק הבטון בקירות החוץ.

אי האטימה של התבנית, גורמת להתנקזות מלט דרך החיבורים ונזילתו החוצה בכמויות ניכרות. הנזילה נמשכת במשך כל זמן הריטוט.

אשפרת הבטון נעשית בטמפרטורה בלתי מבוקרת ובשעת הביקור ניתן היה לראות תבנית ממולאה בבטון בתהליך אשפרה, והמים שהכיל הבטון רותחים.

בטון הנוצק לצורך תיקונים שונים באלמנטים איננו בעל איכות מבוקרת ואינו מקבל אשפרה כלשהי.

4. פגמים באלמנטים הקשויים

ניתן להבחין בפגמים באלמנטי הבטון הקשוי, שנגרמו ע"י הליקויים שצוינו לעיל:

פגמים שנגרמו עקב נזילת מלט דרך חבורי התבנית פגמים אלו מופיעים בצורת יציקת בטון ללא דק והם שכיחים לאורך מקצועות הקיר (המקצועות בקצות הקיר ובתחתיתו). כמעט ובלתי ניתן למצוא אלמנט אשר בו לא יהיה קיים פגם כזה.

פגמים שנגרמו עקב סגרגציה של הבטון פגמים אלו מופיעים בצורת קיני חצץ במקומות שונים על פני שטח האלמנטים. פגמים שנגרמו ע"י צפוף בלתי מספיק של הבטון. פגמים אלו מופיעים בצורת שקעים לאורך הזיון האופקי. עצמת הריטוט לא הספיקה להתגבר על מכשולים כגון מוטות זיון אופקי.

פגמים שנגרמו ע"י בטון קשוי דבוק לפני התבנית. הפגמים מופיעים בצורת שקעים בשטח פני הבטון וחספוס ניכר של פניו בעומק המגיע לעיתים ל-10 מ"מ.

פגמים שנגרמו ע"י אפשרה בטמפרטורה גבוהה מדי. נראים בבטון פגמים בצורת סדקים אופקיים שנגרמו ע"י אפשרת הבטון בטמפרטורות גבוהות מדי. פגמים שנגרמו בזמן פרוק התבניות. ניכרים פגמים שנגרמו עקב הוצאת הצנורות שהיו מיועדים ליצירת חורים בקצות האלמנטים לצרכי העברת לולבי החיבור.

5. פגמים הנראים במהלך ההרכבה

במהלך ההרכבה ניתן לראות, שהפגמים המרובים הקיימים באלמנטים הקשויים, אינם מאפשרים הדוק האטמים באופן אחיד ולעיתים אף משאירים את חמרי האיטום חשופים כלפי חוץ.

6. הצעות לשיפורים

המערך כפי שהוא קיים כיום אינו נראה כניתן לשיפור ללא שינויים יסודיים מאד.

גם אם תונהג בקרה מלאה על איכות הבטון ואשפרתו נותרות עדין בעיות כגון: אטימת התבנית (תבנית אטומה היא תנאי הכרחי ליציקות מטוג זה), הקשיים בניקוי התבנית הגוררים בהכרח ניקוי בלתי משלם על כל הפגמים הכרוכים בו וכן יציקה בלתי נכונה ורטוט בלתי מספיק של הבטון.

נראה כי יש נגוד בין המטרה לתעוש יצירת אלמנטי השלד לבין שיטת יצור האלמנטים הנוכחיים המצריכה תיקונים כה רבים בעבודת יד וכן טיח. (שכבת שליכט במקרה זה אינה מספקת).

כדי לשפר את המצב הנ"ל שאין מנוס מהגדרתו כבלתי משביע רצון יש צורך בהכנסת שינויים יסודיים ונרחבים.

כדי להגיע לתוצרת משביעת רצון, יש לפי מיטב הבנתנו לתכנן מערך שונה מהקיים על כל שלביו, החל מהבטחת אחידות הבטון וכלה באשפרת הבטון, דרך שינוי פרטי התבנית, השימה והציפוף של הבטון.

המטרה הסופית צריכה להיות קיר מוכן לשימוש בהעדר או במינימום עבודות תיקונים באתר. שינויים חלקיים או שיפורים מזעריים אין בהם כדי לשנות את המוצרים לגבי הדרישות הראשיות הנ"ל.

בכבוד רב,
ד"ר א. קליין
מרכז החדידה

הצדדים יגרמו לכך כי החברה לכשתירכס כדין הקבל על עצמה את כל ההתחייבויות שניתנו מטעם המדינה בין בצורה ישירה ובין בעקיפין למינהל מקרקעי ישראל בקשר עם הקצאת המגרש ומסירת החזקה בו לידי הממציא כנציגה של החברה העומדת להווסד, וכי החברה תשחרר את המדינה מכל ההתחייבויות האלה.

.6

.7

(1) נוסף למניות אותן יקבל הממציא בחור תמלוג חד פעמי בהתאם להנראות סעיף 17 (1) א' דלמטה, נותנת בזה המדינה אופציה לממציא לרכוש מניות של החברה בשיעור שלא יעלה על 15% (חמשה עשר אחוז) מהון המניות הרשום במחיר לפי ערכן הנקוב של המניות. אופציה זו תישאר פתוחה לקבלתה על ידי הממציא תוך ששה חדשים מיום רשום החברה.

(2) השתמש הממציא בזכותו לקבל את האופציה תוך התקופה האמורה, תעביר לו המדינה את המספר המהאים של המניות באופן הדרגתי בהתאם לשלבי הזכויים שייעשו לחשבון השלומי הממציא עבור מניותיו כמבואר להלן: במקום העברת חלק ממניותיה בחברה לטובת הממציא רשאה המדינה להשאיר חלק מהון מניותיה הרשום של החברה בלתי מוצא ולגרום להקצאת מספר מהאים של מניות מהון החלק הבלתי מוצא האמור - לטובת הממציא לפי השלבים האמורים.

(3) לא השתמש הממציא בזכותו לקבל את האופציה תוך התקופה האמורה, תפוג האופציה ולממציא לא תהיה עוד כל זכות לתבוע רכישה חלק ממניות החברה, מלבד למניות שיגיעו לממציא על פי סעיף 17 (1) א' להלן בחור תמלוג חד-פעמי.

.8

(1) המניות אותן יקבל הממציא כתמלוג חד-פעמי אינן ניתנות להעברה על ידי הממציא אלא לבנו אמנון סלבין, וזה האחרון לא יוכל להעבירן שוב לאחר.

(2) כל עוד לא תושלם הקמתו של המפעל ולא יתחיל ההליך הייצור הסדיר במפעל לא יהיה הממציא רשאי להעביר את מניותיו הנוספות בחברה - כלומר אלה שלגביהן השתמש הממציא בזכות האופציה הנזכרת לעיל - אלא לבנו אמנון, ואולם יוכל הממציא להעביר עד כדי שליש (1/3) אחד מהמניות הנוספות האלה לידי איש או גוף משפטי שביחס לזהותו או לאישיותו לא תהיה למדינה התנגדות; בכל מקרה חייבות המניות המועברות על ידי הממציא להיות מניות משולמות במילואין.

(3) עם התחלת ההליך הייצור הסדיר במפעל, לאחר שהקמתו הושלמה, יהיה כל צד חופשי להעביר את מניותיו הרגילות כולן או מקצתן, לכל איש או גוף משפטי אחר, כפוף לחובה להציען החילה לצד השני כאמור בסעיף משנה (4) להלן.

(4) בכל מקרה שבו ירצה אחד הצדדים להעביר את מניותיו בחברה, כולן או מקצתן, לאחר, יהיה על אותו צד להציע תחילה את המניות הנדונות לצד השני לרכישה על ידו, והצד השני יהיה זכאי לרכוש את כל המניות המוצעות למכירה ולא חלק מהן. בהיעדר הסכמה בין הצדדים בדבר מהיר שיש לשלם עבור המניות המוצעות למכירה, ייקבע מחירן על ידי ועדה מומחים בת כלושה חברים שיתמנו כדלקמן: אחד על ידי כל צד, והשלישי על ידי המנהל הכללי של בנק לאומי לישראל בע"מ, חברי ועדה המומחים לא יפעלו כבוררים, וקביעתם תהיה סופית ומחייבת.

9. הממציא ישלם את תמורת המניות הנוספות שלגביהן השתמש בזכות האופציה באופן ובצורה הבאים:-

- א. מיד לאחר יסוד החברה, יעביר הממציא לבעלותה בהעברה מוחלטת את המכונות ואת הצילוד, הן אלה שנרכשו על ידי בחוץ לארץ, והן אלה שנבנו או נרכשו על ידי בארץ, לפי הפירוט שבנספח ב', במחיר שווים. השווי ייקבע על ידי ועדה של שלשה מומחים שיתמנו כדלקמן: כל צד ימנה מומחה אחד, והשלישי ימונה על ידי מנהל מכון התקנים הישראלי. המומחים לא יפעלו כבוררים, וקביעתם תהיה סופית ומחייבת את הצדדים.
 - ב. מחוץ השווי האמור יזקף 95% לחשבון המניות שלגביהן השתמש הממציא באופציה, ומניות במספר יחסי שעבורן שולם כנ"ל תיחשבה כמניות משולמות במלואן.
 - ג. עודף המחיר האמור ייזקף כהשלום חלקי על חשבון יתר המניות שלגביהן השתמש הממציא בזכות האופציה כאמור לעיל.
 - ד. על הממציא יהיה לשלם למדינה את עודף מחירן של המניות שלא שולמו במלואן לא יאוחר מאשר תוך 7 שנים מהאריך רישום החברה על ידי רשם החברה. הסכום שלא שולם על חשבון מניות הממציא יהיה צמוד למדד מחירים של הומרים ושרותים לבנייה המהפרסם על ידי הלשכה המרכזית לסטטיסטיקה ולמחקר הכלכלי. כמדד יסודי ישמש גובה המדד שיפורסם על ידי הלשכה לגבי החודש שיבוא לאחר תאריך רישומה של החברה, ובמקרה של עלייתה, יוגדל סכום היתרה ע"ה המניות באופן יחסי. החישוב ייערך כל אימת שהמדינה תשלם השלום על חשבון מניותיה היא.
- במידה וההשלומים ששולמו על ידי המדינה על חשבון מניותיה בחברה יעלו בזמן מן הזמנים, על חלקה היחסי של המדינה בחון מניותיה של החברה, תהיה המדינה זכאית לקבל רבייה מכסימאלית חוקית על ההפרש שבין סכומם הכולל של ההשלומים ששולמו על ידי לבין חלקה היחסי האמור, וזאת למשך אותו פרק זמן שבו נמשך ההפרש.

ה. חלק ההמלוגים אשר יגיעו מאת החברה לממציא על פי הסכם זה ייזקף לטובת הממציא על חשבון המניות כנגד עודף מחיר המניות שוגיע מאת הממציא וכל סכום שנזקף כך יישב, בכפופות לכל נכוי שיידרש לעשותו למס הכנסה או מס אחר כלשהו, כהשלום על חשבון מהיר מניות אלו.

ו. אכן, אם בחום הקופה 7 השנים מהאריך רישום החברה לא שולם עודף מהיר המניות על ידי הממציא, בין במישרין ובין על ידי זקיפה כנגד המלוגים כאמור, תהיה החברה, על פי החלטת המנהלים, זכאית להפקיע חלק מהמניות האמורות ולמכרן באופן שתמצא לנכון, בהתאם לתקנות ההתאגדות של החברה, ולשלם תמורתן את מהיר יתר המניות שהייתה מוחזקות באותה עת על ידי הממציא, ואשר תמורתן לא שולמה במלואה;

ז. אם החברה תחליט להקצות מניות הטבה, או לחלק רווחים בצורה אחרת, או שתחליט על חלוקה נכסיה בעין בפירוק, לא יהיה זכאי הממציא להשתתף בקבלת מניות הטבה או רווחים, או להשתתף בחלוקה נכסי החברה בעין, אלא בגין אותם סכומים שיהיו משולמים על ידי הממציא על חשבון מניותיו בחברה, או שיהשבו על ידי החברה כמשולמים על חשבון מניותיו אלו.

זכות ההצבעה בגין אותן מניות הטבה תהיה בהתאם לערכן הנקוב.

ח. לא השתמש הממציא בזכות האופציה שלו בכלל, או השתמש באופציה לגבי מספר מניות שערכן הנקוב הנו פחות משווי המכונות והציוד שנקבע בהתאם להוראות סעיף משנה (א) דלעיל, הגרום המדינה לכך שהחברה השלם לממציא את שווי המכונות והציוד במלואו, או את החלק הנותר של השווי לאחר נכוי החלק המתאים למהיר המניות, כפי המקרה, וזאת כנגד העברת המכונות והציוד על ידי הממציא לזכות החברה בבעלות שלמה.

א. 10. הממציא מתחייב בזה, שבשעת העברת המכונות והציוד לבעלות החברה, כאמור בסעיף הקודם, יהיו המכונות והציוד חופשיים מכל חוב, עיקול, משכון או שעבוד אחר כלשהו ו/או מחביעה זכות על ידי צד שלישי, וכן במצב טוב ותקין וראוי לשימוש מידי.

ב. הממציא מצהיר בזה, כי המכונות והציוד המפורטים בנספח ב' כוללים אך ורק פריטים הנהוצים לשם ניצול יעיל במפעל לצורך ייצור בתים לפי השיטה.

חלק ג' - מימון פעולות החברה

11. הצדדים מעריכים כי ההשקעה הכוללת במפעל הדרוש - נוסף לסכום הונה הרשום של החברה - סכום של כמליון לירות ישראליות, וזה יבוא בצורת הלוואה שהמדינה הגרום לנהיגתה מתוך כספי הקצבת הפיתוח של המדינה. הלוואה זו הינתן לחברה במועדים ובשעורים לפי ההקדמות הקמתן של המפעל וציודו, ועל פי החלטת המינהלה. הצדדים מניחים כי הלוואה הינתן באמצעות הבנק לפיתוח העשייה בישראל בע"מ.

חברה לייצור בתים להרכבה בע"מ

החברה התאגדה באוקטובר 1964, בהון רשום של 4 מיליון ל" (מזה 75% בידי המדינה ו-25% בידי המטציא) במטרה להקים ולנהל מפעל לייצור בתים להרכבה, על פי שיטה שפותחה ע"י המהנדס והמטציא חיים סלביין.

השיטה מבוססת על שעור תיעוש גבוה יחסית ועל מספר קטן של אלמנטים גדולים המשמשים על חסכון בפעולות הרכבה ועל צמצום מספר החיבורים.

כמו כן לפי שיטה זו, יציקת האלמנטים היא אנכית והוסכת בעיקר שטחי ייצור.

המפעל ברמלה, הוכנן לכוסר ייצור של 1,000 יח"ד ב-2 משמרות ייצור ומטרת אחזקה. היקף החשקעות המקורי היה בסדר גודל של 5 מיליון ל" עד היום הושקעו בכספים קבועים כ-6.5 מיליון ל" .

החברה החלה לפעול באפריל 1965, כשקצב ההשקעות וההקטת היה איטי. לאחר בחירת מועצת המנהלים בהרכבה הנוכחי מטרץ 1967 הוחל בהרצה וייצור - ועד סוף מרץ 1969 נוצרו כ-104 יח"ד ברמלה, הבניין הראשון נמסר למשתכנים במרץ 1969.

הדירות הן בנות 70 מ"ר וכוללות 2 חדרי שינה, חדר מגורים ושירותים.

בשנה הכספית 1969/70 ייצור המפעל 240 יח"ד לאתרים ברמלה ובמלור, וביורי המפעל הזמנות ל-472 יח"ד נוספות.

המחירים אותם מקבל המפעל עבור ייצור הדירות והרכבתן, נקבעו בתקופת המיתון ואינם תואמים עוד את הוצאות הייצור הריאליות לאור ההתייקרויות בהמרים ובשכר עבודה.

מיצוי יעילותה של השיטה, נפגם בשל מספר בעיות כגון חוסר בכח אדם מקצועי שיאפשר הפעלה סדירה של ייצור האלמנטים במפעל, הרכבתם באתרים השונים ואחזקה שיטתית, וכן הקשיים בגיבוס מערכת ארגונית וביסוס מערכת המהירות.

חכנית הייצור של המפעל לשנה הקרובה, נאמדת ב-480 יח"ד, בבדי להבטיח חכנית ייצור זו, יש צורך להשלים השקעות נוספות במערכת הייצור, ולהבטיח רמת אחזקה וכת אדם מקצועי מתאימים.

- | | |
|---------------------|------------------------|
| חברי מועצת המנהלים: | 1. הלל ששכנזי - משה"ש |
| | 2. משה לפיד - משה"ש |
| | 3. דוד טרנה - מהנדס |
| | 4. שלמה לברון - עו"ד |
| | 5. חיים סלביין - מנכ"ל |

SECRET

On the 15th of the month of May, 1964, the following information was received from the source:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

The source has been advised that the following information is being furnished to you for your information:

- SECRET
1. The source has been advised that the following information is being furnished to you for your information:
 2. The source has been advised that the following information is being furnished to you for your information:
 3. The source has been advised that the following information is being furnished to you for your information:
 4. The source has been advised that the following information is being furnished to you for your information:
 5. The source has been advised that the following information is being furnished to you for your information:

חברה ליצור בתים להרכבה בע"מ

תאריך

6.2.70

מספרנו

רכוז עלויות לדירהפרטיםעבודה

בבית חרוש

3,180.--

האתרים

3,465.52

6,645.52

חומרים

בבית חרוש

2,200.05

באתרים

3,614.43

5,814.48

הוצאות עקיפות

1,540.--

סה"כ הוצאות לדירה 13,000.-- ל"י

הערות:

1. פרוטים לרכוז זה נתנו במכתב קודם מיום 19.1.70 בפרוט הנ"ל
נפלה טעות בחשוב העבודה הישירה בכית"ר וצ"ל 140 יום $\times 22.80$ ל"י = 3180 ל"י
(המספרים עוגלו).
2. חשוב ההוצאות העקיפות נעשה לפי ההוצאות הממשיות בתקופה 4.9.69
מחולקות למספר הדירות שנבנו באותה תקופה.

בכבוד רב,

חברת "ש ב ח"

070101

כתובת למכתבים
רמלה
ת.ד. 225

"ש ב ח"
חברה ליצור בתים להוכנה בע"מ

טלפון 961446
תאריך 19.1.70
מספר

הוצאות ישירות לדירה

ע כ ו ד ה			ח ו מ ר י מ			פרטים
סה"כ	כמות	מחיר ליחידה	סה"כ	כמות	מחיר ליחידה	בבית"ר
2,160.-	100 יום	21.60 ל"י	962.50	1.25 טון	770.- ל"י	ברזל
			295.05	7 יחידות		משקופים
			135.-			אומים וברגים
			420.-	30 קוב	14.- ל"י	אגרגטים
			407.50	8.25 טון	110.- ל"י	מלט
			105.-	1.2 קוב	87.- ל"י	חומרי בידוד
			75.-	30 ליטר	2.5.- ל"י	כימיקלים
<u>2,160.-</u>			<u>2,200.05</u>		סה"כ	
4,360.05						

עבודות גמר

321.70			25.-			סיח
378.-			471.53			אינסטלציה חשמלית
353.24			816.-			רצוף
47.-			931.-			הובלת מרצפות
			203.-	29 ל"י	7	חלונות ודלתות הזזה
210.-	30	7	100.-		1	חריסים
21.-			35.-		1/2	דלתות חמדיה
			170.-		1	ארונות מטבח
364.15						ארונות חשמל
180.68	15.78	מ"ר 11.45	30.-	2 ל"י	15 מ'	מאוררים
43.75	10	מ' 4,375				צבע
249.60						ציפוי גב
565.40						מעקות
			175.-			מוזיאקה
			40.-			צבע חוץ
			337.55			דוד חשמל
			12.50			ארון לדוד חשמל
			31.35			אינסטלציה סניטרית
			236.50			ארגזי מטבחים 4 לבית
						שיש
						ניקיון ושטות
<u>16.-</u>			<u>3,614.43</u>			סה"כ
7079.95			<u>5,814.48</u>			סה"כ כללי
11440						

1
 17.70
 647

647

17.70

הוצאת פאנאל להקמת חניה וזכוכ 500 וחצי צור בסך

הוצאת חשבון 17.70 (כספים) ~~הוצאת חשבון 17.70~~

1 (כספים) (חשבון)

1/1 פאנאל 500 וחצי צור להקמת חניה (כספים) (חשבון) 2 חשבון

2/2 חשבון חצי פאנאל (כספים) (חשבון) 2 חשבון

הוצאת חשבון 17.70 (כספים) (חשבון) 2 חשבון

3/3 פאנאל 2 חשבון (כספים) (חשבון) 2 חשבון

4/4 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

5/5 פאנאל 2 חשבון (כספים) (חשבון) 2 חשבון

6/6 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

7/7 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

8/8 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

9/9 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

10/10 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

11/11 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

12/12 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

13/13 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

14/14 חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

חשבון 2 חשבון (כספים) (חשבון) 2 חשבון

1b. interstitial mass adhesive non-retractile

8/1/19 3:45 PM 3/1/19 3:45 PM 3/1/19 3:45 PM

9/11/16 21.2v 2.02m 21.2v 2.02m

2

לשנת 1977

17.1.70

מחיר פאנאל לבקרת מים 500 ואינדיקטור לנקה אינדיקטור
עין תוכנית קאמל 11 - 11

2. אגרא עמאל 23 שולק 10 מ6

1101
4 14
110 10
110 35

2/1 חסות חס
2/2 " " " " " "
2/3 " " " " " "
2

\$ 11,000.00

מחיר קרן / וקמ 390 \$ סלח כולל 76

\$ 9,000.00

2/4 קרית, פונדציות, איגודים, תכנית איגודים

\$ 20,000

הם מחיר כל אגרא

\$ 250,000

13 ירח 12 אגרא 20,000 x 12

10,000

2/5 מחיר פחית פונדציות מחיר אגרא
2

\$ 260,000

3 אגרא קרית, פונדציות, איגודים, פקידים 4 מ6

\$ 8,000

מחיר אגרא כולל פונדציות

\$ 50,000

13 ירח 6 אגרא קרית 6 x 8,000

upl-f)

Year 200

1. Main purpose of the project is to study the effect of the new policy on the economy.

2. The project is divided into three parts.

1.1. The first part is to study the effect of the new policy on the economy.

1.2. The second part is to study the effect of the new policy on the economy.

1.3. The third part is to study the effect of the new policy on the economy.

1.4. The fourth part is to study the effect of the new policy on the economy.

1.5. The fifth part is to study the effect of the new policy on the economy.

2.1. The first part is to study the effect of the new policy on the economy.

2.2. The second part is to study the effect of the new policy on the economy.

2.3. The third part is to study the effect of the new policy on the economy.

2.4. The fourth part is to study the effect of the new policy on the economy.

2.5. The fifth part is to study the effect of the new policy on the economy.

3.1. The first part is to study the effect of the new policy on the economy.

3.2. The second part is to study the effect of the new policy on the economy.

3.3. The third part is to study the effect of the new policy on the economy.

3

חשבון 647 חשבו

7.170.

4. על ידי מכירת המניות המוחזקות ב-100 מניות
 אם המניה מחזיקה 3 שקלים (מחיר המניה יורד לשקל)

נחשבו 200 שקלים $\times$ 250 \$ = 50,000

- 30,000

- 10,000

\$ 40,000

200 $\times$ 300 \$ = 60,000
 מכירת המניות מחזיקה 300 שקלים (מחיר המניה יורד לשקל)
 200

\$ 15,000

5. על ידי מכירת המניות 300 מניות מחזיקות

6. מכירת המניות 100 מניות מחזיקות 10 שקלים

\$ 6,000

\$ 10,000

\$ 5,000

\$ 4,000

\$ 25,000

מכירת המניות מחזיקה 10 שקלים $\times$ 400 \$ = 40,000
 מכירת המניות מחזיקה 10 שקלים $\times$ 400 \$ = 40,000
 מכירת המניות מחזיקה 10 שקלים $\times$ 400 \$ = 40,000
 מכירת המניות מחזיקה 10 שקלים $\times$ 400 \$ = 40,000
 מכירת המניות מחזיקה 10 שקלים $\times$ 400 \$ = 40,000

\$ 75,000

25,000

100,000

100 מניות $\times$ 300 \$ = 30,000

מכירת המניות מחזיקה 300 שקלים

200

QFLE

date

from

to

to the ...
for ...
(...)

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

...

4

תשלום 647

מס' 17

17.1.70

\$ 10.000

7 מ' 811/101

\$ 10.000

17 מ' 811/101

811/101

\$ 30.000

811/101

10.000

812/101

\$ 40.000

812/101

9 מ' 811/101

\$ 25.000 -

811/101

\$ 15.000

812/101

\$ 5.000

813/101

\$ 15.000

814/101

\$ 10.000

815/101

\$ 2.000

816/101

\$ 2.000

817/101

\$ 6.000

818/101

\$ 2.000

819/101

\$ 7.000

8110/101

\$ 90.000

8111/101

10.000

8112/101

100.000

8113/101

2007 647 13/07

17.170

$$7 \text{ (51157) } 117$$

11/10/2021

11/7 פסל ברונזה למקדש ~~המזרחי~~ (המערבי) (אנטיגו)

לא ממונה

10.000

integrated bookshelves for home? 100
76W 5 inch 90 150

1000

1 \$1,000

80000

11/9

162

22

30,000

15,000

10.000

5. 000

10, 100, 1000

10. 000

\$ 80,000

20,000.

21360, 110 12

Final R/1

am 12/2

21/10 12/3

603,17 12/4

5/11/15 n/5

12/6 קו"כ

502

Analiza 13

Dimanche 25 Nov

602 31 1

000, 11

50

1.19 1.20

$\frac{1}{n} \sum_{i=1}^n x_i$

0022

U.S. Title

7

החשבון 647 מס' 17.170

17.170

הקצבה (13)

60.000	13 חודשים	14/1
50.000	2 חודשים	14/2
60.000	6 חודשים	14/3
20.000	(2+6) חודשים	14/14
10.000	5 חודשים	14/5
200.000	סה"כ	

17.1.70
 500 !

(וינתן כללי למי בלעו גלות ארץ ישראל)

17.1.70

16, מחקרים אצל נשים בגיל 250 ויותר, מחקרים אצל נשים בגיל 250 ויותר, מחקרים אצל נשים בגיל 250 ויותר.

(ווינקט אים אן אים צו פארלאזן)

והנחת כללם לזו כללם קטנות עם ונמצא ונמצא

17.1.70

הערכה הוצאות להקמת מפעל לייצור 500 יחידות דיור בספרד. הערכה זו מחוסר כל פרטים מבוססת על הנחות הבאות.

1. הנתונים החסרים

- 1.1 האם 500 יחידות דיור לשנה הוא במשמרת אחת או 2 משמרות.
- 1.2 מה היא יחידת הדיור הטיפוסית גודל, חלוקה לחדרים, אין שום נתונים מחוסר ברירה אקבל ליסוד החישובים יחידות דיור 70 מ² דומה לזו שאנו בונים.
- 1.3 האם זה צריך להיות מפעל לפירוק או קבוע. ייחשב בחור קבוע.
- 1.4 האם זה צריך להיות מפעל שדה בלי או עם בנין אחשב בלי בנין. מחיר בנין תלו מתנאים מקומיים יכול להתנודד בגבולות של 300 %.
- 1.5 האם קיימים במקום המפעל הספקת חשמל אחשב שקומת.
- 1.6 האם קיימים במקום המפעל הספקת מים וביוב אחשב שקימת.
- 1.7 האם קיימים כבישים מסביב המפעל אחשב שקיימת.
- 1.8 האם יש או אין מפעל להכנה בטון בסביבה. אחשב שיש ואתן הערכה לבנין מפעל כזה.
- 1.9 מה הם מחירי בנין ציוד, עבודות הקמה וכו' בספרד אין לי מושג. אקבל ביסוד החישובים מחירי הארץ לפני שנתיים היות ועכשיו אין מחירי עבודה בארץ כל אחד דורש מה שהוא רוצה.
- 1.10 מחירי הברזל הם עלו בארץ במשך שנה אחרונה עד 100% מה המצב בספרד לא ידוע לי אחשב מחיר הברזל ל- \$ 120 סונה שזה הוא בערך המחיר לפני שנתיים.
- 1.11 מחירי דודי קיטור, קומפרסורים ושאר הציוד היבוא חשמל למים. אחשב לפי המחירים שהיו בארץ לפני שנתיים.
- 1.12 האם אפשר לקנות רשתות זיון עם ריתוך נקודתי או לא. אתן הערכה לבנין מחלקה כזו להכנת רשתות בלי בנין.
- 1.13 עבודות אדמה ליסור מגרש, ניקוז כבישי גישה לא נכלל.
- 1.14 בנינו משרד ומחסנאות לא כלולים.
- 1.15 סנדריס אוטו-מובילים ומחסן כלים וחלקים רזרביים לא כלול.
- 1.16 ביטוח בהקמה לא כלולים.
- 1.17 מיסים עירוניים וממשלתיים לא כלולים.
- 1.18 לימוד עובדים על ידי נסיעה לארץ לא כלולים.
- 1.19 משלוח אנשי הארץ להקמת ^{המפעל} לא כלולים

חישוב הוצאות להקמה מפעל ל- 500 יחידות דיור לשנה במשמרת אחת
עיינן הערות קודמות מ- 1.1 - 1.11

2. תכנית גדולות עד לאורך של 10 מטר

2.1	משקל מסגרת חוץ	11 טון
2.2	משקל גופי הזזה	" 14
2.3	משקל גופי בינים	" 10
		35 טון

מחיר בנין והקמה \$ 320 טונה כולל ברזל

\$ 11,000 בסה"כ

2.4 קפיצים, הידרוליקה, ויברציה,

\$ 9,000

\$ 20,000 בסה"כ מחיר כל תכנית

יורשו 12 תכנית $20,000 \times 12$

\$ 250,000

2.5 מערכת הרחקה שאריות בשון מתחת לתכניות

\$ 10,000

\$ 260,000 בסה"כ

3. תכניות קטנות מדרגות, מחיצות, פקקים וכו' עד לאורך 4 מטר

מחיר תכנית כולל הידרוליקה

\$ 8,000

יורשו כ- 6 תכניות כאילו $6 \times 8,000$

\$ 50,000

4. גשר יציקה לתכניות גדולות באורך כ- 100 מטר

עם עליה מצד אחד בנוי מקונסטרוקציה

(אפשר לבנות מבטון יוחר זול).

המשקל 1,200 ק"ג למטר כולל עליה במחיר \$ 250 טונה

- 30,000

בסה"כ כ- 100 מטר $\times$ 300 \$

- 10,000

כסוי בשון מעקים מהצדדים מבטון

\$ 40,000 בסה"כ

5. גשר תכניות קטנות 30 מטר אורך עם עליה מצד אחד

\$ 15,000

6. מנוף ייצור הרמה 13 מטר רוחב 9 מטר גובה

\$ 6,000

משקל הקונסטרוקציה 15 טון $\times$ 400 \$

\$ 10,000

מרים 4 מטר לדקה הרמה

\$ 5,000

גלגלים גירים להנעה לאורך ורוחב

\$ 4,000

השמל ושונות

\$ 15,000 בסה"כ

\$ 75,000

יורשו 3 מנופים כאילו $25,000 \times 3$

\$ 25,000

פסים באורך 300 מטר

\$ 100,000 בסה"כ

THESE ARE THE ONLY TWO WHICH HAVE BEEN
 FOUND IN THE ENTIRE COLLECTION.

1. THE FIRST TWO OF THE

1.5 THE FIRST TWO
 2.5 THE FIRST TWO
 3.5 THE FIRST TWO
 4.5 THE FIRST TWO

THE FIRST TWO OF THE
 1.5 THE FIRST TWO
 2.5 THE FIRST TWO
 3.5 THE FIRST TWO
 4.5 THE FIRST TWO

2. THE FIRST TWO OF THE

THE FIRST TWO OF THE
 1.5 THE FIRST TWO
 2.5 THE FIRST TWO

3. THE FIRST TWO OF THE

THE FIRST TWO OF THE
 1.5 THE FIRST TWO
 2.5 THE FIRST TWO
 3.5 THE FIRST TWO
 4.5 THE FIRST TWO

4. THE FIRST TWO OF THE

THE FIRST TWO OF THE
 1.5 THE FIRST TWO
 2.5 THE FIRST TWO
 3.5 THE FIRST TWO
 4.5 THE FIRST TWO
 5.5 THE FIRST TWO
 6.5 THE FIRST TWO
 7.5 THE FIRST TWO
 8.5 THE FIRST TWO
 9.5 THE FIRST TWO

7. מנוף לרשתות זיון ¹טונה כ- \$ 10,000
 ידרש מנוף אחד כזה \$ 10,000

8. אחסון התוצרת

- 8.1 קונסטרקציות ובטון \$ 30,000
 8.2 מטדר לסיבוב רצפות \$ 10,000
 בסה"כ \$ 40,000

9. מחלקת רשתות זיון

- 9.1 מכונת ריתוך נקודתי עד 16 \$ 25,000
 9.2 מכונת ריתוך נקודתי עד 8 \$ 15,000
 9.3 מכונת פיתול \$ 5,000
 9.4 ²מנופים של 1 טון \$ 15,000
 9.5 24 עמדות ליצור גנטי זיון \$ 10,000
 9.6 מכונת וליתוך ברזל עגול \$ 2,000
 9.7 מכונת חיתוך שטוחים \$ 2,000
 9.8 פסים וקרוניות לטרנספורט \$ 6,000
 9.9 2 עגלות להעברת הרשתות למחלקת יציקה \$ 2,000
 9.10 סידורים שונים ורצפות בטון \$ 7,000
 בסה"כ \$ 90,000
 \$ 10,000
 בסה"כ \$ 100,000

פסים

10. מרכז בטון ¹המערבל עם הגרגטים בלי בנין

- 10.1 מאזני מערבלי עם יציקה חבור \$ 25,000
 10.2 סילוסים \$ 5,000
 10.3 סילו מלט \$ 3,000
 10.4 הספקה מים חמים \$ 3,000
 10.5 משטחים ¹לגרגטים יציקה בטון \$ 3,000
 10.6 טרקטור מעמים \$ 15,000
 10.7 2 מערבלים 6 טון \$ 50,000
 10.8 חשמל \$ 3,000
 10.9 סידורי מנומטיקה \$ 2,000
 10.10 שונות \$ 6,000
 בסה"כ \$ 115,000

11. אולם מכונות

\$ 20,000	11.1 2 דודי קיטור ¹ טונה לשעה 6 ק"ג/ס"מ
\$ 3,000	11.2 מוריד לחץ עם ברכות ל- 0.25 ק"ג/ס"מ
\$ 10,000	11.3 2 קומפרטורים 40 כ"ס
\$ 10,000	11.4 1 דיזל - קומפרטור 150 כ"ס
\$ 5,000	11.5 לוח חשמל ראשי
\$ 5,000	11.6 חיבור חשמל
\$ 10,000	11.7 ^{ביצ} גנרטור למקרה הפסקה בהספקת חשמל 100 עם מנתקים
\$ 10,000	11.8 ^ר בנין מעל לדודים ולוחות חשמל וקומפרטור 150 מ' גובה 5 מטר
\$ 7,000	11.9 שונות
\$ 80,000	בסה"כ

12. אינסטלציות

\$ 30,000	12.1 חשמל
\$ 15,000	12.2 מים
\$ 10,000	12.3 אויר
\$ 5,000	12.4 קונדנסט
\$ 10,000	12.5 ניקוז
\$ 10,000	12.6 קיטור
\$ 80,000	בסה"כ

13. רצפות בטון וכבישים

לא כולל עבודות הדמה

14. ה ק מה

\$ 60,000	14.1 2 מנופי הקמה 13 מטר רוחב 18 מטר גובה
\$ 50,000	14.2 2 מופים להובלת החוצרת מהמפעל לבנין המוקם
\$ 60,000	14.3 6 טריילרים של 50 טון ^{הא}
\$ 20,000	14.4 משטחים וקונסטרוקציות להובלת קורות ורצפות (2x6)
\$ 10,000	14.5 סידורים ועבודות גמר מוטות, מותכי ברגים וכו'
\$ 200,000	בסה"כ

15. ריכוז הוצאות להקמת מפעל ל- 500 יחידות דיור לשנה במשמרת אחת.

\$ 260,000	15.1 חבניות גדולות עי/ סעיף 2
50,000	15.2 6 " " קטנות 3
40,000	15.3 גשר יציקה לתבניות גדולות 4
15,000	15.4 גשר יציקה לתבניות קטנות 5
100,000	15.5 3 מנופי ייצור 6
10,000	15.6 1 מנוף לרשתות זיון 7
40,000	15.7 איחסון 8
100,000	15.8 מחלקת רשתות זיון 9
115,000	15.9 מרכז בטון 10
80,000	15.10 אולם מכונות 11
80,000	15.11 אינסטלציה 12
20,000	15.12 רצפות וכבישים 13
200,000	15.13 הקמה 14
1,120,000	בסה"כ
110,000	10% תכנון והשגחה
\$ 1,230,000	סה"כ כללי

הרכבה של כל יחידה ויחידה כלולות במחיר הרכבה כללית לא כלולה חלופה בחנאים מקומיים.

16. במקרה ורוצים להקים מפעל ל- 250 יחידות דיור למשמרת ההוצאות יהיו:

\$ 150,000	16.1 6 חבניות גדולות
30,000	16.2 3 חבניות קטנות
25,000	16.3 גשר יציקה 50 מטר אורך לתבניות גדולות
10,000	16.4 גשר יציקה 20 מטר אורך לתבניות קטנות
70,000	16.5 2 מנופים 10 טון
10,000	16.6 1 מנוף רשתות זיון
30,000	16.7 איחסון
80,000	15.8 מחלקת רשתות זיון
100,000	15.9 מרכז בטון
60,000	16.10 אולם מכונות
60,000	16.11 אינסטלציה
15,000	16.12 ריצוף וכבישים
150,000	16.13 הקמה
90,000	בסה"כ
\$ 890,000	10% תכנון והשגחה
	סה"כ כללי

הרכבה של כל יחידה כלולה הרכבה כללית לא כלולה קשורה עם החנאים המקומיים.

13. 1950-1951 season - 100% of the total area.

1.01	100%	100,000
2.01	100%	100,000
3.01	100%	100,000
4.01	100%	100,000
5.01	100%	100,000
6.01	100%	100,000
7.01	100%	100,000
8.01	100%	100,000
9.01	100%	100,000
10.01	100%	100,000
11.01	100%	100,000
12.01	100%	100,000
13.01	100%	100,000
14.01	100%	100,000
15.01	100%	100,000
16.01	100%	100,000
17.01	100%	100,000
18.01	100%	100,000
19.01	100%	100,000
20.01	100%	100,000
21.01	100%	100,000
22.01	100%	100,000
23.01	100%	100,000
24.01	100%	100,000
25.01	100%	100,000
26.01	100%	100,000
27.01	100%	100,000
28.01	100%	100,000
29.01	100%	100,000
30.01	100%	100,000
31.01	100%	100,000
32.01	100%	100,000
33.01	100%	100,000
34.01	100%	100,000
35.01	100%	100,000
36.01	100%	100,000
37.01	100%	100,000
38.01	100%	100,000
39.01	100%	100,000
40.01	100%	100,000
41.01	100%	100,000
42.01	100%	100,000
43.01	100%	100,000
44.01	100%	100,000
45.01	100%	100,000
46.01	100%	100,000
47.01	100%	100,000
48.01	100%	100,000
49.01	100%	100,000
50.01	100%	100,000
51.01	100%	100,000
52.01	100%	100,000
53.01	100%	100,000
54.01	100%	100,000
55.01	100%	100,000
56.01	100%	100,000
57.01	100%	100,000
58.01	100%	100,000
59.01	100%	100,000
60.01	100%	100,000
61.01	100%	100,000
62.01	100%	100,000
63.01	100%	100,000
64.01	100%	100,000
65.01	100%	100,000
66.01	100%	100,000
67.01	100%	100,000
68.01	100%	100,000
69.01	100%	100,000
70.01	100%	100,000
71.01	100%	100,000
72.01	100%	100,000
73.01	100%	100,000
74.01	100%	100,000
75.01	100%	100,000
76.01	100%	100,000
77.01	100%	100,000
78.01	100%	100,000
79.01	100%	100,000
80.01	100%	100,000
81.01	100%	100,000
82.01	100%	100,000
83.01	100%	100,000
84.01	100%	100,000
85.01	100%	100,000
86.01	100%	100,000
87.01	100%	100,000
88.01	100%	100,000
89.01	100%	100,000
90.01	100%	100,000
91.01	100%	100,000
92.01	100%	100,000
93.01	100%	100,000
94.01	100%	100,000
95.01	100%	100,000
96.01	100%	100,000
97.01	100%	100,000
98.01	100%	100,000
99.01	100%	100,000
100.01	100%	100,000

14. 1952-1953 season - 100% of the total area.

1.02	100%	100,000
2.02	100%	100,000
3.02	100%	100,000
4.02	100%	100,000
5.02	100%	100,000
6.02	100%	100,000
7.02	100%	100,000
8.02	100%	100,000
9.02	100%	100,000
10.02	100%	100,000
11.02	100%	100,000
12.02	100%	100,000
13.02	100%	100,000
14.02	100%	100,000
15.02	100%	100,000
16.02	100%	100,000
17.02	100%	100,000
18.02	100%	100,000
19.02	100%	100,000
20.02	100%	100,000
21.02	100%	100,000
22.02	100%	100,000
23.02	100%	100,000
24.02	100%	100,000
25.02	100%	100,000
26.02	100%	100,000
27.02	100%	100,000
28.02	100%	100,000
29.02	100%	100,000
30.02	100%	100,000
31.02	100%	100,000
32.02	100%	100,000
33.02	100%	100,000
34.02	100%	100,000
35.02	100%	100,000
36.02	100%	100,000
37.02	100%	100,000
38.02	100%	100,000
39.02	100%	100,000
40.02	100%	100,000
41.02	100%	100,000
42.02	100%	100,000
43.02	100%	100,000
44.02	100%	100,000
45.02	100%	100,000
46.02	100%	100,000
47.02	100%	100,000
48.02	100%	100,000
49.02	100%	100,000
50.02	100%	100,000
51.02	100%	100,000
52.02	100%	100,000
53.02	100%	100,000
54.02	100%	100,000
55.02	100%	100,000
56.02	100%	100,000
57.02	100%	100,000
58.02	100%	100,000
59.02	100%	100,000
60.02	100%	100,000
61.02	100%	100,000
62.02	100%	100,000
63.02	100%	100,000
64.02	100%	100,000
65.02	100%	100,000
66.02	100%	100,000
67.02	100%	100,000
68.02	100%	100,000
69.02	100%	100,000
70.02	100%	100,000
71.02	100%	100,000
72.02	100%	100,000
73.02	100%	100,000
74.02	100%	100,000
75.02	100%	100,000
76.02	100%	100,000
77.02	100%	100,000
78.02	100%	100,000
79.02	100%	100,000
80.02	100%	100,000
81.02	100%	100,000
82.02	100%	100,000
83.02	100%	100,000
84.02	100%	100,000
85.02	100%	100,000
86.02	100%	100,000
87.02	100%	100,000
88.02	100%	100,000
89.02	100%	100,000
90.02	100%	100,000
91.02	100%	100,000
92.02	100%	100,000
93.02	100%	100,000
94.02	100%	100,000
95.02	100%	100,000
96.02	100%	100,000
97.02	100%	100,000
98.02	100%	100,000
99.02	100%	100,000
100.02	100%	100,000

15. 1954-1955 season - 100% of the total area.



**Government of Israel
Investment and Export Authority**

Midwest Office

936 NORTH MICHIGAN AVENUE
CHICAGO, ILLINOIS 60611

כ"ט בטבת תש"ל
7 בינואר 1970

אל: מר י. גור אריה, ח-א.
מאת: מ. גורפונג, שיקגו.

הנדון: מר הנסון - בניה טרומית

בהתאם לבקשתך שוחחתי עם מר הנסון.

1. לדברי מר הנסון, מהחומר שקבל אודות שיטתו של ד"ר סלביץ קשה לו לחוות דעה על השיטה.
2. מהמעט שלמד מהחומר שקיבל אינו רואה את היהירות בהשואה לשיטות האירופאיות השונות.
3. כלליה לגבי השוק האמריקאי.
משרד השכון בארה"ב נמצא עתה בתהליך הסוסי של בחירה מספר שיטות בניה אותן תאמץ הממשלה הפדרלית. כרגע נשארו 8 מתוך 20 שיטות שנופו עוד קודם לכן. השיטות שחברתנו ע"י הממשלה הפדרלית חיינה השיטות שללא ספק תקבענה את המבמות בשטח הבניה, לפחות בעתיד הנראה לעין.
לדברי מר הנסון, מחכים עתה לתוצאות הסופיות שתקבענה תוך חצי שנה עד שנה. גם אם אחת השיטות שתאומץ תהיה הבניה הטרומית, חשוב לדעת כמה מהבניה תעשה בבית החרושת (כיום קימת התנגדות גדולה מצד האיגודים המקצועיים לכך שעבודות האינסטלציה, החשמל וכו' תעשה במפעל ותח מחיבים מסירתן לקבלני משנה במקום הבניה). באם אמנם תאומץ שיטה שכל או מרבית העבודות תעשה במסגרת ביהח"ר ובאם שיטתו של ד"ר סלביץ אמנם תצביע על חסכון בהשואה לשיטות אחרות, יהיה לה, לדעת מר הנסון, סכוי.
4. לסכום.
מר הנסון מבקש חומר יותר מפורט מזה שקיבל על מנת שיוכל לחוות דעה על השיטה עצמה. באשר לסכויי החדוה לשוק, גם בהנחה שהשיטה טובה, מוקדם עדין לחוות דעה.
5. אני חייב להוסיף שמר הנסון הביע חמיהה על כך שבמסמכך נענה על פניה שנעשתה באפריל במטרה לקשר עם יצרנים טרם נסיעתו לארץ.

בברכה

מ. גורפונג

מר א. קריתי, י-ס.
העמק: מר ב. ברוק, י-ס.
מר ה. אשכנזי, משרד השיכון, ח-א.



Government of Israel
Investment and Export Authority

Head Office
335 NORTH MICHIGAN AVENUE
CHICAGO, ILLINOIS 60611

TELEPHONE (312) 462-4334
FAX (312) 462-4334

Dear Sirs,
Reference is made to your letter of the 12th of May 1988.

REPLY TO YOUR LETTER OF THE 12TH OF MAY 1988

1. In reply to your letter of the 12th of May 1988.

2. In reply to your letter of the 12th of May 1988, regarding the matter of the 12th of May 1988.

3. In reply to your letter of the 12th of May 1988, regarding the matter of the 12th of May 1988.

4. In reply to your letter of the 12th of May 1988, regarding the matter of the 12th of May 1988.

5. In reply to your letter of the 12th of May 1988, regarding the matter of the 12th of May 1988.

6. In reply to your letter of the 12th of May 1988, regarding the matter of the 12th of May 1988.

Yours faithfully,

Director

cc: Mr. [Name] - [Address]

cc: Mr. [Name] - [Address]

07 0101

H. Slavin
Consulting Engineer
43 Frishman str.,
Tel-Aviv, Israel
Phone 239518

SLAVIN PROCESS - MECHANISED PRODUCTION OF PREFABRICATED R.C.
ELEMENTS FOR INDUSTRIAL BUILDINGS AND HOUSING PROJECTS

General description

- 1/1 The concrete mix is supplied from a standard batching plant (outside or on-the-spot) and casted directly into steam-heated vertical forms, operated hydraulically.
 - 1/2 The slab is ready in about 4 hours for dismantling and storage or despatching to the site, with the aid of a portal crane.
 - 1/3 After dismantling, the forms are cleaned and oiled and reinforcement assemblies are mounted with the aid of an overhead crane. (In the case of housing-units slabs, inserts for doors, windows, wiring, piping etc., are also installed). The form is ready for the next casting in about one hour.
 - 1/4 If the slabs are not despatched immediately, they are stored with the aid of cranes at 50cm ($1\frac{1}{2}$ ft) spacing, and all preparatory operations are carried out if necessary.
 - 1/5 Delivery to the site is by trailer. A special erection crane is used. Elements are joined by bolting to nuts welded to the reinforcement.
 - 1/6 After the erection, the structure is ready for the finishing operation.
2. Technical description of process for plant with output of 4 housing units
(100 m^2 floor area (1000 sq. ft.), or 1200 sq. m^2 slab surface) per shift.
- 2/1 The mix is delivered in truck mixers, preferably of 9 m^3 (12 cu. yd.) capacity.
 - 2/2 As seen from the drawing, the truck is driven on to a bridge 2.8 m (about 9 ft.) wide, and the mix is discharged through a chute into the forms arranged on both sides of the bridge.
 - 2/3 The discharge time for a full mixer charge is up to 15-20 minutes.
 - 2/4 No special arrangements are required in the mixers. Any standard mixer truck may be used, so that a mechanical breakdown need not interfere with the operation.
 - 2/5 The vertical form is designed for two slabs, size $10 \times 3 \text{ m}$ ($33 \times 10 \text{ ft}$), surface area 30 m^2 (300 sq. ft.), volume 4.5 m^3 (6 cu. yd.), weight 11 tons. concrete thickness 10 - 25 cm (4" - 10").

1. 10
2. 10
3. 10
4. 10
5. 10
6. 10
7. 10
8. 10
9. 10
10. 10

THE PROPOSED - THE PROPOSED - THE PROPOSED
THE PROPOSED - THE PROPOSED - THE PROPOSED

THE PROPOSED - THE PROPOSED - THE PROPOSED

1. The proposed - The proposed - The proposed
2. The proposed - The proposed - The proposed
3. The proposed - The proposed - The proposed
4. The proposed - The proposed - The proposed
5. The proposed - The proposed - The proposed
6. The proposed - The proposed - The proposed
7. The proposed - The proposed - The proposed
8. The proposed - The proposed - The proposed
9. The proposed - The proposed - The proposed
10. The proposed - The proposed - The proposed

1. The proposed - The proposed - The proposed
2. The proposed - The proposed - The proposed
3. The proposed - The proposed - The proposed
4. The proposed - The proposed - The proposed
5. The proposed - The proposed - The proposed
6. The proposed - The proposed - The proposed
7. The proposed - The proposed - The proposed
8. The proposed - The proposed - The proposed
9. The proposed - The proposed - The proposed
10. The proposed - The proposed - The proposed

1. The proposed - The proposed - The proposed
2. The proposed - The proposed - The proposed
3. The proposed - The proposed - The proposed
4. The proposed - The proposed - The proposed
5. The proposed - The proposed - The proposed
6. The proposed - The proposed - The proposed
7. The proposed - The proposed - The proposed
8. The proposed - The proposed - The proposed
9. The proposed - The proposed - The proposed
10. The proposed - The proposed - The proposed

- 2/6 A reasonable size of the form battery is 10 units each side of the bridge, i.e. a total of 20.
- 2/7 This requires a bridge 150 m long, 4 m high and 3.2m wide (500x14x11 ft).
- 2/8 The bridge may be built of steel profiles or concrete slabs, according to local conditions.
- 2/9 Access to the bridge is via a ramp (at one or both ends), slope 8%, length 50m.
- 2/10 Casting is accomplished by air vibration, 2-4 vibrators per form.
- 2/11 The vibrators may be driven by stationary or mobile compressors. 2 diesel compressors (200 HP) are required.
- 2/12 Superheated steam for heating the forms is supplied from a boiler at 6 Kg/cm² pressure (100 psi), output 5-6 ton/hour, steam temperature 115°C, discharge pressure 1/4 kg/cm² (240°F, 4 psi).
- 2/13 The hydraulic drive for the forms requires 3 tons of oil and pumps of the order of 20 HP, pressure up to 100 kg/cm² (1500 psi).
- 2/14 Portal cranes for dismantling - capacity 15 ton, width (between rail centerlines) about 13 m (44 ft.), height 9m (30 ft), travelling speed 60 m/min (200ft/min). The crane may have one or two transverse tracks, protruding about 6m on either side (20 ft.), i.e. an overall top width of 25 m. Weight of crane - 40 ton. Drive . diesel generator or electric current supply.
- 2/15 The slab storage space, or crane traverse, depend on local conditions. Generally 1m traverse corresponds to a space for five 10m slabs. A reasonable traverse is 20m, i.e. 1000 slabs or the output of 25 single-shift or 8 three-shift days. Number of cranes required 2 - 3 for production, 1 - 2 for loading and despatching. (Total 3 - 5).
- 2/16 In the case of industrial buildings, no special arrangements are required except for a single 1 ton portal crane.
- 2/17 The complete plants requires:
- | | |
|--------------------------|---|
| Water supply piping; | Condensate installation; |
| Air supply piping; | Transit storage space (if required); |
| Electrical installation; | Waste concrete disposal; |
| Hydraulic installation; | Water-curing facilities (if steam is not used); |
| Steam Installation; | Floor turntable; |

3. Additional equipment for housing-unit slabs

- 3/1 20 large two-slab forms (floor and wall slabs), output 5 units (100 sq.m. floor area) per shift, or 15 units in three shifts.

The first of these is the fact that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

It is also true that the...

3/2 Second bridge (about 100 m long) for 20 small forms up to 5m (17 ft) long each, for elements (partitions, staircases, balustrades, balconies etc.), totalling about 500m^2 , 2m^3 or 5 ton each.

3/3 This calculation is based on local design experience, according to which the total element surface area equals 3 times the floor areas. Accordingly, five 100m^2 (1000 sq. ft.) housing units requires 1500m^2 elements as follows:

$$20 \times 50 = 1000\text{m}^2 \text{ large elements}$$

$$20 \times 25 = 500\text{m}^2 \text{ small elements.}$$

3/4 2 additional 10 ton portal cranes for dismantling and loading.

3/5 Housing elements involve considerable labour and space requirements for preparing inserts for the windows and doors, wiring and piping, assembly nuts etc., running into hundreds of items per unit. The size of the department depends on requirements; special spot-welding equipment is needed, and standard reinforcement cannot be used. The order or magnitude of the required space is estimated at $5000\text{--}6000\text{m}^2$ under 1-ton cranes, and at least 50 stations for reinforcement assemblies.

3/6 It is possible to cast 4 types of flats during one day work, and 8 types of flats with few days stop.

4. The plant may be set up in a number of forms, some of them basic:

4/1 A mobile field plant, without a shed. In these circumstances there is only a limited possibility of working in winter, and the local climate is an important factor.

4/2 A permanent plant with all the equipment housed in a shed, permitting work in any weather.

4/3 The equipment may be installed so as to permit dismantling and transportation in consignments not exceeding 15 tons (within the limits of crane capacity and road width).

4/4 The cost of the shed is 30% (or more) of that of the equipment.

4/5 In order to avoid misunderstanding, the possibility of moving the plant is considered after 3-4 years; the cost of moving is assumed as 25% of the investment.

5. Economic considerations

5/1 The investment in a 20-form plant (5 units per shift) depends largely on local conditions, but a reasonable idea is \$1.25 - 1.5 million.

5/2 In the case of on-the-spot mix production, a 200m^3 daily output requires 2 batching plants and 6 workers.

... ..
... ..
... ..

... ..
... ..
... ..
... ..
... ..

... ..
... ..
... ..
... ..
... ..
... ..
... ..
... ..
... ..
... ..

... ..
... ..
... ..
... ..

... ..

... ..
... ..
... ..

... ..
... ..
... ..

... ..
... ..
... ..
... ..
... ..

- 5/3 Mix transportation to bridge - 2 workers.
- 5/4 Discardage of mix - 10 workers.
- 5/5 Preparation of reinforcement assemblies for slabs only - 5 workers. (Total for 5 units - 50 workers).
- 5/6 Crane operators - 15 workers.
- 5/7 Preparations of forms for casting - 10 workers.
- 5/8 Repairs and cleaning (depending on conditions) - about 15 workers.
- 5/9 Small forms - 35 workers.
- 5/10 Steam boiler and maintenance - 10 workers.
- 5/11 Administration - 10 workers.
- Total, for industrial buildings - 80 workers.
- Total, for housing (5 units per shift) - 160 workers.

6. Erection

- 6/1 In the case of industrial buildings no general description is possible.
- 6/2 In the case of housing projects, much depends again on site conditions, transportation facilities, building-code requirements etc. It can be stated that under conditions similar to those in Israel, 5 erection cranes (portal or other type) are required for 5 units per day, 18-20 runs per crane.
- 6/3 Transportation of the elements for one housing unit requires 3 trailer runs. Assuming $1\frac{1}{2}$ runs per day, the 5 units require ten 50-ton trailers (horse- or tractor-drawn, according to the distance between plant and erection site.).
- 6/4 A special erection technique, similar to that of steel construction, obviates the need for temporary scaffolding.
- 6/5 Elastic seals, tightened by bolts, keep out rainwater.
- 6/6 The erection crane is served by a crew of four. Erection time per unit may be assumed as 12-14 hours.
- 6/7 Measuring, marking and sealing crew - about 4 workers per unit.
- 6/8 Joint filling, grinding and strengthening operations depend on requirements - order of magnitude 10-15 workdays per unit.
- 6/9 Finishing work is usually farmed out to subcontractors, and no guidelines can be laid down unless local conditions and finishing type are known.

1. The first part of the document is a letter from the President of the United States to the Congress, dated January 3, 1862. It contains a report on the state of the Union and the progress of the war against the rebellion. The President mentions the recent victories of the Union forces and expresses confidence in the ultimate success of the cause. He also discusses the financial and military challenges facing the Union and requests the Congress's support in meeting these needs. The letter is signed by Abraham Lincoln.

2. The second part of the document is a report from the Secretary of the War to the President, dated January 10, 1862. It provides a detailed account of the military operations and the status of the Union's forces. The report mentions the recent battles of Fort Mifflin and Fort Mifflin, and the successful capture of the forts. It also discusses the progress of the Union's military preparations and the need for additional resources. The report is signed by General Winfield Scott.

מסדר השיכון

29.10.69

הקריה

א ל: א. אלוואיל

מאת: ע. בן צבי

הנדון: מצב היצור בביתח"ר שבה.

ביום א' 26 באוקטובר ביקרתי בביתח"ר באחרי הבניה ונוכחתי בשעה יציקת הבטון בנוכחות מנהל המפעל, ד. טרנה מחברת הכנון, מהנדסי המחוז אברמוביץ ורון ואחר כך נפגשתי עם הסמנכ"ל הלל אשכנזי.

הדיון נטב על הצעתו של מנהל המחוז מר מרכוס לסגור את ביתח"ר שבה. הדעה הכללית היתה שאסנם אין אפשרות להרשות שהמפעל ימשיך בשיטות העבודה הנוכחיות אולם מקוים שאפשר למצא דרך להבראת המצב.

המחלה העיקרית של המפעל היא עצם היציקה של הבטון. יוצקים בטון דליל לחוך בטירות אנכיות המחזירות אל ויברטור. כתוצאה, כמובן הויברטור גורם סגרגציה לבטון וכתוצאה, הצורה העלובה של המוצרים. למעשה המנהל משתמש בויברטור להובלת הבטון בתוך הדפוסים בלבד, בזאת הוא לכאורה חוסך בכח אדם וכמובן מקלקל את הבטון.

הנסיון מלמד שאין לצקת בבטירות אלמנטים בצורת טנדויסט, הויברטורים האחדים על החבניה אינם יעילים במידה מטפיק ובמחט אי אפשר להשתמש בצורה זו.

המוצא היחידי הנראה לי הוא:

1. להפסיק מיד את יצור האלמנטים של הקירות בצורה הנוכחית ולבצע את ההזמנה בכניה שגרהית.
2. להמשיך ביצור הקירות והמחיצות בתנאי שהבטון יהיה בקונסיסטנציה מתאימה לויברציה בהדרכה מקצועית של מומחים מהטכניון.
3. להכניס את בית החרושת ושיטת היצור ולנסות את השיטות החדשות ביצור נסיוני עד שיגיעו לתוצאות האיכות הנדרשת.
4. קבעתי פגישה עם מר ד. טרנה חבר הנהלת שבה ליום א' 2 בנובמבר, ברצוני להעלות הצעה זו לדיון.

ב ב ר כ ה
lr

ע. בן צבי

לכבוד

הנהלת "רסקו"

הנדון: הערות בקשר לטכנולוגיה של ייצור בתי מגורים לפי שיטת מהנדס סלבין

בהתאם לבקשתכם בדקתי את הטכנולוגיה של שיטת סלבין ובוזה הנני מביא את חוות דעתי המפורטת בארבעת הסעיפים דלהלן:

- (1) טכנולוגיה ;
- (2) ציוד ותבניות ;
- (3) כלכליות ;
- (4) הצעה.

(1) טכנולוגיה

השיטה שונה בחלית מאלה המוכרות באירופה באופן עקרוני היא מחאימה ביותר לחרושת הבטון הטרם ויש בה חדושים מהפכניים בהשוואה לשיטות המקובלות.

יתרונות

- 1.1 חסול חלק גדול, באופן יחסי מהעבודה הבלתי נמנית.
- 1.2 השגת דיוק מכסימלי באלמנטים הטרומיים.
- 1.3 ייצור האלמנטים הוא באופן אנכי ועל ידי כך חוסכים הרבה תנועות מיותרות.
- 1.4 ישנה אפשרות לקבוע באופן רצוני את מספר, מקום וגודל הפתחים, כמו כן אפשר לשנות אורכי האלמנטים.
- 1.5 צמצום רב בעבודות הגמר במקום הבניה, כי רוב עבודות הגמר כגון: הרכבת נגרות, אינסטלציה סניטרית וחשמלית, רצוף וכו' נעשות בביהח"ר; ע"י כך חוסכים במספר הפועלים וקבלני משנה במקום העבודה ומאפשרים ארגון יעיל והקטנת זמן העבודה במקום.

סמכות

- 1.6 ביציקת אלמנט בגודל -20 מ"ר (אורך -8, גובה 2.50 מ' או 2.80 מ') אינני בטוח שהרטוב שווה בכל השטח ושפני השטח יהיו לגמרי חלקים. השגת שטח חלק בד-בבד עם חוזק בטון אחיד, היא בעיה די קשה של הנדסה וטכנולוגיה הבטון.

11.11.11

11.11.11

11.11.11

11.11.11

- 1) 11.11.11
- 2) 11.11.11
- 3) 11.11.11
- 4) 11.11.11

11.11.11

11.11.11

11.11.11

- 1.1) 11.11.11
- 2.1) 11.11.11
- 3.1) 11.11.11
- 4.1) 11.11.11
- 5.1) 11.11.11

11.11.11

- 1.1) 11.11.11

פרוט הסעיף 1.6

1.6.1 באקלים שלנו קשה לקבוע ולהבטיח את מקדם מים-צמנט וזרובת נכונה של הבטון, אפילו אם גודל וטיב האגרגטים אינו משתנה. לפי הנסיון, בית - חרושת שאין לו מחצבה משלו, אינו יכול להבטיח זרובת אחידה של האגרגטים. באלמנטים הגבוהים הנ"ל מרחק בין הזיון והתבנית קטן ואם נכנסת אבן יותר גדולה מאשר המתוכנן, אזי מתחת לאבן נשאר מקום ריק עד תחתית האלמנט.

1.6.2 לרטוט יש בדרך כלל שלוש מטרות :

- א. העברת הבטון ממקום למקום בתבנית ;
- ב. הדוק הבטון ;
- ג. ייצור שטח חלק בצדי התבנית.

לכל אחת מפעולות אלה יש צורך ברטוט שונה. אם כן, יש הכרח להתאים את כל שלוש הפעולות וזאת בעיה רצינית, בגובה כזה של אלמנט. יש חשש שבתוך גובה כזה, הזרובת תחלק בשכבות שונות בגלל משך הרטוט הארוך וגם בגלל נפילת הבטון מהסרט הנע עד תחתית התבנית.

התאמת זרובת הבטון ושטח הרטוט הם היסוד להצלחת השיטה בכללה. ביקשתי ממר סלבין להיות נוכח בנסיון או לראות אלמנט מוכן שבוצע לפי השיטה הנ"ל. התשובה הייתה כי הנסיון הצליח, אבל מר סלבין לא יכול להראות את האלמנט, מפני שהתבנית הנסיונית בנויה בצורה סגורה ואי אפשר היה להוציא את האלמנט בשלמותו.

1.6.3 הסרט הנע נותן אפשרות של אחסון אלמנטים מוכנים עבור 7 ימי עבודה ייצור. במקרה ויש תקלה במקום מסויים, אזי נגרמת סחימה לכל הייצור אחרי שבוע ימים. אפילו במקרה שספק הנגרות לא עומד בהתחייבויות הזמן או שטח מקום הבניה אינו כוכן בזמן וגם תקלה במזג האוויר יכולים לגרום להפסקת על הייצור. לפי דברי מר סלבין, ההשקעה לתכניתו היא של 2 מליון ל"י כולל אחסון מינימלי של שבוע ימים כנ"ל. במקרה ורוצים להגדיל את אחסון האלמנטים, יש צורך בתוספת השקעה של בערך - 200,000 ל"י. לפי דעתי אסור לבנות בית חרושת בלי אחסון מינימלי של שלשה שבועות.

2. ציוד ותבניות

עיינתי בחופרת המצורפת של הציוד, אבל לא במובן מצב מכני של הציוד עצמו, אלא במובן שרות הציוד לטכנולוגיה של הייצור.

UNITED STATES DEPARTMENT OF AGRICULTURE

[illegible]

2.1.1) *Group Theory of Algebraic Groups* : -

4. REPORT YOUR OWN RESEARCH

2. THEORETICAL BACKGROUND

2. FAZT SON DER DEUT. UND FR.

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific information required.

[illegible]

10. The above information was obtained from the records of the [redacted] and is being furnished to you for your information only. It is not to be used for any other purpose without the express written consent of the [redacted].

POWELL JOHN DE GEORGE, JR., was an officer of the New York Air Guard.

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED

накладено. 2000.

(L.O.T.) Sample size must be between 30 and 100 unless otherwise stated with γ for normal approx.

[illegible]

1950. 1951. 1952. 1953. 1954. 1955. 1956. 1957. 1958. 1959. 1960. 1961. 1962. 1963. 1964. 1965. 1966. 1967. 1968. 1969. 1970. 1971. 1972. 1973. 1974. 1975. 1976. 1977. 1978. 1979. 1980. 1981. 1982. 1983. 1984. 1985. 1986. 1987. 1988. 1989. 1990. 1991. 1992. 1993. 1994. 1995. 1996. 1997. 1998. 1999. 2000. 2001. 2002. 2003. 2004. 2005. 2006. 2007. 2008. 2009. 2010. 2011. 2012. 2013. 2014. 2015. 2016. 2017. 2018. 2019. 2020. 2021. 2022. 2023. 2024. 2025. 2026. 2027. 2028. 2029. 2030. 2031. 2032. 2033. 2034. 2035. 2036. 2037. 2038. 2039. 2040. 2041. 2042. 2043. 2044. 2045. 2046. 2047. 2048. 2049. 2050. 2051. 2052. 2053. 2054. 2055. 2056. 2057. 2058. 2059. 2060. 2061. 2062. 2063. 2064. 2065. 2066. 2067. 2068. 2069. 2070. 2071. 2072. 2073. 2074. 2075. 2076. 2077. 2078. 2079. 2080. 2081. 2082. 2083. 2084. 2085. 2086. 2087. 2088. 2089. 2090. 2091. 2092. 2093. 2094. 2095. 2096. 2097. 2098. 2099. 2100. 2101. 2102. 2103. 2104. 2105. 2106. 2107. 2108. 2109. 2110. 2111. 2112. 2113. 2114. 2115. 2116. 2117. 2118. 2119. 2120. 2121. 2122. 2123. 2124. 2125. 2126. 2127. 2128. 2129. 2130. 2131. 2132. 2133. 2134. 2135. 2136. 2137. 2138. 2139. 2140. 2141. 2142. 2143. 2144. 2145. 2146. 2147. 2148. 2149. 2150. 2151. 2152. 2153. 2154. 2155. 2156. 2157. 2158. 2159. 2160. 2161. 2162. 2163. 2164. 2165. 2166. 2167. 2168. 2169. 2170. 2171. 2172. 2173. 2174. 2175. 2176. 2177. 2178. 2179. 2180. 2181. 2182. 2183. 2184. 2185. 2186. 2187. 2188. 2189. 2190. 2191. 2192. 2193. 2194. 2195. 2196. 2197. 2198. 2199. 2200. 2201. 2202. 2203. 2204. 2205. 2206. 2207. 2208. 2209. 2210. 2211. 2212. 2213. 2214. 2215. 2216. 2217. 2218. 2219. 2220. 2221. 2222. 2223. 2224. 2225. 2226. 2227. 2228. 2229. 2230. 2231. 2232. 2233. 2234. 2235. 2236. 2237. 2238. 2239. 2240. 2241. 2242. 2243. 2244. 2245. 2246. 2247. 2248. 2249. 2250. 2251. 2252. 2253. 2254. 2255. 2256. 2257. 2258. 2259. 2260. 2261. 2262. 2263. 2264. 2265. 2266. 2267. 2268. 2269. 2270. 2271. 2272. 2273. 2274. 2275. 2276. 2277. 2278. 2279. 2280. 2281. 2282. 2283. 2284. 2285. 2286. 2287. 2288. 2289. 2290. 2291. 2292. 2293. 2294. 2295. 2296. 2297. 2298. 2299. 2300. 2301. 2302. 2303. 2304. 2305. 2306. 2307. 2308. 2309. 2310. 2311. 2312. 2313. 2314. 2315. 2316. 2317. 2318. 2319. 2320. 2321. 2322. 2323. 2324. 2325. 2326. 2327. 2328. 2329. 2330. 2331. 2332. 2333. 2334. 2335. 2336. 2337. 2338. 2339. 2340. 2341. 2342. 2343. 2344. 2345. 2346. 2347. 2348. 2349. 2350. 2351. 2352. 2353. 2354. 2355. 2356. 2357. 2358. 2359. 2360. 2361. 2362. 2363. 2364. 2365. 2366. 2367. 2368. 2369. 2370. 2371. 2372. 2373. 2374. 2375. 2376. 2377. 2378. 2379. 2380. 2381. 2382. 2383. 2384. 2385. 2386. 2387. 2388. 2389. 2390. 2391. 2392. 2393. 2394. 2395. 2396. 2397. 2398. 2399. 2400. 2401. 2402. 2403. 2404. 2405. 2406. 2407. 2408. 2409. 2410. 2411. 2412. 2413. 2414. 2415. 2416. 2417. 2418. 2419. 2420. 2421. 2422. 2423. 2424. 2425. 2426. 2427. 2428. 2429. 2430. 2431. 2432. 2433. 2434. 2435. 2436. 2437. 2438. 2439. 2440. 2441. 2442. 2443. 2444. 2445. 2446. 2447. 2448. 2449. 2450. 2451. 2452. 2453. 2454. 2455. 2456. 2457. 2458. 2459. 2460. 2461. 2462. 2463. 2464. 2465. 2466. 2467. 2468. 2469. 2470. 2471. 2472. 2473. 2474. 2475. 2476. 2477. 2478. 2479. 2480. 2481. 2482. 2483. 2484. 2485. 2486. 2487. 2488. 2489. 2490. 2491. 2492. 2493. 2494. 2495. 2496. 2497. 2498. 2499. 2500. 2501. 2502. 2503. 2504. 2505. 2506. 2507. 2508. 2509. 2510. 2511. 2512. 2513. 2514. 2515. 2516. 2517. 2518. 2519. 2520. 2521. 2522. 2523. 2524. 2525. 2526. 2527. 2528. 2529. 2530. 2531. 2532. 2533. 2534. 2535. 2536. 2537. 2538. 2539. 2540. 2541. 2542. 2543. 2544. 2545. 2546. 2547. 2548. 2549. 2550. 2551. 2552. 2553. 2554. 2555. 2556. 2557. 2558. 2559. 2560. 2561. 2562. 2563. 2564. 2565. 2566. 2567. 2568. 2569. 2570. 2571. 2572. 2573. 2574. 2575. 2576. 2577. 2578. 2579. 2580. 2581. 2582. 2583. 2584. 2585. 2586. 2587. 2588. 2589. 2590. 2591. 2592. 2593. 2594. 2595. 2596. 2597. 2598. 2599. 2600. 2601. 2602. 2603. 2604. 2605. 2606. 2607. 2608. 2609. 2610. 2611. 2612. 2613. 2614. 2615. 2616. 2617. 2618. 2619. 2620. 2621. 2622. 2623. 2624. 2625. 2626. 2627. 2628. 2629. 2630. 2631. 26

2000-2001 2001-2002 2002-2003 2003-2004 2004-2005 2005-2006 2006-2007 2007-2008 2008-2009 2009-2010 2010-2011 2011-2012 2012-2013 2013-2014 2014-2015 2015-2016 2016-2017 2017-2018 2018-2019 2019-2020 2020-2021 2021-2022 2022-2023 2023-2024 2024-2025 2025-2026 2026-2027 2027-2028 2028-2029 2029-2030 2030-2031 2031-2032 2032-2033 2033-2034 2034-2035 2035-2036 2036-2037 2037-2038 2038-2039 2039-2040 2040-2041 2041-2042 2042-2043 2043-2044 2044-2045 2045-2046 2046-2047 2047-2048 2048-2049 2049-2050 2050-2051 2051-2052 2052-2053 2053-2054 2054-2055 2055-2056 2056-2057 2057-2058 2058-2059 2059-2060 2060-2061 2061-2062 2062-2063 2063-2064 2064-2065 2065-2066 2066-2067 2067-2068 2068-2069 2069-2070 2070-2071 2071-2072 2072-2073 2073-2074 2074-2075 2075-2076 2076-2077 2077-2078 2078-2079 2079-2080 2080-2081 2081-2082 2082-2083 2083-2084 2084-2085 2085-2086 2086-2087 2087-2088 2088-2089 2089-2090 2090-2091 2091-2092 2092-2093 2093-2094 2094-2095 2095-2096 2096-2097 2097-2098 2098-2099 2099-2100 2100-2101 2101-2102 2102-2103 2103-2104 2104-2105 2105-2106 2106-2107 2107-2108 2108-2109 2109-2110 2110-2111 2111-2112 2112-2113 2113-2114 2114-2115 2115-2116 2116-2117 2117-2118 2118-2119 2119-2120 2120-2121 2121-2122 2122-2123 2123-2124 2124-2125 2125-2126 2126-2127 2127-2128 2128-2129 2129-2130 2130-2131 2131-2132 2132-2133 2133-2134 2134-2135 2135-2136 2136-2137 2137-2138 2138-2139 2139-2140 2140-2141 2141-2142 2142-2143 2143-2144 2144-2145 2145-2146 2146-2147 2147-2148 2148-2149 2149-2150 2150-2151 2151-2152 2152-2153 2153-2154 2154-2155 2155-2156 2156-2157 2157-2158 2158-2159 2159-2160 2160-2161 2161-2162 2162-2163 2163-2164 2164-2165 2165-2166 2166-2167 2167-2168 2168-2169 2169-2170 2170-2171 2171-2172 2172-2173 2173-2174 2174-2175 2175-2176 2176-2177 2177-2178 2178-2179 2179-2180 2180-2181 2181-2182 2182-2183 2183-2184 2184-2185 2185-2186 2186-2187 2187-2188 2188-2189 2189-2190 2190-2191 2191-2192 2192-2193 2193-2194 2194-2195 2195-2196 2196-2197 2197-2198 2198-2199 2199-2200 2200-2201 2201-2202 2202-2203 2203-2204 2204-2205 2205-2206 2206-2207 2207-2208 2208-2209 2209-2210 2210-2211 2211-2212 2212-2213 2213-2214 2214-2215 2215-2216 2216-2217 2217-2218 2218-2219 2219-2220 2220-2221 2221-2222 2222-2223 2223-2224 2224-2225 2225-2226 2226-2227 2227-2228 2228-2229 2229-2230 2230-2231 2231-2232 2232-2233 2233-2234 2234-2235 2235-2236 2236-2237 2237-2238 2238-2239 2239-2240 2240-2241 2241-2242 2242-2243 2243-2244 2244-2245 2245-2246 2246-2247 2247-2248 2248-2249 2249-2250 2250-2251 2251-2252 2252-2253 2253-2254 2254-2255 2255-2256 2256-2257 2257-2258 2258-2259 2259-2260 2260-2261 2261-2262 2262-2263 2263-2264 2264-2265 2265-2266 2266-2267 2267-2268 2268-2269 2269-2270 2270-2271 2271-2272 2272-2273 2273-2274 2274-2275 2275-2276 2276-2277 2277-2278 2278-2279 2279-2280 2280-2281 2281-2282 2282-2283 2283-2284 2284-2285 2285-2286 2286-2287 2287-2288 2288-2289 2289-2290 2290-2291 2291-2292 2292-2293 2293-2294 2294-2295 2295-2296 2296-2297 2297-2298 2298-2299 2299-2300 2300-2301 2301-2302 2302-2303 2303-2304 2304-2305 2305-2306 2306-2307 2307-2308 2308-2309 2309-2310 2310-2311 2311-2312 2312-2313 2313-2314 2314-2315 2315-2316 2316-2317 2317-2318 2318-2319 2319-2320 2320-2321 2321-2322 2322-2323 2323-2324 2324-2325 2325-2326 2326-2327 2327-2328 2328-2329 2329-2330 2330-2331 2331-2332 2332-2333 2333-2334 2334-2335 2335-2336 2336-2337 2337-2338 2338-2339 2339-2340 2340-2341 2341-2342 2342-2343 2343-2344 2344-2345 2345-2346 2346-2347 2347-2348 2348-2349 2349-2350 2350-2351 2351-2352 2352-2353 2353-2354 2354-2355 2355-2356 2356-2357 2357-2358 2358-2359 2359-2360 2360-2361 2361-2362 2362-2363 2363-2364 2364-2365 2365-2366 2366-2367 2367-2368 2368-2369 2369-2370 2370-2371 2371-2372 2372-2373 2373-2374 2374-2375 2375-2376 2376-2377 2377-2378 2378-2379 2379-2380 2380-2381 2381-2382 2382-2383 2383-2384 2384-2385 2385-2386 2386-2387 2387-2388 2388-2389 2389-2390 2390-2391 2391-2392 2392-2393 2393-2394 2394-2395 2395-2396 2396-2397 2397-2398 2398-2399 2399-2400 2400-2401 2401-2402 2402-2403 2403-2404 2404-2405 2405-2406 2406-2407 2407-2408 2408-2409 2409

Prison, for part or all, means facing the full force of the law.

SHIRT SLEEVES BY 20% FOR 33", 20% OFFER PRICED AT 100%

[illegible]

THESE ARE THE NAMES OF THE PEOPLE WHOSE NAMES ARE ON THE LIST.

C. LEFT FILTER

These efforts resulted in 1967, and in 1968, the first year of the war, when the number of deaths was 10,000.

2.1) מסרתי למר משה שור את בדיקת הציוד במובן מכני והוא ימסור את חוות דעתו למר הררי.

הציוד עומד ללא שמוש זמן רב, בערך 8-9 שנים ושנת ייצורו בדרך כלל לפני 20 שנה או יותר. במקרה שמצב המכני הוא טוב, אזי הציוד יכול לשרת את הייצור. אבל הבעיה היא אם רציפות העבודה מובטחת והחזקת הצפוד הדרוש הוצאות גדולות.

לפי החוברת המצורפת ל-77% מכל הציוד יש ערך בכלל רק במקרה והציוד משרת את הטכנולוגיה והיא מוצלחת. השאלה היא אם יש הכרח לקנות את כל הציוד יחד עם השיטה, או יש אפשרות לקנות השיטה ורק חלק מהציוד. אם יוחלט לקנות את השיטה, הנני ממליץ כי מר סלביץ ימכור את הציוד הלא מתאים בשוק החדש.

בחור דוגמא: - ישנה מכונה בטון בערך -60,000 ל"י, המיקסר הזה היה בשימוש לפני הרבה שנים לבניית כבישים ויכול לייצר כמה מאות מ3 בטון ביום ובעתיד אולי עד 100 מ3 בטון. לכמות זאת אפשר לקבל במחיר זה מכונה חדישה ומתאימה יותר למטרה. השיטה בכללה חדישה ביותר אבל הציוד הוא מיושן ולפי דעתי בצודל השקעה זה, אפשר לקנות גם ציוד חדיש. חוברת הציוד לא כוללת את כל הציוד הדרוש להקמת בית החרושת וההשקעה השלמה של הציוד היא בערך מליון ל"י, לעומת -413,100 ל"י המפורטות.

2.2) תבניות

הקונסטרוקציה של התבניות היא יוצאת מהכלל ומחוכנת בצורה גאונית. אם טכנולוגית הבטון ושיטת הרסוס מוצלחת, אזי עם תבניות כאלה אפשר לייצר אלמנטים טובים ביותר. כמובן שלתבניות אלה ישנו ערך ספציפי רק במקרה והטכנולוגיה מוצלחת.

1.2) Some of the most important factors which affect the rate of change are:

1. The rate of change of the population, which is determined by the birth rate, the death rate, and the rate of migration. The rate of change of the population is a function of the birth rate, the death rate, and the rate of migration.

2. The rate of change of the economy, which is determined by the rate of investment, the rate of savings, and the rate of consumption. The rate of change of the economy is a function of the rate of investment, the rate of savings, and the rate of consumption.

3. The rate of change of the technology, which is determined by the rate of research and development, the rate of innovation, and the rate of diffusion. The rate of change of the technology is a function of the rate of research and development, the rate of innovation, and the rate of diffusion.

4. The rate of change of the social structure, which is determined by the rate of urbanization, the rate of industrialization, and the rate of modernization. The rate of change of the social structure is a function of the rate of urbanization, the rate of industrialization, and the rate of modernization.

5. The rate of change of the political system, which is determined by the rate of democratization, the rate of decentralization, and the rate of reform. The rate of change of the political system is a function of the rate of democratization, the rate of decentralization, and the rate of reform.

6. The rate of change of the cultural system, which is determined by the rate of globalization, the rate of Westernization, and the rate of modernization. The rate of change of the cultural system is a function of the rate of globalization, the rate of Westernization, and the rate of modernization.

7. The rate of change of the environmental system, which is determined by the rate of industrialization, the rate of urbanization, and the rate of modernization. The rate of change of the environmental system is a function of the rate of industrialization, the rate of urbanization, and the rate of modernization.

8. The rate of change of the international system, which is determined by the rate of globalization, the rate of Westernization, and the rate of modernization. The rate of change of the international system is a function of the rate of globalization, the rate of Westernization, and the rate of modernization.

1.3) Conclusion

The rate of change is a function of many factors, including the rate of population change, the rate of economic change, the rate of technological change, the rate of social change, the rate of political change, the rate of cultural change, the rate of environmental change, and the rate of international change.

The rate of change is a function of the rate of population change, the rate of economic change, the rate of technological change, the rate of social change, the rate of political change, the rate of cultural change, the rate of environmental change, and the rate of international change.

The rate of change is a function of the rate of population change, the rate of economic change, the rate of technological change, the rate of social change, the rate of political change, the rate of cultural change, the rate of environmental change, and the rate of international change.

The rate of change is a function of the rate of population change, the rate of economic change, the rate of technological change, the rate of social change, the rate of political change, the rate of cultural change, the rate of environmental change, and the rate of international change.

(3) כלכליות

| משך הקמת והכנת המפעל | 2 שנים |
|--------------------------------------|-----------------|
| משך הרצה ונסיונות | 1/4 שנה |
| השקעה: א. פתוח (בהשערה) בערך | 500,000.- ל"י |
| ב. בחים, כבישים פנימיים ורצפות בערך | 1,200,000.- ל"י |
| ג. ציוד וחב/ניות בערך | 1,000,000.- ל"י |
| ד. הוצאות הרצה בערך | 100,000.- ל"י |
| הוצאות בלתי נראות מראש (8% מ-א-ר) | 200,000.- ל"י |
| רביית ל-2 1/4 שנה לפי 11% בערך | 500,000.- ל"י |
| השקעה סה"כ בערך | 3,500,000.- ל"י |
| ייצור בית החרושת יהיה 600 דירות לשנה | |
| אמורטיזציה (כרגיל ל-7 שנים) תהיה | 3,500,000.- ל"י |
| בערך - 633 ל"י לדירה | 7×600 |

הסכום הוא די גבוה ביחס למחיר דירה שהוא יכול להיות בערך - 10,000 ל"י.

(4) הצעות

לפני גמר איזה שהוא הסכם, אני מציע להזמין ולארגן ייצור נסיוני על יסוד חכניה וחשיב מסויים ועבודה משותפת של מהנדס סלבין ובעל ההשקעה. הבאתי את הבעיה הנ"ל למר סלבין ועל יסוד השיחה אתו, אני מציע כמה פרטים עבור הנסיון.

4.1 מקום הנסיון: מפעל מר סלבין ;

4.2 משך ההכנות: 6 - 8 חדשים ;

4.3 הוצאות הנסיון - 250,000 ל"י.

במקרה והנסיון יצליח, אזי מסכום זה - 50,000 ל"י ילכו לאיבוד עבור ההכנות הזמניות במקום הנסיון. סכום זה הוא מ-1.5% מערך ההשקעה. אני משוכנע שהשקעה כל כך גדולה ורצינית מצריכה נכיון והסכום של 1.5% לא נלקח בחשבון. עלי להוסיף שתקופת הנסיון תגרום לדחיה במועד הקמת המפעל. אבל הדבר הכרחי מכל הבחינות.

ברצוני לנמק את דרישת הנסיון גם מנקודת הראות של עתיד חרושת הבטון הטרומ בארץ. במקרה והטכנולוגיה לא תצליח בגלל חוסר נסיון, אזי ההפסד הוא לא רק של 3.5 מליון ל"י, אלא הדבר יגרום בעתיד לנסיגה בחרושת הבטון הטרומ בארץ, ולכן הנני דורש באופן אישי את הנסיון הנ"ל לטובת הארץ והמקצוע. כי הבטון הטרומ הוא הדרך היעילה ביותר לפתרון בעיות הבניה בארץ.

אנדרה פיליש

מהנדס ביצוע
רטרום

F) correct

and each other. 2. 100

ONE MORE REQUEST ALL THE

1957: 1. 1958 (1959) 2000 - 1959, 1960 1961

2. 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 2680, 2681,

4. Ziffernfolge 0000 - 9999, 10000, 10001, etc.

7. 1950 1000 1000

... ..

$\text{norm} \rightarrow \text{f.s.} \rightarrow \text{ver} \rightarrow \text{f.s.}$

המחיר: 100,000 ₪

Seit der Gründung des OGB hatte sich

aggregieren (oder $\delta - T$ also) nach $-\frac{1}{2} \frac{d^2 \ln \rho}{d \ln T^2} = \frac{d^2 \ln \rho}{d \ln T^2}$

1000 x 1

[illegible]

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific information required.

1.4) Agroecology: food or drugs?

5.6) our network: $d = 8$ nodes

Р. 2) - 100,000 руб.

down rates; then, we have in $-0.00, 02$ etc. for every year since

Исследованное здание имеет, по сути, 2-х этажную конструкцию, при этом

000000-00 00 0000 000000 000000 000000 000000 000000 000000 000000 000000

100-443887-1000

see center.

ONLY. CANNOT BE USED FOR ANY OTHER PURPOSE, AND CANNOT BE REPRODUCED.

ad 2.5 cm, with more than one dozen small eggs per egg.

that place a few extra years on getting it'd foreman they suggest, or more

During the early 1970s, when the dairy system was in crisis,

2000 年 12 月 1 日

2004年12月 12日 星期三

1992

לכבוד
הנהלת "רסקו"

הנדון: הערות בקשר למכנולוגיה של ייצור
בתי מגורים לפי שטח מתגורר מלבין

בהתאם לבקשתכם בדקתי את המכנולוגיה של שטח מלבין
ובזה הנני מביא את חוות דעתי המפורטת בארבעה הסעיפים דלהלן:

- (1) מכנולוגיה ;
- (2) ציוד וחבניות ;
- (3) כלכליות ;
- (4) הצעה.

1) מכנולוגיה

השיטה שונה בחבליה מאלה הסוכרות באירופה. באופן עקרוני היא
מתאימה ביותר לחרושת הבטון הסרום ויש בה תרומה מהפכנית
בהשוואה לשטות המקובלות.

יתרונות

- (1.1) חסול חלק גדול, באופן יחסי מהעבודה הגורמית.
- (1.2) השגת דיוק טכני מלי באלמנטים המרוכבים.
- (1.3) ייצור האלמנטים הוא באופן אנכי ועל ידי כך חוסכים הרבה
הנועות מיותרות.
- (1.4) ישנה אפשרות לקבוע באופן רצוני את מספר, מקום וגודל
הפתחים בסו"כ אפשר לשנות אורכי האלמנטים.
- (1.5) צמצום רב בעבודות הגמר במקום הבניה, כי רוב עבודות הגמר
כגון: הרכבת נגרות, אינסטלציה מניטרית וחשמלית, רצוף
וכו' נעשות בביהח"ר ; ע"י כך חוסכים במספר הפועלים
וקבלני משנה במקום העבודה ומאפשרים ארגון יעיל והקטנת
זמן העבודה במקום.

ממדים

- (1.6) ביציקת אלמנט בגודל 20 מ"2 (אורך 8, גובה 2.50 מ'
או 2.80 מ') אינני בטוח שהרבות שווה בכל השטח ושפני
השטח יהיו לגמרי חלקים. השגת שטח חלק בר-בבד עם חוזק
בטון אחיד, היא בעיה די קשה של הנדסה ומכנולוגיה הבטון.

פרוט הטעיה 1.6

- (1.6.1) באקלים שלנו קשה לקבוע ולהבטיח את מקדם סיי-צמנט
והערובה נכונה של הבטון, אפילו אם גודל וסיב האורגמים
אינו משתנה. לפי הנסיון, בית חרושת שאין לו מתצבת
משלו, אינו יכול להבטיח הערובה אחידה של האורגמים.
באלמנטים הגבוהים הנ"ל סרחק בין ה, יון והחבנית קטן
ואם נכנסת אבן יחור גדולה מאשר המתוכנן, אזי מתחת
לאבן נשאר מקום ריק עד תחתית האלמנט.

1957
1958

STATE OF NEW YORK
IN SENATE
January 15, 1958

REPORT OF THE COMMISSIONER OF THE DEPARTMENT OF SOCIAL SERVICES
ON THE ADMINISTRATION OF THE DEPARTMENT FOR THE YEAR 1957

COMMISSIONER OF THE DEPARTMENT OF SOCIAL SERVICES
ALBANY, NEW YORK
1958

1. INTRODUCTION

The Department of Social Services is pleased to present to the Senate its report on the administration of the Department for the year 1957. This report is a summary of the work of the Department and its various divisions during the year.

2. DEPARTMENTAL ACTIVITIES

The Department of Social Services is composed of several divisions, each of which is responsible for a specific area of social service. These divisions are: the Division of Child Welfare, the Division of Family Services, the Division of Mental Health, the Division of Public Welfare, and the Division of Social Work. Each division has a number of staff members who are responsible for the day-to-day operations of the Department. The Department also has a number of advisory committees and boards which provide guidance and advice on various issues related to social service.

3. FINANCIAL STATEMENT

The Department of Social Services has a budget of approximately \$10 million for the year 1958. This budget is used to pay the salaries of the staff members, to purchase the materials and supplies needed for the various programs, and to cover the other expenses of the Department. The Department is committed to the efficient use of its funds and to the provision of high-quality social services to the people of New York.

4. CONCLUSIONS

The Department of Social Services is proud of the work it has done during the year 1957. It has made significant progress in many areas, including the improvement of the child welfare system, the expansion of family services, and the development of new programs for the mentally ill. The Department is committed to continuing this work and to providing the highest quality of social services to the people of New York.

1.6.2) לרשות בדרך כלל יש שלוש פטרות:

- א. העברה הבטון מסקום למקום בתבנית ;
 - ב. הרוק הבטון ;
 - ג. ייצור שטח חלק בצרי התבנית.
- לכל אחת מפעולות אלה יש צורך ברשות שונה. אם כן, יש הכרה להתאים את כל שלוש הפעולות וזאת בעיה רצינית, בגובה כזה של אלמנט.
- יש חשש שבחור גובה כזה, התערובה החלק בשכבות שונות בגלל מסך הרטום הארוך וגם בגלל נפילת הבטון מהסרס הנע ער התחית התבנית.

התאמת הערובה הבטון ושטח הרטום הם היסוד להצלחת השיטה בכללה. בקשתי מר סלבין להיות נוכח בנסיון או לראות אלמנט מוכן שבוצע לפי השיטה הנ"ל. החשובה היתה כי הנסיון הצליח, אבל מר סלבין לא יכול להראות את האלמנט, מפני שתבנית הנסיונית בנויה בצורה סגורה ואי אפשר היה להוציא את האלמנט בשלמות.

1.6.3) הסרט הנע נותן אפשרות של אחסון אלמנטים מוכנים עבור 7 ימי עבודה ייצור. במקרה ויש תקלה במקום מסוים, אזי נגרסת סתימה לכל הייצור אחרי שבוע ימים. אפילו במקרה שספק הנגרות לא עומד בהתחייבות הזמן או שטח מקום התבנית אינו מוכן בזמן וגם תקלה בסוג אויר יכולים לגרום להפסקת כל הייצור. לפי דברי מר סלבין, ההשקעה לתכניתו היא של 2 מיליון ל"י כולל אחסון מינימלי של שבוע ימים כנ"ל. במקרה ורוצים להגדיל את אחסון האלמנטים, יש צורך בחוספת השקעה של בערך - 200.000 ל"י. לפי דעתי אסור לבנות בית חרושת בלי אחסון מינימלי של שלשה שבועות.

2) ציוד ותבניות

עיינתי בחוברת המצורפת של הציוד, אבל לא בסובן מצב מכני של הציוד עצמו, אלא בסובן שרות הציוד לטכנולוגיה של הייצור.

2.1) מסרתי למר משה שור את בדיקת הציוד בסובן מכני והוא ימסור את חוות דעתו למר הררי.

הציוד עומד ללא שמוש זמן רב, בערך 8-9 שנים ושנה ייצורו בדרך כלל לפני 20 שנה או יותר. במקרה שמצב המכני הוא טוב, אזי הציוד יכול לשרת את הייצור, אבל הבקיה היא אם רציפות העבודה מובטחת והחזקת הציוד הדרש הוצאות גדולות.

לפי החוברת המצורפת ל-77% מכל הציוד יש ערך בכלל רק במקרה וחציור משרת את הטכנולוגיה והיא מוצלחת.

השאלה היא אם יש הכרה לקנות את כל הציוד יחד עם השיטה, או יש אפשרות לקנות השיטה ורק חלק מהציוד.

אם יוחלט לקנות את השיטה, הנני מסליץ כי מר סלבין יסבור את הציוד הלא מתאים בשוק החדש.

בחור דוגמה: ישנה מכונה בטון בערך - 60.000 ל"י, המיקמר הזה היה בשמוש לפני הרבה שנים לבניה כבישים ויכול לייצר כסה סאות מ³ בטון ביום ובעמיד אולי עד 100 מ³ בטון.

לכסות זאת אפשר לקבל במחיר זה מכונה חדשה ומתאימה יותר למטרה.

השיטה בכללה חרישה ביותר אבל הציוד הוא מיושן ולפי דעתי בגורל השקעה זה, אפשר לקנות גם ציוד חדש.

THESE ARE THE RESULTS OF THE
ANALYSIS OF THE SAMPLES
OBTAINED FROM THE
SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964.
THE RESULTS SHOW THAT
THE SAMPLES CONTAIN
A HIGH PERCENTAGE OF
IRON AND NICKEL
AND A LOW PERCENTAGE OF
COPPER AND ZINC.
THIS IS IN ACCORDANCE
WITH THE ANALYSIS OF
THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964.

THE RESULTS OF THE ANALYSIS
OF THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964, SHOW THAT
THE SAMPLES CONTAIN
A HIGH PERCENTAGE OF
IRON AND NICKEL
AND A LOW PERCENTAGE OF
COPPER AND ZINC.
THIS IS IN ACCORDANCE
WITH THE ANALYSIS OF
THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964.

THE RESULTS OF THE ANALYSIS
OF THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964, SHOW THAT
THE SAMPLES CONTAIN
A HIGH PERCENTAGE OF
IRON AND NICKEL
AND A LOW PERCENTAGE OF
COPPER AND ZINC.
THIS IS IN ACCORDANCE
WITH THE ANALYSIS OF
THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964.

THE RESULTS OF THE ANALYSIS
OF THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964, SHOW THAT
THE SAMPLES CONTAIN
A HIGH PERCENTAGE OF
IRON AND NICKEL
AND A LOW PERCENTAGE OF
COPPER AND ZINC.
THIS IS IN ACCORDANCE
WITH THE ANALYSIS OF
THE SAMPLES OBTAINED
FROM THE SITE OF THE
DISASTROUS COLLISION
ON THE 15TH OF
MAY 1964.

הוברח הציור לא כולל את כל הציור הדרוש להקמת בית החרושת וההשקעה השלמה של הציור היא בערך מיליון ל"י, לעומת 413,100 ל"י המפורטות.

(2,2) חבניות.

הקונסטרוקציה של החבניות היא יוצאת מהכלל ומתוכננת בצורה גאונית. אם טכנולוגיה הבטון ושיטת הרטוט מוצלחות, אזי עם חבניות כאלה אפשר ליצור אלמנטים טובים ביותר. כמובן שלחבניות אלה ישנו ערך ספציפי רק במקרה והטכנולוגיה מוצלחת.

(3) כלכליות

| משך הקמת
משך הרצה
השקעה:א. | והכנת המפעל
ונסיונות
פחות (בהשקעה) בערך
ב. בחים, כבישים פנימיים ורצפות בערך
ג. ציור ותבניות בערך
ד. הוצאות להרצה בערך
הוצאות בלתי נראות סראש(8% מ"א"ד)
רביית ל-1/4 2 שנה לפי 11% בערך
השקעה סה"כ בערך
ייצור בית החרושת יהיה 600 דירות לשנה
אמורטיזציה(כרגיל ל-7 שנים) תהיה
בערך 633 ל"י לדירה | 2 שנים.
1/4 שנה | ל"י |
|----------------------------------|--|--------------------|-------------|
| | | | 500.000.- |
| | | | 1,200.000.- |
| | | | 1,000.000.- |
| | | | 100.000.- |
| | | | 200.000.- |
| | | | 500.000.- |
| | | | 3,600.000.- |
| | | | 3,500.000.- |
| | | | 7x600 |

הסכום הוא די גבוה ביחס למחיר דירה שהוא יכול להיות בערך 10.000 ל"י.

(4) הצעות

לפני גמר איזה שהוא הסכם, אני מציע להקמין ולארגן ייצור נסיוני על יסוד חכניה ותחשיב סמים ועבודה שוחפת של מהנדס סלבין ובעל ההשקעה. הבאתי את הבעיה הנ"ל למר סלבין ועל יסוד השיחה אחר, אני מציע כמה פרטים עבור הנסיון.

(4,1) מקום הנסיון

מפעל מר סלבין;

(4,2) משך ההכנות: 6-8 חדשים;

(4,3) הוצאות הנסיון 250.000 ל"י.

במקרה והנסיון יצליח, אזי מסכום זה 50.000 ל"י ילכו לאבוד עבור ההכנות והנסיון במקום הנסיון. סכום זה הוא סך-כול 1% מערך ההשקעה. אני משוכנע שהשקעה כל כך גדולה ורצינית מצריכה מסיון והסכום של 1% לא נלקח בחשבון. עלי להוסיף שתקופת הנסיון תגרום לבחיה בסווד הקמת המפעל. אבל הדבר הכרחי מכל הבחינות. בראוני לנסק את דרישת הנסיון גם מנקודת הראות של עתיד חרושת הבטון הטרומ בארץ. במקרה והטכנולוגיה לא תצליח בגלל חסר נסיון, אזי ההפסד הוא לא רק של 3% מיליון ל"י, אלא הדבר יגרום בעתיד לנסיגה בחרושת הבטון הטרומ בארץ, ולכך הנני דורש באופן אישי את הנסיון הנ"ל למובת הארץ והמקצוע, כי הבטון הטרומ הוא הדרך העילה ביותר לפתרון בעיות הבניה בארץ.

אנדרה פיליש
מהנדס בצוע
ר ט ר ט

1. The first part of the report is a general statement of the purpose and scope of the study. It is followed by a brief review of the literature on the subject.

2. The second part of the report is a description of the methods used in the study.

This part includes a description of the subjects, the instruments used, and the procedures followed. It also includes a description of the data analysis techniques used.

3. The third part of the report is a presentation of the results of the study.

| Item | Amount |
|--------------|-------------------|
| Salaries | \$1,000.00 |
| Travel | 500.00 |
| Supplies | 200.00 |
| Postage | 100.00 |
| Telephone | 150.00 |
| Printing | 100.00 |
| Other | 50.00 |
| Total | \$2,100.00 |

The total amount of the study is \$2,100.00. This amount is to be paid in three installments of \$700.00 each.

4. The fourth part of the report is a discussion of the results of the study.

This part includes a discussion of the findings of the study and their implications. It also includes a discussion of the limitations of the study and suggestions for further research.

5. The fifth part of the report is a conclusion.

This part includes a summary of the findings of the study and a statement of the conclusions drawn from the study. It also includes a statement of the author's appreciation for the assistance of the staff and the cooperation of the subjects.

Very truly yours,
[Signature]
[Name]

טלפון 961446

"ש ב ח"

חברה ליצור בתים להרכבה בע"מ

בית למכתבים

רמלה

ת.ד. 225

26.10.69

תאריך

60

מספרנו

לכבוד,

מר אשכנזי

סמנכ"ל

משרד השכון

הקריה

חל-אביב

א.נ.

ר"ב עותק מכתב עורכי פטנטים, כהן צדק ושפיסכר.

מה- 7.10.69

משרד השיכון, הקריה
המשרד הראשי

29.10.69

אלכנזי

חברת "שבח"
לכבוד רב, בית
טל. 961446
חברת "שבח" בע"מ
רמלה

STATE
UNION STATE
UNION
UNION
UNION
UNION

THE STATE OF TEXAS
COUNTY OF DALLAS

STATE OF TEXAS
COUNTY OF DALLAS

בהן צדק ושפיטבך
קורכי פסנטים מוסמכים

תל-אביב,

ח. ד. 1189

חיק 66, 13105 א'

(בחשבה נא להזכיר)

7 באוקטובר, 1969.

622736, 622737

המשרד:

רחוב לבונטין 21, תל-אביב

טלפון 615290

אחרי שעות המשרד: 721525

לכבוד

מר חיים סלביץ,

רח' פרישמן 43,

תל - אביב.

א.מ.נ.,

הנדון: - בקשה פסנט מס' 24.935 במסר, לגבי -
"חבנית ליצוקת בטון".

אנו ממחים להודיעך כי הבקשה הנ"ל החקבלה ע"י משרד הפטנטים
ואי לכך היה צורך בתשלום אגרת הפרסום. זאת עשינו ואנו
מזכירים חשבונו הנדון.

בכבוד רב,

לוחה

כג

HAIM ASHER.

DELEGATION IN SPAIN

07 01 01

AMIEX INTERNATIONAL LTD

JUAN HURTADO DE MENDOZA, PISO 2 / 204

TELEPHONES

OFFICE: 250 86 00 EXT. 92

PRIVATE MR. ASCHER:

223 96 47 EXT. 34

CABLES: AMINTEX

MADRID-16

Your ref.

Our ref.

מדריד, 11 באוקטובר 1969

לכבוד

מר ישראל למדן

תל-אביב

ישראל יקירי,

הנדון: בניה לפי שיטת סלבין

בהמשך למה שכבר כתבתי לך בעניין זה:

הקבלן הנדון מעוניין באופן רציפי בבניה לפי שיטת זו, אבל טוען שיש מעט פרטים ב-2 הסופסים שקבל ביחס לנקודה: מה תרומתנו לעניין זה, כלומר, אם אנו דורשים \$250,000 להכנת בית-חרושה לבניה זו לכן-וכך יחידות, מה כולל הסכום הזה. האם רק המכונות והציוד (מלבד הקרקע, כמובן), או גם הדרכת אישית של מומחים.

אפשר לרכז את המאלות העיקריות כדלקמן:

(1) הסכום שיקבל (מי, משרד השיכון או גוף אחר?) בעד הכנת מפעל לבניית דירות, בעד איזה עבודה/חברים/שירות ניתן? מכונות-ציוד עד למפתח, או גם הדרכת, ומה בדיוק כל שירות שיקבל קונה ה"שיטה"?

(2) המכונות שיוכנסו למפעל הנ"ל יובאו מאיזה מקום? האם אי-אפשר לבנות חלק מהן כאן, במספר (בהדרכתנו) על-מנת שהעלינה פחות?

(3) חסרים פרטים בכלל על הצורה בה עשוי להבנות המפעל: מי יספק בבנייתו, האם יבואו מומחים מהארץ, מה צורת הטיפול והעבודה ועו'.

(4) אתה כותב לי שמשרד השיכון יקבל 10% ממחיר הדירה (מחיר מכירה). כיצד תהיה הפרוצדורה לביקורת ולתשלום, ומי יבדוק? האם אחוזים יחיו רק מהמכירה, ולא ממחיר הכנת המפעל כולל מכונות (זו שאלה שאני שואל), במקרה הנדון - האם לא נקבל אחוזים מ-\$250,000 מחיר בניית המפעל?

האנשים טוענים שאנו מאוד חסכניים בהסברים. הפורמלים שבדינו כוללים דברים כללים מאוד. כדוגמא הם מביאים שפורסם כאן בעתון יומי מאמר על צורת בניה בוינה לפי שיטת המזכירה מאוד את שיטת סלבין, ויש במאמר עתונאי זה יותר פרטים משיש בהסברים בכתב של מומחי סלבין.

העניין רציפי מאוד ומעשי, וניתן למימוש, ואנא דבר עם מי שצריך ויהנו לך פרטים רבים על האפשר - ועוד סופסים. המעוניינים מחכים לחשובה מהירה.

בברכה

ח. א. שר

07.01.01

16.10.1969

לכבוד
מר חיים אשר
מדיין
משרד

א.נ.ס.

הנדון: בניה לפי שיטת סלביץ

על מנת שנוכל לספק לך אומדנים מחאימים על הוצאות הקמת דירות לפי שיטת סלביץ, נודה לך
אם תוכל לספק לנו אינפורמציה על הנאי השוק בספרד, לפי המירוט הבא :

1. שכר עבודה (כולל זכויות מוציאליות)

- א. מועל בנין שווט
- ב. מועל בנין מקצועי
- ג. חשמלאי בבנין
- ד. שרברבים בבנין
- ה. מנהלי עבודה בבנין
- ו. מועלי אחזקה
- ז. שכנאים
- ח. מהנדסים
- ט. פקידים
- י. מנהלי משרד

כמו כן נבקשך לציין מהוא שוק העבודה של כל אחד מסוגי העובדים המפורטים. מה המצב
באשר להשגה עובדים אילו.

2. מחירי חומרים (בשערי המפעל, במידה שהמחיר הוא של הספק - נא לציין מחירי הובלה)

- א. מלט - טונה
- ב. ברזל בעובי של 18 - 6 מ"מ
- ג. חצץ בגודל טונה
- ד. חול

האם ניתן להשיג חומרים אילו, ודרגה הקושי של השגתם, מועדי ותנאי הספקה ותנאי תשלום.

1. 1000 1000 1000 1000

2. 1000 1000 1000 1000

3. 1000 1000 1000 1000

4. 1000 1000 1000 1000

5. 1000 1000 1000 1000

6. 1000 1000 1000 1000

7. 1000 1000 1000 1000

8. 1000 1000 1000 1000

9. 1000 1000 1000 1000

10. 1000 1000 1000 1000

11. 1000 1000 1000 1000

12. 1000 1000 1000 1000

13. 1000 1000 1000 1000

14. 1000 1000 1000 1000

15. 1000 1000 1000 1000

16. 1000 1000 1000 1000

17. 1000 1000 1000 1000

18. 1000 1000 1000 1000

19. 1000 1000 1000 1000

20. 1000 1000 1000 1000

3. מחירי עבודות מקצועיות (כולל חומרים)

- א. אינסטלציה חשמלית (
- ב. אינסטלציה מים (
- ג. אינסטלציה סניטרית (
- ד. גבוקה - לספר מרובע
- ה. הריצוף - איזה ריצוף מקובל, מחירו למס"ר - עבודה וחומרים

4. מחירי שימוש בגורמים המקצועיים, הנאים מקובלים ומחירים

- א. עבודה ברזל כמו מעקה של מדרגות וכו'. האם קיימים בחי מלאכה המקבלים עבודה כאלו בקבלנות או שיש לבצע אותם ישירות בעזרת פועלים.
- ב. האם קיימים מרכזי חספה בשוץ. מחיר לשונה.
- ג. מה גודל מקסימלי של מובילי בשוץ ומהם החנאים המקובלים.

5. ביסני חוץ לבית

- א. מה מקובל לכיסוי חיפוי:
 - (1) גבע היוד
 - (2) גבע שמן
 - (3) גבע פלסטי
 - (4) שפריץ, מרופיל עם חוספה של אבנים קטנות
- ב. מה המחירים המקובלים למס"ר של כל סוג גבע (והם מקובל לפי השקל - מחיר ליחידה משקל).
אם המחירים המקובלים לחומר לחוד ולעבודה לחוד, נא לציין בנפרד.

6. מאלות כלליות

- א. מהם עבודות הפיתוח המקובלות כשהם חבניה: כבישים, מדרגות, גינות, חניה וכו'. האם נהגים לכלול אותם במחיר חבניה ומה המחירים המקובלים.
- ב. מהם מחירי המגרשים לבניה באיזוריט הרלוונטיים, אחוזי בניה מקובלים (מספר יחידות לשטח וטירה הריבוד של הבנינים).
- ג. מה קומה מקובל לבנות ומה מספר הקומות המבוקש. לצרכי בניה מחוקקת מהאים ביוחר
- ד. קומה. אכלנו אין צורך במקלית למבנה כזה. באם צריך מקלית למבנה כזה, מה המחירים והחנאים המקובלים.

(ד) האם אפשר לקבל שירותים של דירה עממית מקובלת. אצלנו דירה כזאת היא בגבולות של 70 מ"ר ברוטו וכוללת 2 חדרי שינה, חדר מגורים, מטבח, שירותים, מרפסת וחלק יחסי בחדר המדרגות. נא לציין מה כולל השטח אצלכם לפי המידות הנ"ל.

(ה) מה הסטנדרט המקובל לדירה כזאת ומה הוא כולל (אביזרים וכד').

(ו) מה מחיר השוק של דירה כזאת בבניה קונבנציונלית ומה עלותה לבונה. הוך פירוט המרכיבים השונים.

(ז) במידה האפשרי נא לציין מרכיבי המחיר מקובלים, כל פרט חשוב לנו.

(ח) האם קיימות במקום הבניה ובמקום המפעל תחנות השמל או קוי השמל מרכזיים אשר יספקו השמל לצרכי בניה ומאור ולצרכי המפעל. כנ"ל השפעת מיס. נא לציין מחירים והנאים.

(ט) מיסים

(1) מה המיסים המקובלים בבניה, כגון - מיסי בניה, מיס, ביוב וכדומה.

(2) מיסי הכנה ומיסי חברות, שיעורים מקובלים הנחות וכדומה.

(י) שיעורי פחת מקובלים, לציוד מבנים וכדומה.

(יא) הנאי מימון מקובלים, מקורות האשראי, הנאי האשראי, הנאי השלום וכד'.

(יב) הוצאות נוספות אפשריות כגון חיבור לרשת ההשמל, מס עסקים וכדומה.

בנוסף לשאלות שפורטו לעיל אנו מצפים שירותים של מספר דירות טיפוסיות. נבקשכם לציין המחאים ביותר עבורכם ובמידה האפשר לציין שינויים הנראים לכם. כמו כן נבקשכם אומדן עלות ומחיר של דירה כזאת בבניה קונבנציונלית.

האינפורמציה הנדרשת הינה היונית ביותר כדי שנוכל לענות בצורה מפורטת על כל השאלות הקשורות בנושא ולעשות החיבים והערכות.

נודה לכם מאוד על כל פירוט שיוגש לנו ונבקשכם במידה האפשר לרצו את מתן החשובות.

במבד רב

הלל אשכנזי

העתק: מר ישראל למדן, חב' "לכר" רח' דרך יפו ח"א 9, ת"א.

נחוני עזר (לשיטת סלבין)

מ/נ
12/1
13.5.69
(ש)
מקור

1. היקף יציקה
40 מ"ר יציקה תבניות $2 \times 80 \times 250$ ימי יציקה = 20,000 מ"ר שנתי לתבנית.
150,000 מ"ר היקף שנתי = $8 - 7.5$ תבניות.
2. מחיר תבנית מסוג חדש
כ- 60,000.- ל"ל אינסטלציה אולם כולל הידראוליקה.
3. שינוי גודל דירה
יש חוק כללי: מעבר של כ-50% בגודל הדירה (מ-70 ל-100 מ"ר) - משמעו גידול של כ-25% בהוצאות.
4. כניסה לייצור, כיסוי השקעה ורווח
במחיר הדירה של חישוב של 2,000.- ל"ל להחזר-השקעה ורווח. שיעור הרווח הממוצע הוכנס להחזר השקעה במשך שבע שנות ייצור מלא, זאת אומרת לאחר כ-9-10 שנים מחילת הייצור. (קצב ייצור מתוכנן של $\frac{1}{3}$ בשנה א' $\frac{1}{2}$ בשנה ב' ומלא בשנה ג').
5. נקודות מיוחדות הראויות לציון בשיטת סלבין:
 - א. הפלטה מתייחסת לדירה ולא להדר;
 - ב. היציקה ורטיקאלית;
 - ג. מחיר ייצור והרכבה של $\$ 70$ למ"ר לעומת כ- $\$ 130$ בשיטות דומות;
 - ד. ההוצאות לזיון גבוהות יותר אולם מביאות לאחוז אפסי של שברים - וכן מורכבת האינסטלציה כולה על רשתות הזיון;
 - ה. שיטת חיבורים שונה בתבנית - מאפשרת ויבראציה חיצונית;
 - ו. יוס עבודה אחד למ"ר לעומת $1 \frac{1}{2}$ בשיטות דומות;
 - ז. דירה מורכבת ביום אחד, כולל גימור;
 - ח. עמידות גבוהה יותר של המבנה מפני רעידות אדמה וחדירת רטיבות;
 - ט. היציקה הורטיקלית מקטינה את שטח המפעל עד לחצי שטחם של מפעלים דומים;
 - י. אין עבודת ידיים בייצור.

40

"שבה", חברה לייצור בתים להרכבה בע"מ

"שיטה סלביץ"

מרץ 1969

בימים אלה נמסר לחברת "עמידר" בנין המכיל את 40 יחידות הדיור הראשונות, שנוצרו והורכבו על ידי מפעל "שבח" ובכך נכנס המפעל לתקופה של בתים מבניה טרומית.

תיעוש הבניה

הבניה הטרומית הינה שיטה ההולכת וחודרת לתעשיית המדינות המפותחות, בהן פיגר ענף הבניה אחר התיעוש המזורז בענפים אחרים. יתרונות רבים ובולטים לבניה הטרומית לעומת הבניה בשיטות המקובלות: היא מאפשרת תיעוש הבניה וייצור מהיר של יחידות דיור רבות, בשיטה מבוקרת היטב בכל סלבי הייצור ובמידת אמינות גבוהה, הרבה יותר מהמוטג בבניה באמצעים מקובלים. היא משיגה חסכון ניכר במאמץ, בזמן, בכח-אדם, בשטח עבודה ובהוצאות ייצור - ומאפשרת לנצל את יתרונותיה על מנת להגיע להישגים שאינם ניתנים להשגה בשיטות הישנות.

מפעל שבח ברמלה, הינו מפעל לייצור ולהרכבה של בתים טרומיים המבוסס על פטנט ישראלי בלעדי של המהנדס חיים סלבין. "שיטת סלבין" הינה, כנראה, יחידה במינה - וזהו הישג שבודאי ניתן להתגאות בו.

התכונה הראשונה הבולטת ב"שיטת סלבין" הינה רמת התיעוש הגבוהה. כל שיטה של בניה טרומית מבוססת על דרגה כזו או אחרת של תיעוש, אולם בעוד שהשיטות האחרות בארץ ובעולם מגיעות לרמת תיעוש של בין 50 ל-80%, הרי ב"שיטת סלבין" היא מגיעה לכ-90%.

הבדל נוסף בין שיטה זו לאחרות הינו גודל האלמנטים המיוצרים: בעוד שבמפעלים אחרים יוצקים אלמנטים בגדלים שונים של עד קיר אחד לחדר, הרי ב"שבח" יוצקים אלמנטים המתייחסים לדירות שלמות; למוחר להסביר סבדרך זו גדלה יציבות המבנה, עמידותו ומה שחשוב ביותר: קטן מספר החיבורים שבין האלמנטים. ככל שמספר החיבורים קטן, גדלה יעילות השיטה ועולה איכות התוצר וכמובן נחסכים מאמץ וזמן. בשיטה "שבח" ניתן להרכיב על ידי צוות-מנוף-אחד, דירה ורבע ליום עבודה בן משמרת אחת. חכונה אפיינית נוספת ל"שיטת סלבין" הינה שיטת היציקה בסלב הייצור: יציקה האלמנטים נעשית אנכית, לגובה, - ולא אפקית כמקובל בשיטות אחרות ובכך מסיגים כמה יתרונות: טיב האלמנט גבוה יותר מבחינת עמידותו; נחסך טיט יציקה במפעל - עובדה המשפיעה על עלות ההשקעה; וכמו כן השטח אותו צריך להשחז (השטח ממנו יוצקים טאין לו "גב" של חבנית) הינו קטן ביותר. החסכון בכח אדם ובזמן המושג באמצעות "שיטת סלבין" ניכר למדי: ניתן לייצר במפעל עד ארבע יחידות דיור ליום, בגדלים שונים כשכל יחידה כוללת שלושה עד ארבעה חדרים, טרוחיים, מרפסות וכל ההתקנות של אביזרים שונים לרבות חשמל ואינסטלציה סניטרית.

חשוב לציין שכל הציוד למפעל תוכנן ונבנה על ידי המהנדס סלבין במקום, כמעט סבלי להזדקק לייבוא ציוד.

יתרונות אלו ואחרים עושים את "שבח" ליפעל מיוחד לבניה טרומית, בהשוואה למפעלים טרומיים אחרים.

בין מיתון לגאות

יש לזכור כי בישראל הביקוש לבניה הינו מאד גמיש ומוחנה בעיקר בקצב העליה המשתנה; עובדה זו מחייבת להביא בחשבון מצב בו צריך להגביר את קצב הייצור של יחידות דיור או לצמצמו בפרק זמן קצר ביותר, הבניה הטרומית הינה החסובה הבלעדית כמעט לצרכים אלה. יש לציין שברוב ארצות אירופה, בהן אין בעיה דומה לצרכי העליה המשתנים בישראל, מהווה הבניה הטרומית בין 18 ל-28% מכלל הבניה למגורים.

"שבח" הוא מפעל ממלכתי שמומן על ידי משרד הסיכון ונהנה ממעמד של מפעל מאוסר. על הקמתו הוחלט בשנת 1964 לאור השיקולים שנומקו לעיל. ההחלטה נחקבלה בחקופה של גאות בענף הבניה ובדרישות לדיור, אולם כשהמפעל התקרב לייצור החל המיתון שצמצם את הצורך הדוחק במפעלים מסוג זה.

הסלמת המפעל התעכבה, אך מתוך יצא מעז: תקופת המיתון נוצלה לסכלול הסיטה ולמימוש רעיונות חדשים, במקביל לכך הוכשר הצוות המקצועי להפעלת המפעל.

"שבח" בנוי להיקף ייצור של 1,000 יחידות דיור לשנה, עם הכניסה לייצור סדיר ייצר המפעל בסנה הקרובה כ- 500 יחידות דיור ובסלב נוסף יעבור לחפוקתו המירבית.

גיוון הייצור

במקביל לכניסת המפעל לייצור המוני, מוכנסים בו שינויים שמטרתם להביא לגיוון הייצור על ידי בניית דירות מטוגים שונים, זאת הן עקב העלאת סטנדרט השיכון על ידי הגדלת שטח הדירות מעל ל- 70 מ"ר כפי שהיה מקובל עד כה בדיוור לעולים והן כדי להביא לרב-גווניות של מוצרי המפעל, כך סיוכל להיענות לדרישות השונות של צרכי הדיוור.

בח אדם ותעסוקה

במפעל מועסקים כ- 100 עובדים וכאשר יגיע לייצור בהיקף מלא יועסקו בו כ- 250 עובדים רובם בייצור ובהקמה, לרבות מהנדסים ועובדי שרוחים.

כשהוקם המפעל ברמלה, נעשה הדבר, בין היתר, בהחשב בעובדה שעיר זו נמצאת במרכז הארץ, מיקום זה מאפשר למפעל לפעול ברדיוס המקיף אזורי בניה מובהקים.

הנהלה והון

עם הפעלת המפעל מונחה מועצת מנהלים מצומצמת המורכבת מנציגי הממשלה והממציא; מנהלים אלה הינם בעלי מקצוע בתחומים שונים המסוגלים לשקוד על ענייני המפעל ופיתוחו; כיו"ר מועצת המנהלים מכהן מר הלל אשכנזי, סגן המנהל הכללי של משרד השיכון.

הון המניות מתחלק בין הממשלה לממציא: 75% לממשלה ו-25% למהנדס סלבין.

ההסקעות במפעל לרבות ההסקעות במחקר ובפיתוח הגיעו עד כה לסך של כ- 8 מיליון ל"י;

בדיקות הכדאיות קבעו, כי בהיקף ייצור של 1,000 יחידות דיור לשנה, התקבל תשואה ברוטו של 18%.

כאמור, נמסרו בימים אלה 40 יחידות דיור ראשונות; בחודש הקרוב תמסרנה 32 יחידות נוספות. 252 יחידות דיור נוספות נמצאות בשלבי ייצור והקמה.

רעיונו של הממציא מר סלבין שהביא להקמת "שבח" - קורט עור וגידים באחרי הבניה.

החברה התאגדה באוקטובר 1964 בהון רשום של 4 מיליון ל" (מזה 75% בידי המדינה), במטרה להקים ולנהל מפעל לייצור בתים להרכבה, לפי שיטה שפותחה על ידי המהנדס חיים סלבין.

אחד המאפיינים של שיטה זו, היא גישה חדשה לבעיית הבניה הטרומית. אין היא מנסה לחפש תהליכי בניה מקובלים, אלא להפוך את הבניה לתהליך תעשייתי מלא. השיטה מבוססת על אלמנטים גדולים, ומידת התייעוש על כן היא מן הגבוהות בארץ.

מפעל החברה ברמלה חוכנן לכושר ייצור של 1,000 יח"ד בשנה, וההשקעה המשוערת בו ללא הון חוזר נאמדת בכ- 7 מיליון ל"י. עד סוף מרץ 1969 הסתכמו ההשקעות בנכסים קבועים בכ- 6.5 מיליון ל"י.

עד עתה הקימה החברה בהנהלתו של הממציא מר ח. סלבין 3 בנייני מגורים באתר מס' 1 (ויצמן) ברמלה עם 104 יח"ד, מזה שני בניינים מאוכלסים (72 יח"ד) ובניין שלישי בשלבי גמר. מועד איכלוס משוער ספטמבר 1969. הדירות הן בשטח של 70 מ"ר וכוללות 2 חדרי שינה, חדר מגורים ושרותים.

כעת פועלת החברה במסגרת הזמנות לכ- 400 יח"ד על פי הטיפוס הקיים של 70 מ"ר מהן מתוכנן לייצר ולהרכיב בשנת התקציב הנוכחית כ- 240 יח"ד והיחרה בשנת התקציב הבאה. יצויין, כי המחירים אותם מקבל המפעל עבור הייצור והרכבת הדירות באתרים נקבעו עוד בזמן המיתון ואין הם תואמים יותר את הוצאות הייצור הריאליות של המפעל לאור ההתקדמות הרבה בחומרים ושכר עבודה כאחד.

אחת הבעיות המרכזיות של המפעל בשעה זאת - השגת כח אדם מקצועי שיאפשר הפעלה סדירה של ייצור האלמנטים במפעל והרכבתם באתרים השונים. כמו כן יש לציין את הצורך בגיבוש מערכת אירגונית למפעל וביסוס מערכת המחירית.

כושר הייצור של המפעל בשנה הקרובה נאמד בכ- 400 יח"ד. יחד עם זאת יש לציין, כי בכדי להבטיח כושר ייצור זה ואף להגדילו יש צורך להשלים מספר השקעות נוספות במערכת הייצור ולרכוש ציוד וחלקי חילוף רזרביים להבטחת פעולה רצופה של המפעל.

יצויין, כי המפעל אושרו 4 טיפוסים דירות חדשות הנמצאים בשלבי תכנון שונים. התאמת המפעל לייצור מקביל של 4 - 5 טיפוסים דירות תדרוש השקעה נוספת של כ- 750 אלף ל"י.

על מנת להגיע ליכולת הייצור המתוכננת דהיינו כ- 1,000 יח"ד לשנה, ב- 2 משמרות ייצור ומשמרת שלישית לאחזקה יהיה צורך להשלים את ההשקעה, להגדיל את כח האדם ולהכשירו לתהליכי הייצור וההרכבה המיוחדים לשיטת סלבין.

וְהָיָה הַיָּמָּה הַזֶּה מִיְּמֵי הַבְּנֵי אֱלֹהִים

[illegible]

(3) האם יש לא אים, הכולל

(4) האם נשקף מעל המים זרועות המים?

(5) את המושל והיהודים באו בלילה 1000

10/1/2018

200. Every worker should be given the opportunity to participate in all activities of the union. The workers should be given the opportunity to participate in all activities of the union.

7 1/2 ms (r)

מדינת ישראל

לשכת ראש הממשלה

ירושלים, ל" באב תשכ"ט
14 באוגוסט 1969

אל : מנהל לשכת שר השכון

מאת: סגן מנהל לשכת ראש הממשלה

הנדון: מר אירבינג נורי

מר אירבינג נורי מניו-יורק השתתף בועידה הכלכלית שהתקיימה בארץ בחודש יוני ש.ז. ולפני עזבו את הארץ שגר לראש הממשלה את המכתב הרצ"ב.

המכתב עוסק בין היתר בענייני בניה ורצוי היה שתבדקו ישירות את האפשרויות לממש את ההצעות הנזכרות במכתב בא'פן כללי בלבד.

נודה לכם אם תואילו לספל בענין בהתאם להבנתכם.

ב ב ר כ ה,



שמואל שילה

שש/אכ

ה"מ נא 10/8/69
24/8/69

נא 10/8/69

18/8/69

CONFIDENTIAL

1. The purpose of this document is to provide information on the status of the project.

2. The project is currently in the planning stage.

3. The project is expected to be completed by the end of the year.

4. The project is being managed by the project manager.

5. The project is being funded by the government.

6. The project is being implemented by the project team.

7. The project is being monitored by the project manager.

8. The project is being evaluated by the project manager.

9. The project is being reported to the project manager.

10. The project is being completed.

11. The project is being closed.

12. The project is being archived.

13. The project is being deleted.

Irving Norry c/•

Gideon Spiro

Journalist

19 Keren Ha'Yesod str.

Jerusalem, Israel

Dear Golda, my 25th visit comes to an end - I shall return with Ann in October.

Your 47 years here - as you stated - are truly a remarkable saga - your personal challenge appears to have given you added strength.

I am most anxious for you to have a talk with our daughter Devorah - I see her following in your path. She is reluctant to bother you - so please take the initiative.

I am seeing Slavin again to day - and after listening to Yegal Allon on the need for rented housing - it seems the time for further use of the Slavin Factory - he says work is now plentiful - but labour short.

In one thing or another this plant should be either working overtime - or if not economic - perhaps it should close. I think there is a chance of merging it with a plant in Yavne.-

I am not concerned with my personal investment here in this plant - I would gladly give my shares to some Israel charity.

I suggest a personal talk with Haim's son Amnon, he seems to be practical.

Fully understanding the many pressures you face - I pray you can arrange these two personal talks.

The Economic Conference I think a great step forward - this meeting of minds will bear fruit.

Hope to ^{review} these matters on your USA visit.

Irving Norry (-)

2680 Highland Ave.

Rochester

New York 14610

gideon spiro
journalist

19, KEREN HA'YESOD ST.,
JERUSALEM, ISRAEL

IRVING
NORRY

TEL. 52180 טל.
25180

גדעון ספירו
עיתונאי

רחוב קרן היסוד 19,
ירושלים

Dear Golda - my 75th
visit comes to an end - I shall
return with Ann in October.

Your 47 years here - as
you stated - are truly a
remarkable saga - your present
challenge appears to have
given you added strength -

I am most anxious for
you to have a talk with
our daughter Orvach - I
see her following in
your path -

gideon spiro
journalist

19, KEREN HA'YESOD ST.,
JERUSALEM, ISRAEL

TEL. 52180 טל.
25180

גדעון ספירו
עיתונאי

רחוב קרן היסוד 19,
ירושלים

She is reluctant to
bother you - so please
take the initiative.

I am seeing Slavin again
to day - and after listening
to Ygal Allon on the need
for rental housing - it
seems the time for fuller
use of the Seavon factory -
he says work is now
plentiful - but labor short

gideon spiro
journalist

19, KEREN HA'YESOD ST.,
JERUSALEM, ISRAEL

טל. 52180
25180

גדעון ספירו
עתונאי

רחוב קרן היסוד 19,
ירושלים

In one way or another
this plant should be either
working overtime - or if
not economic - perhaps
it should close - I think
there is a chance of merging
it with a plant in Yarn -
I am not concerned with
my personal investment here
in this plant - I would
gladly give my shares to
some Israel charity.

gideon spiro
journalist

19, KEREN HA'YESOD ST.,
JERUSALEM, ISRAEL

טל. 52180
25180

גדעון ספירו
עתונאי

רחוב קרן היסוד 19,
ירושלים

I suggest a personal talk
with Haim's son Amnon (AMNON)
he seems to be practical -

Fully understanding the
many pressures you face - I
pray you can arrange these
two personal talks.

The Economic Conference I think
a great step forward - the meeting
of minds will bear fruit.

Hope to review these matters
on your USA visit -
Kol Zor.

IRVING NORRY
2680 Highland Ave.
Rochester,
New York 14610

Irving Norry
Box 51 - Rochester NY

פיליס אנדרה,
רח' שמגר 16,
צ.ה.ל.ה,
תל - אביב

31.7.1968

07 01 01

לכבוד
חברת שבת בע"מ,
אזור התעשייה,
ר.מ.ל.ה

לידי מר חיים סלבין, מנהל

א.נ.א.

כדי לענות לבקשת מועצת המנהלים של החברה וללמוד את
שיטת הבניה אשר פותחה ע"י כב' וכדי להביע דעתי בקשר להשקעות
בנושאות ושיטורים בוססים במפעל ברצוני לבקש מכב' להכין עבורי
את החומר המצויין להלן:

1. דוקומנטציה מושלמת על שיטת סלבין כפי שברשמה
במסרד הפטנטים.
 - 1.1 תיאור ממורט של השיטה כולל תכניות ומפרטים.
 - 1.2 תכניות ומפרטים של הציוד לייצור והרכבה.
 - 1.3 לייאוס ותכנית טכנולוגיה לייצור.
2. תכנית השקעה ממורטת להקמת המפעל כולל ציוד
להובלה והרכבה
 - 2.1 תכנית השקעה מקורית מושלמת וממורטת כפי שהוגשה
למסקיעים.
 - 2.2 העתק מפרוטוקל של אישור ההשקעה כולל לוח
זמנים מאושר להתקדמות עבודה וזרימת כספים.
 - 2.3 ציון המצב בהתקדמות ההשקעה עד 1.7.68.
 - 2.4 גא' לציין באם במצב הנכחי ללא השקעה נוספת
מסוגל המפעל ליצור שוטף ומה יכולתו.
 - 2.5 לוח זמנים להשלמת ההשקעה הדרושה כדי להגיע
ליכולת הממוכנת ע"י כב' ואשר עליו מבוסס
הישוב הכדאיות, ז"א 1000 יח' דיור בגודל
ממוצע של 70 מ"א בשתי משמרות ייצור לשנה.
3. אבקש להודיעני על ההתפתחויות על סמך הערותי לפי הפרוט
הבא:
 - 3.1 בדיקת תכנון של מהלכי מדרגות ופודסטים.
 - 3.2 הזמנת בסיון העמסה ע"י מכון.
 - 3.3 תכנית לתקון מהלכי המדרגות שהורכבו בבנין.
 - 3.4 סינוי בשיטת הובלת והרכבת מהלכי מדרגות ופודסטים.
 - 3.5 הכנת בסיון לציפוי קירות חוץ על קירות מחוץ למסכים.
 - 3.6 דוגמה לציפוי קיר חוץ ע"י פלסטרון.
 - 3.7 הכנת בסיון לעיבוד קירות היצוביים צרבוליסטיים
בשיטת ייצור וורטיקלי.

אחיה אסיר תודה לכב' באם יודיעני על לוח הזמנים לביסויים
הב"ל חיות ולפני ביצוע הביסויים ברצוני לראות את ההכנות, לקבוע
ביחד את מועדי ביצוע הביסויים ובכל מקרה אפשרי להיות נוכח בביצועם.

בכבוד רב,

א. פיליס

אברהם עקביה, רואה חשבון

A. AKAVIA, B.Sc., F.C.C.S., Certified Public Accountant

Haifa, 65, Ha'azmaout Rd., Tel. 531055

Tel-Aviv, 15, Carlebach St., Tel. 36121
38620

חיפה, דרך העצמאות 65, טל. 531055

תל-אביב, רח' קרליבך 15, טל. 36121
38620

תיק מס' 205

חיפה, י"ד בטבת ה'תשכ"ח
15 בינואר 1968

לכבוד
מר הלל אשכנזי
יו"ר הדירקטוריון
"שבח" חברה לייצור בתים להרכבה בע"מ
משרד השכון
תל-אביב

מר אשכנזי היקר,

הנני מתכבד להמציא לך בזה, כבקשתך, פירוט מצב החשבון של
"שבח" חברה לייצור בתים להרכבה בע"מ עם מר ח. סלבין.
הסכום העומד לזכותו של מר ח. סלבין ביום 1.4.67, לאחר
שהוקצו לו מניות בסך 700,000 ל"י (מזה לפי בקשת מר ח. סלבין
המחצית ע"ש בנו אמנון סלבין) הוא 180,234 ל"י.
מתוך הנחה שיושקעו השנה עוד 850,000 ל"י בהשלמת המפעל, הרי
לפי דמי פיקוח בשיעור של 3%, הסכום הנוסף שיגיע למר סלבין הוא
25,500 ל"י.
בהזדמנות זו הנני מעביר אליך העתק נוסף של הדו"ח המפורט
על ההשקעות ליום 31.3.65.

בכבוד רב,

אברהם עקביה

העתק: מר ח. סלבין, מהנדס
מר מ. לפיד, חבר דירקטוריון

REPORT OF THE
COMMISSIONER OF THE
LAND OFFICE

TO THE
LEGISLATIVE ASSEMBLY
OF THE
PROVINCE OF ONTARIO

1900

PRINTED BY
THE GOVERNMENT OF ONTARIO

REPORT
OF THE
COMMISSIONER OF THE
LAND OFFICE
TO THE
LEGISLATIVE ASSEMBLY
OF THE
PROVINCE OF ONTARIO

1900

THE
LAND OFFICE
OF THE
PROVINCE OF ONTARIO

REPORT
OF THE
COMMISSIONER OF THE
LAND OFFICE
TO THE
LEGISLATIVE ASSEMBLY
OF THE
PROVINCE OF ONTARIO

1900

THE
LAND OFFICE
OF THE
PROVINCE OF ONTARIO

1900

1900

REPORT
OF THE
COMMISSIONER OF THE
LAND OFFICE
TO THE
LEGISLATIVE ASSEMBLY
OF THE
PROVINCE OF ONTARIO

"שבח" חברה לייצור בתים להרכבה בע"מ

מצב חשבון עם מר. ח. סלבין

1. החישוב עד 31.3.65.

| ל"ח | ל"ח | ל"ח | יחידה |
|---------|---------|-----------|-------------------------------------|
| | | 1,995,692 | יחידה |
| | | 145,299 | ס"ח ההשקעות לפי דו"ח רואה החשבון |
| | | 2,140,991 | מפורעות לספקים 31.3.65 |
| | | 1,898,993 | נחשב מהממשלה |
| | | 241,998 | |
| | | 177,862 | נחשב מחברת "שבח" (עד 31.3.65) |
| | 64,136 | | |
| | 109,645 | 1,370,561 | 8% דמי תכנון ופקוח מקצועי מסך |
| | 21,248 | 708,278 | 3% דמי פקוח מקצועי והנהלת הבניה מסך |
| | 162,000 | | דמי שכירות לצידוד |
| 357,029 | | | |

2. שנת 1965/66.

| ל"ח | ל"ח | ל"ח | יחידה |
|--------|--------|-----------|-------------------------------------|
| | 33,946 | 424,325 | 8% דמי תכנון ופקוח מקצועי מסך |
| | 30,078 | 1,002,600 | 3% דמי פקוח מקצועי והנהלת הבניה מסך |
| | 33,000 | | דמי שכירות לצידוד |
| 97,024 | | | |

3. שנת 1966/67.

| ל"ח | ל"ח | ל"ח | יחידה |
|---------|--------|---------|-------------------------------------|
| | 5,817 | 72,718 | 8% דמי תכנון ופקוח מקצועי מסך |
| | 18,527 | 617,555 | 3% דמי פקוח מקצועי והנהלת הבניה מסך |
| | 10,000 | | דמי שכירות לצידוד |
| 34,344 | | | |
| 488,397 | | | ס"ח |

4. ניכויים.

| ל"ח | ל"ח | יחידה |
|---------|-------|---------------------------|
| | 6,803 | חיובים שונים בשנת 1965/66 |
| | 1,360 | חיובים שונים בשנת 1966/67 |
| 8,163 | | |
| 480,234 | | |

5. תמלוגים חד פעמיים (ראה הפרטים והתנאים בחוזה מיום 30.6.64)

| |
|---------|
| 400,000 |
| 880,234 |
| 700,000 |

6. מניות שהוקצו

| ל"ח | יחידה |
|---------|--------------------|
| 180,234 | יחידה ליום 31.3.67 |

יחידה זו אינה כוללת כל זיכוי בעד הצידוד האמריקאי.

• חשבונית מס' 266 - חשבונית מס' 266

החשבונית מס' 266 - חשבונית מס' 266

חש"מ 1,637

חש"מ 10

חש"מ 10

חש"מ 10

חש"מ 1,627

חש"מ 277

חש"מ 277

חש"מ 250

חש"מ 250

חש"מ 1,100

חש"מ 1,100

++ א חש"מ 1,100 חש"מ 1,100 חש"מ 1,100

100-443887-100

1242241 *See* 1242242

44275-44284

10100000

5182-1137-3-11

22440

41047273

++ 2 4747 01500 42200 0000 0000

כספי ושות'
קורבני-ריין ונוטריונים
CASPI & Co.

BARRISTERS-AT-LAW, ADVOCATES & NOTARIES

MICHAEL CASPI
SHLOMO LEVRON
RAM CASPI

CHAIM GLASER
CHAIM ADINI
DAVID COHEN
MOSHE WAGNER
ZVI HARTAL
MOSHE NISSIM
ZVI RAPAPORT
RAANAN RON
AHARON BAVARSKY
ISRAEL S. KANTOR

מיכאל כספי
שלמה לברון
רם כספי

חיים גלזר
חיים עדיני
דוד כהן
משה וגנר
צבי הר טל
משה נסים
צבי רפפורט
רענן רון
אהרון בברסקי
ישראל ז. קנטור

תל-אביב, 4 בינואר 1968.

TEL-AVIV תל-אביב
SHALOM TOWER מגדל שלום
ACHAD HA'AM ST. 9 רח' אחד העם
PHONES: 57137-57138-57139 טלפונים
CABLES: SHAKSPEARS TEL-AVIV

JERUSALEM ירושלים
BEN YEHUDA ST. 12 רח' בן-יהודה
TELEPHONE 26634 טלפון

HAIFA חיפה
NORDAU ST. 9 רח' גורדאו
TELEPHONE 40980-40989 טלפון

Our Ref. מספרנו ס/140/לב/יפ.

לכבוד
מר הלל אשכנזי,
סמנכ"ל משרד השיכון,
הקריה, תל-אביב.
א.נ.

הנדון: "שבח" חברה לייצור בתים להרכבה בע"מ

על פי בקשתך הנני להביא בפניך תמצית זכויותיו של המהנדס חיים סלבין הן מכתב ההסכם היסודי שנחתם בזמנו בין המדינה לבינו והן מכתב עבודותיו עבור החברה וכלל שרותו במפעל.

א. על פי סעיף 17 (1) (א) מן ההסכם היסודי, זכאי מר סלבין לקבלת 10% מהון מניותיה הרשום של החברה ללא תשלום כסף על ידו, בתורה תמלוג חד פעמי, דהיינו 400,000 מניות רגילות בנות 1 ל"י כ"א.

ב. מר סלבין השתמש באופציה שניתנה לו בסעיף 7 (1) מן ההסכם לרכוש מניות נוספות בשיעור 15% מהון המניות הרשום, כלומר 600,000 מניות רגילות בנות 1 ל"י כל אחת. כתמורה עבור רכישת המניות ישמשו זכויותיו של מר סלבין בעד הציוד והמכונות שהעביר לבעלות החברה.

עד כה הוקצו על ידי החברה 700,000 מניות לזכות מר סלבין (מחציתן לשמו של אמנון סלבין בתוקף העברה מאביו).

ג. בתוקף סעיף 3 (5) מן ההסכם ותקנה 71 (4) לתקנות החברה, זכאי מר סלבין לייצוג יחסי במועצת המנהלים לפי חלקו בהון המניות.

ד. בהתאם לסעיף 9 (א) מההסכם בוצעה הערכת שוויין של המכונות ושל הציוד שנבנו על ידי מר סלבין עד ליום 1.4.65, הוא היום בו נפתחו פנקסי החברה.

בישיבת ההנהלה מיום 3.1.65 נקבעו ההנחיות בדבר קביעת שוויין של המכונות והציוד האמורים, וועדת ההערכה פעלה על פיהן.

הועדה קבעה כי הערך הממשי לפי מחירי השוק הוא סך 1,147,000 ל"י.

מאידך עלתה בניית המכונות והציוד לפי רישומיו של מר סלבין בסכום קטן יותר, דהיינו סך

770,000.-

377,000.-

נוצרה איפוא יתרה לזכות בסך

שלגביה שמורה זכותו של מר סלבין לתבוע את תשלומה מתוך רווחי החברה לכשיווצרו.

WILLIAMS & CO.
STATIONERS & PRINTERS
CASA 1 & 2

WASHINGTON, D. C. 20540

WILLIAMS & CO.
STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO.
STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO.
STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

WILLIAMS & CO. STATIONERS & PRINTERS
CASA 1 & 2
WASHINGTON, D. C. 20540
TELEPHONE: 222-1111
FAX: 222-1111
E-MAIL: WILLIAMS@CASA1.COM

אל: מר הלל אשכנזי.

ה.

ביחס לציוד האמריקאי שנרכש בזמנו על ידי מר סלבין, נעשתה הערכת שוויו עוד בחודש מאי 1962 על ידי המכון לפיריון עבודה, ולכן ועדת השלושה שוחררה מהתפקיד לבצע הערכה חדשה.

ההערכה משנת 1962 מסתכמת בסך - 169,296 ל"י. לעומת הסך - 197,400 ל"י שנדרש אותו זמן על ידי מר סלבין.

בהקשר זה יש להזכיר את החלטת ההנהלה מיום 3.1.65 כי כל הציוד והמכונות שנרכשו על ידי מר סלבין בחו"ל יועברו לבעלות החברה במחירי רכישתם.

יחד עם זאת תובע מר סלבין תוספת שווי בגלל פיצוח הלירה שנעשה בפברואר 1962.

בתוקף הסעיף 17 (1) (ב) ו-(ג) מן ההסכם, זכאי מר סלבין לתמלוגים עבור השימוש בשיטתו, והם בשיעור של 2% מכלל המכירות של הצגות ובשיעור של 15% מהרווח נטו כפי שהוגדר שם.

על פי האמור בסעיף 22 מן ההסכם חייבת החברה להעסיק את מר סלבין בתפקיד מנהל המפעל במשך תקופה של 5 שנים מיום הפעלתו של המפעל, תמורת שכר בשעור המקובל במפעלים ממשלחיים או צבוריים בהיקף דומה.

בהחלטת ההנהלה מתאריך 3.1.65 נקבע כי מר סלבין יקבל שכר תיכנון ושכר פיקוח בגין העבודות הבאות: הכשרה ופיתוח של המגרש ברמלה, עבודות הבנייה שבוצעו עד יום 1.4.65.

מאחר וביחס לתקופה שלאחר 1.4.65 טרם נקבע כל הסדר כספי עם מר סלבין, החליטה ההנהלה בישיבתה מיום 27.3.66 לשלם לו סכום כולל אחד פעמי של - 30,000 ל"י על חשבון כלל שירותיו לחברה מאז 1.4.65.

כפי שתיווכח מקריאת הסקירה דלעיל, נמנעתי מהבעת דעה כל שהיא בדבר איכותן או שוויון הכספי של הזכויות אותן פירסתי, ואולם אהיה נכון לעשות זאת אם אדרש.

בכבוד רב,

ש. לברון, ע"ד,
כספי ושות'

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

UNIT 10

H. SLAVIN, Consulting Engineer
43, Frishman Street
Tel-Aviv, Israel
Phone: 239518

Sept. 24, 1967

ADVANTAGES OF THE SLAVIN PROCESS OF MASS PRODUCTION OF R.C. HOUSING UNITS

1. The future belongs to industrialised building

Technological development in all fields of production inevitably leads the building practice in the direction of what is known as prefabrication, but should properly be called mass production.

The causes are:

- 1/1 Labour everywhere prefers more and more work not involving physical effort; moreover, the builder's wages are higher than the factory worker's.
- 1/2 The possibility of year-round production, with assembly confined to periods of favourable weather, is compatible with labour's claim for an assured annual income.
- 1/3 The far superior quality of the industrial product.
- 1/4 Drastic reduction of the time required for erecting the buildings - usually 2 months instead of a whole year, with working capital and financing costs reduced as a result.
- 1/5 Still lower cost of industrialised building in the future.
- 1/6 In countries with high income tax, the advantage of paying part of the taxes through capital gains.

2. Why is the progress of building industrialisation so slow?

- 2/1 All existing methods of industrialised building - full and partial, in factories and in field plants - cover a total of not more than 10% of the overall building activity, while 90% are still by conventional methods (except the USSR). The reasons are, in our view:
- 2/2 Existing methods are still not sufficiently industrial and involve considerable amounts of manual labour and physical effort. The technological revolution has not yet reached this industry.
- 2/3 Only 60% of the process are completed at the plant. The remaining 40% are carried out on the site, more or less under conventional conditions but utilising heavy equipment which is highly expensive and unnecessary for the actual conventional techniques.

Washington, D. C.

February 1, 1917

Dear Sir:

I have the honor to acknowledge the receipt of your letter of January 31, 1917, in relation to the matter of the proposed amendment to the National Convention of the American Society of Civil Engineers.

The proposed amendment is as follows:

"The National Convention of the American Society of Civil Engineers shall be held at the city of New York, New York, in the year 1918."

The proposed amendment is in accordance with the recommendation of the Executive Committee of the American Society of Civil Engineers, and is hereby approved.

Very respectfully,
Secretary

Enclosed for you are two copies of the proposed amendment, one of which is for the National Convention of the American Society of Civil Engineers, and the other is for the National Convention of the American Society of Mechanical Engineers.

I am, Sir, very respectfully,
Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

Very truly yours,
Secretary

- 2/4 All these techniques thus combine the drawback of high investment characteristic of an industrialised process - without the advantage of a high output - on the one hand, and the drawback of 40% manual labour (as in conventional methods) on the other.
- 2/5 The result is that the cost per sq.m. floor area by an industrial method is likely to be close to the cost by a conventional one.
- 2/6 The other characteristics of industrialisation (quality, speed, economy in skilled manpower) are secondary advantages which cannot provide an incentive in replacing conventional methods.
- 2/7 An additional drawback of existing prefabrication lies in sealing of slab joints - a still unsolved problem.

In order to overcome the above drawbacks, which impede the development of industrialisation, we devoted 15 years of work, with investment running into millions, in developing an industrialised process capable of replacing conventional building technique in a very short time - not merely on the strength of secondary advantages, but on the solid grounds of lower production- and erection costs compared both with conventional methods and with other existing industrial techniques.

3. What are the advantages of the Slavin process?

- 3/1 Like any true industrialised method, the Slavin process reduces the cost per housing unit compared with conventional or existing industrial techniques.
- 3/2 For example, a 70 sq.m. unit (3 rooms, kitchen and conveniences) requires by our method (in addition to the material, which is almost the same by any method in the case of reinforced concrete) 70-80 workdays, from raw material to delivery.
- 3/3 By other industrialised methods the number of workdays is of the order of 120, and by conventional methods - over 200.
- 3/4 Our process uses large slabs, variable according to type of structure and size of unit, width 8.5-25 m, length as desired. The attached plans give an idea of these possibilities and present six types of housing units and three types of buildings.

The flexibility of the process permits adaptation to clients' requirements in different countries and under different conditions.

- 4) The first of the two main types of investment is the so-called "horizontal" investment, which is directed towards the production of goods and services which are similar to those which the investor is already producing. This type of investment is usually motivated by the desire to expand the firm's market share or to diversify its product line. It is usually financed by the firm's own resources or by bank loans.
- 5) The second type of investment is the so-called "vertical" investment, which is directed towards the production of goods and services which are different from those which the investor is already producing. This type of investment is usually motivated by the desire to enter new markets or to diversify the firm's product line. It is usually financed by the firm's own resources or by bank loans.
- 6) The third type of investment is the so-called "diagonal" investment, which is directed towards the production of goods and services which are different from those which the investor is already producing, but which are related to them in some way. This type of investment is usually motivated by the desire to enter new markets or to diversify the firm's product line. It is usually financed by the firm's own resources or by bank loans.

In order to overcome the above-mentioned difficulties, the investor must first of all decide on the type of investment which he wishes to make. He must then decide on the amount of capital which he wishes to invest. Finally, he must decide on the type of financing which he wishes to use. Only by following these steps can the investor hope to achieve a successful result.

- 7) The first of the two main types of investment is the so-called "horizontal" investment, which is directed towards the production of goods and services which are similar to those which the investor is already producing. This type of investment is usually motivated by the desire to expand the firm's market share or to diversify its product line. It is usually financed by the firm's own resources or by bank loans.
- 8) The second type of investment is the so-called "vertical" investment, which is directed towards the production of goods and services which are different from those which the investor is already producing. This type of investment is usually motivated by the desire to enter new markets or to diversify the firm's product line. It is usually financed by the firm's own resources or by bank loans.
- 9) The third type of investment is the so-called "diagonal" investment, which is directed towards the production of goods and services which are different from those which the investor is already producing, but which are related to them in some way. This type of investment is usually motivated by the desire to enter new markets or to diversify the firm's product line. It is usually financed by the firm's own resources or by bank loans.
- 10) The fourth type of investment is the so-called "conglomerate" investment, which is directed towards the production of goods and services which are completely unrelated to those which the investor is already producing. This type of investment is usually motivated by the desire to enter new markets or to diversify the firm's product line. It is usually financed by the firm's own resources or by bank loans.

- 3/5 The flexibility of the process also permits production limited to wall- or floor slabs only, as well as production of elements for industrial buildings. The process can be completed in the factory, or alternatively brought up to the finishing stage, with the elements assembled and erected by other techniques, according to local conditions and clients' requirements.
- 3/6 The factory and equipment can be set up in permanent form, as well as in the form of a field plant for a specific project, after whose completion the equipment can be transported elsewhere. Such a field plant is much cheaper than a permanent installation, but obviously has economic disadvantages.

The attached report and economic calculation give an idea of the order of magnitude of the investment.

- 3/7 The workday calculation is based on a rate of one day per sq.m. floor area. The manpower- and wages schemes are given in the attached report.
- 3/8 Apart from a small skilled staff for operating the technological equipment, our process permits 90% of the work crew to be trained in a few weeks.

4. Industrialised method vs. manual labour

- 4/1 The method requires almost no manual labour or physical effort.
- 4/2 All casting, without exception, is carried out vertically. A crew of only 2 or 3 is required for operating electrical and pneumatic accessories. A pair of floor- or wall slabs, 2x20 sq.m. in size and up to 15 ton weight, can be cast in up to 20 min. This technology is based on a series of patents and is the outcome of many years of research.
- 4/3 The slabs, cured on both sides, are ready for stripping in 4 hours.
- 4/4 10 forms, operated by a crew as above in 8-hour shifts, produce in one day all the large elements for a pair of 70 sq.m. units. Other industrialised methods, most of which are horizontal, do not permit such results. A grinding process with special equipment, protected by numerous patents, renders the elements interchangeable, thereby satisfying the basic requirement of industrialisation and obviating the need for hand-finishing during assembly.

5. New technology (see detailed description).

- 5/1 All the advantages of the process, both technical and economical, are the outcome

• 100 •

100-443882-100

of 15 years of research and of a special technology, hitherto not applied in any other known industrialised method.

- 5/2 The reinforcement of the floor and wall slabs consists of rigid three-dimensional assemblies (patented) into which all required inserts can be welded: door and window lintels, binding and stiffening brackets, wiring and piping - a total of several hundred in each unit.

This technology saves much manual labour in mounting the doors, windows and electrical, water-supply and sewage systems.

- 5/3 The reinforcement assemblies permit insulation to be provided inside the elements during the casting process. To the best of our knowledge, this has not been realised to-date in any industrialised process.

- 5/4 The reinforcement assemblies are adapted for precision welding of nuts in them. This technique (again, first of its kind in industrialised building) replaces the projecting steel bars used in all other methods.

Its advantages are as follows:

- a) The nuts are installed in the course of the factory process.
- b) It facilitates precision grinding of the slabs without interference of the projecting steel bars.
- c) The elements are bolted together immediately on being erected, thus dispensing with temporary scaffolding, which encumbers most other methods and involves much expense.
- d) From the assembly viewpoint the elements resemble a steel structure - an enormous advantage obvious to those familiar with handling concrete slabs.
- e) The time required for setting each element in place is reduced considerably, thereby improving the output of the crane, which is the most expensive item of the technological equipment.
- f) It solves the problem of joint sealing. The seal (which can be rubber, plastic etc.) is compressed by the bolts and ensures complete tightness, as in motors or in compressed-air and gas vessels.

In all existing methods, the effectiveness of the seal is conditional on its flexibility, which raises the difficult problem of preserving it over prolonged periods and preventing cracks. In addition, the characteristically "prefabricated" appearance of the building is sometimes undesirable from the architectural point of view.

- g) Joining of slab nuts by welding permits formation of reinforced-concrete membranes in any desired dimensions.
- h) The sealing effect obtained by means of the bolts would have been impossible but for the precision fit of the slab edges, ensured by the grinding process described above.
- i) The joint mortar between the slabs is cast internally, with the slabs in a tight fit and the seals in place. In these circumstances, this does not interfere with the finishing operations, including painting, in contrast to other techniques involving open casting of the joints.

To conclude:

- The assembly process is dry.
- Walls are bolted immediately on being set in place, without auxiliary scaffolding.
- Seals are compressed by the bolts, the joints are cast internally and there is no leakage of the mortar.

6. Site operations

- 6/1 Assembly and erection are facilitated by a new technique, involving plant-assembled integral units consisting of small elements which are installed on the site in a single operation. For example, bathrooms and toilets are delivered as a single 11 ton unit comprising bathtubs, basins and piping in finished form (including painting). Such a unit can be installed in a few minutes. The kitchen unit is produced in the same way.
- 6/2 The number of crane runs for the 70 sq.m. housing unit in question is thus reduced to 14 - about half the number by other industrial methods.
- 6/3 Assuming the erection of each element requires about $\frac{1}{2}$ hour crane time, the overall erection time for a complete housing unit is less than 8 hours, with a crew of three. With such crews working in three 8-hour shifts, the daily output of the crane is 3 units - at least 50% more than by any method based on the use of temporary scaffolding.
- 6/4 Subsequent operations - casting of the joints, paint repairs, installation of doors and boilers, wiring and marking for further erection steps which require large crews and daylight - are carried out in a single shift or occasionally in two shifts. This practice of working round the clock with a small crew, or 8 hours with a large crew, is one of the advantages of our process.

- 6/5 Erection time for a 4-story, 40-unit building, of the type now under construction in Israel, is estimated at 6 weeks from start to delivery - a very short time compared with one year by conventional methods.
- 6/6 The erection operations require only 10-15% of the plant manpower. The rest of the work is carried out inside the plant, so that wages are lower, and the output higher, compared with open-air work.

Briefly, the advantages of the Slavin process are:

- 1) No manual labour, and no need for physical effort.
- 2) 40% less wages compared with any other industrialised method.
- 3) Plant investment does not exceed the normal level - about \$ 350.000 per unit per day.
- 4) Flexibility of equipment, from a complete factory to a mobile field plant.
- 5) Minimum number of crane runs per unit (14 for 70 sq.m. unit).
- 6) Short erection time - 6 weeks for a 40-unit building. (Of course, excluding foundations).

H. SLAVIN

CONSULTING ENGINEER

43, FRISHMAN STREET, TEL-AVIV, ISRAEL

PHONE 226518, PHONE OFFICE 961446 - 961680

*****P

LIST OF CONTENTS

ANSWERS TO THE QUESTIONS

| | <u>Page</u> |
|---|-------------|
| Summary | I |
| Question No 1 | 5 |
| " " 2 . (incl.list of drawings) | 7 |
| " " 3 | 8 |
| " " 4 | 9 |
| " # 5 | 9 |
| " " 6 | 27 |
| " " 7 | 28 |
| " " 8 | 28 |
| " " 9 | 29 |
| " " 10 | 30 |
| List of photographs | 33 |

All rights reserved for Dr. H. Slavin.

43, Frishman Street, TEL- AVIV, Israel

W. H. H.

RECEIVED

DATE: 1914

ORDER + ORDER

LIST OF ORDERS

1914

1.
2.
3.
4.
5.
6.
7.
8.
9.
10.
11.
12.
13.
14.
15.
16.
17.
18.
19.
20.
21.
22.
23.
24.
25.
26.
27.
28.
29.
30.
31.
32.
33.
34.
35.
36.
37.
38.
39.
40.
41.
42.
43.
44.
45.
46.
47.
48.
49.
50.
51.
52.
53.
54.
55.
56.
57.
58.
59.
60.
61.
62.
63.
64.
65.
66.
67.
68.
69.
70.
71.
72.
73.
74.
75.
76.
77.
78.
79.
80.
81.
82.
83.
84.
85.
86.
87.
88.
89.
90.
91.
92.
93.
94.
95.
96.
97.
98.
99.
100.

11 1/2 in. x 1 1/2 in. 11 1/2 in.
12 1/2 in. x 1 1/2 in. 12 1/2 in.

13 1/2 in. x 1 1/2 in. 13 1/2 in.
14 1/2 in. x 1 1/2 in. 14 1/2 in.

LIST OF QUESTION

- 1) The technological scope of the process - i.e. design data of the product and its uses in multistory buildings.
- 2) Examples of projects of this kind already studied, or preferably realised - to permit assessment of the flexibility of the process or its adaptability to different floor-plans and layouts .
- 3) The acoustical and thermal properties of the elements.
- 4) A statical analysis of the process - to permit assessment of its adaptability in practice to the various national codes of r.c. construction.
- 5) A detailed description and cost estimate (in dollars) of equipment required for the plant.
- 6) A description of the plant, and an estimate of the non-recurrent permanent cost items (machinery foundations, premises, special equipment etc.).
- 7) The planned production capacity of the plant, or its output in elements or rooms, and the flexibility of the production process.
- 8) Details of the raw materials required for producing the elements.
- 9) Data on the manpower required at plant - e.g. the estimated man-hours per element p or per room.
- 10) A description of the lifting-, transportation-, and erection-site equipment, including times and techniques.

Dr. H. Slavin

S U M M A R Y

Question No. 1. - Our process is suitable for multi-story buildings, up to 20 stories if proper equipment is available. It is not suitable for single-story houses in its present form, but we believe it can be adapted if necessary.

The process is based on casting large slabs 20 m^2 each. Where smaller elements are required, they are cast jointly and cut up subsequently. Slab thickness is as required; in the local project it ranges from 6 to 20 cm. Conveniences are assembled from small elements at the plant and delivered as a single unit to save labour. Door- and window lintels, piping conduits, wiring boxes etc. are provided in the walls in order to permit all site operations to be completed within a day or two.

The capacity of an erection crane, using a special technique, is two units per day.

No open castings are required, all joints are injected in closed form.

The size of the unit is adjustable as required.

By providing a 30% reserve in forms, running modifications can be effected with minimum labour requirements and without interference with regular production.

Question No. 2. - Our plant was planned for production for the Israel Ministry of Housing, according to whose specifications a 70 m^2 unit in four-story buildings was designed. To permit two frontages, the sanitary block is located inside the unit with artificial ventilation, but this is optional. Sliding windows in the living rooms. Plastic flooring, hot-water and central gas supply, central television facilities.

Question No. 3. - The building material is concrete equivalent to the ordinary type, except for higher consistency and strength. External walls and floors can be insulated. In addition to insulating the floors, soundproofing is obtainable by conventional

means dependent on the envisaged level of investment.

Question No. 4. - The statical analysis prepared for the local project by Dr. S. Rosenhaupt, a prominent designer, is enclosed.

Question No. 5. - The cost of the equipment is governed by site conditions, size of plant, envisaged radius of transportation, maintenance requirements, etc. The cost of installation and premises is more dependent on local conditions than the cost of the equipment, which may range from \$ 250,000 to 350,000 per unit daily output.

If the plant is confined to the conventional prefabrication stages, cost will be reduced accordingly. These stages comprise the following departments:

(1) Reinforcement. Three-dimensional assemblies are prepared from round steel wire, with provision for connections, inserts, insulation etc. The assemblies are inspected before being placed in the forms.

(2) Batching plant. An outside source can be used, subject to economic considerations.

(3) Mix transportation, direct from batching plant to forms.

(4) Casting, using special vertical forms (air-vibrated) and a hopper (with two 40 HP electric vibrators). An annual output of 1,000 units requires 10 such forms plus 6 smaller ones. The casting process is mechanised and effortless. A 14.5 ton casting requires 20-40 minutes. The smaller forms are operated in sets and the time required is about one hour.

The above covers the equipment of a conventional prefabrication plant. Our process comprises the following additional stages:

(5) Grinding. This stage eliminates the need for in-situ open casting of joints. The slabs are ground to correct size and junction angle, thereby permitting

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

injection of internal joints after all finishing operations have been completed. In addition, a large grinding machine for correcting defective slabs is available.

(6) Vertical storage. Storage facilities for 4 days' output with provision for enlargement.

(7) The plant is in U form, and the castings have to be shifted between parallel lines. Special trolleys are used.

(8) Finishing. Inspection of slabs, application of rubber fittings for the joints, wiring, painting etc. The sanitary block and pantry block are assembled in a special subdepartment.

(9) Despatching. This stage is an extension of the production process, not of the storage operation. The finished slabs are loaded on trailers from overhead platforms, and unloaded at the site in the same way. A hydraulic jack system is used, dispensing with additional labour.

(10) Foundations and beams are cast in situ by means of special precision instruments.

(11) Erection. Preparation of the crane is simple and no tracks are required.

Question No. 6. - The type of premises required for the plant depends on local conditions and scope of process. The present premises cover $13,000 \text{ m}^2$, with different heights. Its total cost, including earth work and roads, was \$ 700,000.

Question No. 7. - The plant can be designed for any capacity, as required (1000 units per year in our case).

Question No. 8. - Conventional building materials are required, and any mix in common use is suitable. Reinforcement is ordinary twisted or prestressed steel,

subject to requirements and economic considerations. The exterior is unrendered.

Question No. 9. - Manpower requirements depend on the type of plant. For a plant of the present type using imported materials such as plastic flooring (even if carried out by subcontractors), a total staff of 250 will be required, including administrative and clerical employees.

Question No. 10. - See preceding questions.

Economic calculation. A completed plant will return the investment in 7 years (7,000 units) at a profit of \$ 300 per unit. As the plant retains its full value after 7 years, the profit per unit will then amount to \$ 600. (Rates based on local popular housing standards). In the free-market the profit margin is much larger.

QUESTION NO. 1 - SCOPE OF PROCESS

The method is based on r.c. slabs:

1/1 Size 8 m length, up to 3 m width or height.

1/2 The slabs fall into four categories:

1/2/1 Floor slabs - length up to 7 m, width up to 3m, thickness as required.

Details on reinforcement see Question No.4. These floors are supported on lateral walls bearing the entire building load. (Photo 1, Drawing No. 2/3)

1/2/2 Lateral walls - length up to 8.5 m, width up to 2.6 m, thickness as required.

Reinforcement in the form of rigid 3-dimensional assemblies, with provision for wiring, piping etc. (Photo 2, Drawing 2/4). Details on reinforcement - see Question No.4. The process for preparing and mounting the assemblies has been patented.

1/2/3 Longitudinal walls - length 7 m, height up to 2.6 m, thickness as required.

Reinforcement is 3-dimensional and rigid as in the lateral walls, but permits mounting of lintels as well as thermal insulation. To the best of our knowledge, we are the first to cast insulated walls up to 20 kg/m^3 in vertical forms without manual labour. (Photo 3, Drawings 2/5 and 2/6). Details of reinforcement - see Question No.4.

1/2/4 Full-height partitions in various lengths. Thickness 6 cm or more. Single-mat reinforcement.

1/2/5 Hollow elements for sanitary block (including lavatory and shower), provided with piping conduits. Hollows serve for positive ventilation.

1/2/6 Small elements for the sanitary and pantry blocks are cast as large slabs with the reinforcement exposed at suitable points.

To sum up, the standard models are as follows:

| <u>width (m)</u> | <u>length (m)</u> | <u>appr. gross area (m²)</u> |
|------------------|-------------------|---|
| 8,650 + 1,500 | 8 | 80 |
| 8,650 + 1,500 | 11,5 | 110 |
| 8,650 + 3,000 | 11,5 | 130 |
| 8,650 + 4,500 | 11,5 | 150 |
| 8,650 + 6,000 | 11,5 | 170 |
| 8,650 + 6,000 | 15,0 | 220 |

1/10 All alterations in the above dimensions are based on varying the number of elements without modifying the forms. Smaller-size intervals will require additional forms for basic elements of other dimensions. Forms are so designed that such modifications are readily effected, and a 30% reserve in forms will permit a smooth change-over without interference with regular production.

QUESTION NO. 2 - DATA ON REALISED PROJECT

Enclosed drawings:

2/1 General floor plan of a unit and front view.

2/2 Floor slab cut in two at the plant.

Each half is used for assembling a sanitary block, comprising lavatory with positive ventilation (complete with accessories), shower with positive ventilation (complete with piping closet), washbowl, bathtub and laundry closet.

2/2/1 Floor slab, including wiring.

2/2/2 Upper and lower reinforcement.

2/2/3 Sanitary block in the assembly jig (see also Photo 5 and 6)

2/3/1 Ordinary floor slab (Photo 1).

2/3/2 & 2/3/3 Reinforcement.

$$\frac{1}{\Gamma(\alpha)} \int_0^t (t-\tau)^{\alpha-1} f(\tau) d\tau = \frac{1}{\Gamma(\alpha)} \int_0^t (t-\tau)^{\alpha-1} f(\tau) d\tau$$

1000 900 800 700 600 500 400 300 200 100 0

1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 26

- 2/4/1 Lateral wall (Photo 2).
- 2/4/2 Reinforcement.
- 2/5/1 External wall, kitchen side (Photo 3).
- 2/5/2 Reinforcement.
- 2/6/1 External wall, balcony side (Photo 8F)
- 2/6/2 Reinforcement.
- 2/7/1 Partition
- 2/7/2 Reinforcement.
- 2/8 Sanitary block.
- 2/9 Pantry
- 2/10 Section through stair well.

QUESTION NO. 3 - INSULATION PROPERTIES OF SLABS

- 3/1 Slabs cast by our method do not differ from those by any other method, except that external vibration at 8,000-9,000 cps ensures higher density and strength, unobtainable by any conventional method or by ordinary internal vibration.
- 3/2 The special patented reinforcement assemblies permit an insulating layer to be provided in the centre of the external wall slabs (Photo 4).
The insulation used in the local project has a weight of 18 kg/m^3 . The maximum curing temperature permissible is 90°C .
- 3/3 Soundproofing of floor slabs: An insulating layer (as in wall slabs) is feasible, but experts question its effectiveness. In the local project, felt can be laid under the plastic flooring. This is comparatively cheap but has its disadvantages. The commonly-used local technique of tiling over a sand base is undesirable in prefabrication. Obviously the problem is not one of concrete technology, but of local conditions and limits of investment.

(48)

QUESTION NO. 4 - STATICAL ANALYSIS

At our request, Dr. S. Rosenhaupt, a prominent local engineer in charge of the calculations for the local project, prepared a detailed statical and engineering analysis in English and an evaluation of the applicability of our method overseas in terms of the national codes. For the local project, all calculations were based on the French code, but will be adapted to any other code upon request. A copy of Dr. Rosenhaupt's report is enclosed.

QUESTION NO. 5 - DETAILED DESCRIPTION AND COST ESTIMATE OF PLANT EQUIPMENT

- 5/1 The cost of the equipment depends directly on:
- 5/1/1 Production capacity: An output of 4 units per day (70 m^2), as at the local plant, is considered normal. Larger capacities are preferable in order to increase the flexibility of the plant and reduce investment per unit.
 - 5/1/2 Completeness of process - 95% at the plant, or alternatively only 60% at the plant with finishing operations (painting, wiring, flooring, etc.) assigned elsewhere.
 - 5/1/3 Power and water supply, sewerage facilities, the need for generators, limitations on the size of motors etc.
 - 5/1/4 Envisaged transportation radius.
 - 5/1/5 Proportion of reserve equipment (dependent on maintenance and repair facilities).
 - 5/1/6 Proportion of locally-available and imported equipment.
 - 5/1/7 Installation and operation of the equipment is dependent even more on local conditions, labour practices, etc.
 - 5/1/8 To give some idea of the order of magnitude, we regard the sum of \$250,000-350,000 per unit per day as reasonable, i.e. \$ 1,000,000 -1,400,000 for a plant

THE
OFFICE OF THE
SECRETARY OF THE
NAVY

Washington, D. C.
April 1, 1900
Honorable Mr. [Name]
[Address]
[City]
[State]

Dear Sir:

I have the honor to acknowledge the receipt of your letter of the 27th inst. in relation to the [subject]. The [subject] is being considered by the [department] and a decision will be reached as soon as possible. I am, Sir, very respectfully,
Yours very truly,
[Signature]

Very truly yours,
[Signature]

Enclosed for you are [number] copies of [document].

I am, Sir, very respectfully,
Yours very truly,
[Signature]

Very truly yours,
[Signature]

Very truly yours,
[Signature]

with an output of 4 units per day (280 m^2). If elements are to be delivered at 60% completeness (as by other methods), the investment is much lower.

5/1/9 Installation costs cannot be estimated without information on local conditions, but a rate of 20% of the equipment cost would be reasonable. This does not include earthwork, premises, power supply etc.

5/2 A detailed description of the equipment would comprise some 2000 drawings and a large volume of printed matter. This is obviously ruled out at the present stage of the negotiations, as the equipment is protected by numerous patents and is the outcome of 15 years of research work in which millions were invested. Disclosure of all details is thus conditional on a contract. Still, we shall attempt to provide some idea of the plant.

Reinforcement-assembly department

(photo 9)

Equipment

- 5/3/1 Trolley and track system for delivering round steel in the required sizes (Photo 9); monorail system, capacity 2 tons, track length 120 m.
- 5/3/2 Cutting equipment (up to 25 mm diameter).
- 5/3/3 Twisting machine for floor reinforcement, with 15 HP motor.
- 5/3/4 Transportation system to welding stage.
- 5/3/5 Automatic point-welding machine (4 m high, 3 m wide, 40 m long) for steel lengths up to 8.5 m for floor mats (see Photo 11).
- 5/3/6 Rotary benches (8 m length, 3 m height), for preparing wall assemblies for arc welding, with mountings for each type of assembly.
- 5/3/7 Assembly welding system, each assembly consisting of 2 mats (accuracy $\pm 2 \text{ mm}$) with provision for:

a) Lifting and connection nuts for slabs in vertical and horizontal positions
(Photo 10)

b) Door and window lintels

c) Nuts for wiring and piping

d) Brackets for water heaters etc.

e) Strips for bathtubs and other accessories

f) Insulation.

For each set of 2 units, about 80 different nuts and 100 steel plates must be provided, in addition to the various openings in the castings.

5/3/8 1 ton crane (8 m high) for transporting the reinforcement assemblies during production.

5/3/9 System (5 m high, 10 m wide, 20 m long) for transporting the assemblies to inspection department.

5/3/10 Inspection department, where each assembly is checked for the location of the inserts and hollows, and all studs for the hollows are installed (see Photos 12 & 13).

5/3/11 A mobile tower crane (height 10 m, track length 20 m, capacity 2 t/m) transporting the pairs of assemblies to the casting machine and installing them by means of conical studs at ± 2 mm accuracy, whereby the hundreds of inserts are positioned correctly in the casting.

5/3/12 A device (8 m long, 220 mm high, 200 mm wide) combining the assemblies into a set as above. This device holds the assemblies in rigid position throughout the casting process in spite of the intensive external vibration. Six 1" nuts provided in the assemblies are used for demoulding, for transportation to the finishing stage and to the site, for connecting the walls and floors, and for cutting large slabs in half.

5/3/13 Patents cover:

- a) The idea and technique of reinforcement assemblies ensuring rigidity even if made of 3-4 mm wire in order to save steel.
- b) The idea and technique of using reinforcing mats as a production agent, never attempted before.

This technique permits conversion of the process to an industrial scale, which alone ensures quality and low cost.

Batching plant (Photo 14).

5/4 In our process the mix is used in amounts up to 14.5 tons (6 m^3) in standard transporting devices, so that any batching plant (even one outside the plant) is suitable. In our case a special plant was preferred as more suitable for the mix production. The mixer is placed on a weighbridge (40 tons), and mobile silos (charged by means of two mechanical loaders mounted on tractors) and a mobile conveyor feed the aggregates into the mixer by weight.

Equipment

- 5/4/1 2 mechanical loaders.
- 5/4/2 2 mixers (6 m^3) mounted on a 20 ton truck with special drive.
- 5/4/3 40 ton weighbridge with $8.5 \times 3 \text{ m}$ platform, with provision for taring the truck (accuracy $\pm 5 \text{ kg}$).
- 5/4/4 4 silos (2 m^3 each) mounted on trolleys for four types of aggregate - sand and 2-4, 4-7 and 7-25 mm coarse fractions. Capacity of silos corresponds to one 14.5 ton batch. Each silo is equipped with an electromagnetic vibrator and a pneumatic chute.

- 5/4/5 A mobile conveyor (belt width 60 cm) transporting the aggregates from the silos to the mixer, capacity $1 \text{ m}^3/\text{min}$.
- 5/4/6 Cement silos with screw feeder, capacity 700 kg/min.
- 5/4/7 Water heater, capacity 10 m^3 , heating rate 20 to 90°C , $4 \text{ m}^3/\text{hour}$.
- 5/4/8 Hot water pump, pressure 3 kg/cm^2 , capacity $60 \text{ m}^3/\text{hour}$.
- 5/4/9 Small mixer (capacity 500 kg) mounted on truck, for sand-cement casting of slab base.
- 5/4/10 Reserve stocks of aggregate are stored on concrete platforms (roofed or unroofed) to which the aggregates are delivered by dump truck by contractors. (Height of dumps 1.5 m).
- As batching is carried out in small amounts of each aggregate, superior mixing is obtained.

Feeding of mix

- 5/5 Our casting process is based on an original approach worked out in years of intensive research. There is no intermediary stage between mixer and form. All forms are vertical and open on one side to a certain height. They can be sunk about 3 m below the mixer platform, or alternatively placed at the same level. In the former alternative (adopted here) the mixer is connected to conveyor moving along the form battery, and the mix is fed to the conveyor through a small chute under vibration, and from the conveyor into the form, in small doses to prevent clogging. The forms are equipped with large electric vibrators. The system is designed to overcome the difficulties of vertical casting (up to 3 m height and 6 cm thickness) and ensure penetration of the mix without segregation, overcoming the resistance of the reinforcement and the inserts. (Hitherto vertical casting has been confined to simple elements, and mostly carried out from below).

Equipment

- 5/5/1 2 rotary mix conveyors (belt width 60 cm, length 10 and 15 m long resp.) mounted on trucks with 6 heavy rubber wheels driven by 5 HP motors. The conveyor is operated by the truck driver from his seat.
- 5/5/2 A winch drawing the conveyor together with the mixer alongside the casting battery while the mix is fed in small doses.
- 5/5/3 An electric drive operated from the conveyor head.
- 5/5/4 The process requires 3 operators (one at the head of the conveyor, one to supervise the mixer, one to regulate the air cocks). It involves no physical effort and permits two slabs (more than 20 m^2 , weight up to 7.580 kg) to be cast in 20-40 minutes. To the best of our knowledge, this is unfeasible by any existing prefabrication method. The relevant patents cover the idea of small-dose casting and the batching technology.
- 5/5/5 The principal stage of casting is ended several cm below the required level, inserts are installed, and the final 200 kg are added by hand.

Main casting department (Photo 16)

- 5/6 The core of the process is the casting department, based on the most modern technology. Each casting machine (it would be an understatement to call it a form) consists of the following parts:
- (a) A base and a strong outer frame $9 \times 3 \times 3.5 \text{ m}$
 - (b) 2 section beams up to 9 m long, up to 300 mm wide (bottom of form).
 - (c) Intermediate body consisting of I-sections covered with sheeting (9 m long, 3 m high, and about 300 mm wide). The body is connected to the frame, with provision for steam heating inside.

- (d) Two similar bodies (adjustable), forming, with the intermediate body, the casting space for a pair of slabs.
- (e) Two longitudinal end-sections with adjustable spacing.
- (f) Air vibrator (frequency 8000 cps, air consumption 5 m³/min).
- (g) Pneumatic-hydraulic system for opening and closing the form.

Before casting, a heavy hopper (10 tons) equipped with two electric vibrators (40 HP, 2000 cps) is placed over the form. This vibration, intended to overcome any possible clogging (usually there is none) and propel the mix inside the form, is preferably applied in small amounts and only when necessary; consolidation is effected by the air vibrator referred to earlier (photo I7-I8). The hopper, together with the outer frame (which is usually open and should remain open on remoulding), form a rigid monolithic element lending itself to effective vibration.

Equipment.

5/6/1 The casting battery comprises the following forms:

- 2 for slab floors
- 1 for stair well
- 1 external walls, kitchen side
- 1 " " , balcony side
- 2 partitions
- 1 sanitary block
- 2 lateral walls

Total 10

These produce all the large slabs required for a set of two units. Each form weighs about 25 tons and is mounted on 40 springs.

- 5/6/2 Two vibration hoppers (9 m long, 3 m wide, 0.5 m high, 10 tons weight) with two vibrators.
- 5/6/3 20 sets of jigs for connecting and installing the reinforcement assemblies.
- 5/6/4 Circulating water tanks for flushing the forms.
- 5/6/5 Steam piping 6" (pressure 0.25 kg/cm^2 , temperature 120°C)
Steam piping 4"
Water piping 3"
Flushing water piping 1".
Condensate piping 1".
- 5/6/6 Steam boiler installation (pressure 6 kg/cm^2).
- 5/6/7 Pressure reduction system to 0.25 kg/cm^2 .
- 5/6/8 Condenser system (water softener).
- 5/6/9 Air compressor system (pressure 8 kg/cm^2).
- 5/6/10 Reserve diesel generator (160 kW).
- 5/6/11 Power mains (300 kVA), with 22,000/400 volt transformer.
- 5/6/12 2 portal cranes (10 tons, height 9 m) for casting and grinding department.
- 5/6/13 Batching plant, silo and screw conveyors for completing the castings, with track systems along the casting department.

Dimensions of department - length 120 m, width 11.5 m, pit depth 3 m.

The above equipment permits casting of more than 20 slabs per shift with a crew of 3. This skeleton crew opens, closes and cleans the forms. All forms are based on a uniform rigidity potential, and do not contain a single bolt; they produce slabs over 8 m in length with warp not exceeding 1 mm/m. The vibrator is applied to the form, not vice versa. Vibration is external and independent of the operator. The special design of the vibrator safeguards the motor which forms part of vibrating system. The idea and the design have been patented. There is no rigid connection between vibrator

and motor.

The design of the forms, with hundreds of details, has also been patented. In spite of their length, their deformation normally does not exceed 2 mm owing to the special mode of support. This rigidity causes a so-called "autoclave effect" on curing (widely studied in the USSR), consisting of numerous pressure points in the casting and more rapid increase in strength compared with an open or flexible form. The size of the forms, permitting single castings up to nearly 15 tons, reduces costs considerably compared with the numerous small operations by other methods.

Auxiliary-reinforcement department

5/7 In addition to the main reinforcement-assembly department (see § 5/3), there is a special department for smaller elements such as staircases, partitions, sanitary-block components, balcony- and roof balustrades, auxiliary walls, and roof outlets. Reinforcement for these elements is produced by arc welding on rotary benches, and where necessary formed into rigid assemblies as before. These are transported directly to the forms, bypassing the inspection department.

Equipment

- 5/7/1 Rotary benches with hand feed (no crane needed).
- 5/7/2 Jigs for small assemblies.
- 5/7/3 Jigs for bolting mats to assemblies. One form contains 8 such assemblies for set casting of 8 small elements.
- 5/7/4 Special trolleys for transporting the above directly to the casting department, where the cranes place them (in a single step) in the forms. Of the 10 forms, 3 are used for such set castings.

1898

The first of the year was a very dry one, and the crops were much injured. The weather was very hot, and the ground was very dry. The crops were much injured, and the yield was very small. The weather was very hot, and the ground was very dry. The crops were much injured, and the yield was very small.

The second of the year was a very wet one, and the crops were much injured. The weather was very cold, and the ground was very wet. The crops were much injured, and the yield was very small. The weather was very cold, and the ground was very wet. The crops were much injured, and the yield was very small.

The third of the year was a very dry one, and the crops were much injured. The weather was very hot, and the ground was very dry. The crops were much injured, and the yield was very small. The weather was very hot, and the ground was very dry. The crops were much injured, and the yield was very small.

5/8/1 All 6 small forms are located in a special spot at floor level. The standard 6 m^3 mix feeder is elevated about 1 m and the mix fed directly into the forms under vibration of the chute. The small forms are identical in design with the large ones, except for the limited height (1 m). Each form is supported on springs and provided with a pneumatic-hydraulic drive, the various internal elements, and steam heating (Photo 19).

Small castings for a two-unit set total about 14 tons, and are produced in a single batch. Casting time - about 1 hour.

5/9 § 5/3 to 5/8 cover the equipment normally required by any prefabrication plant, except that our process is much more mechanised. This equipment occupies a floor area of $4,000\text{ m}^2$ of the total 13,000 of our plant. The balance is used for the finishing operations, normally carried out on the site by other methods.

Grinding department (Photo 20)

5/10 In ordinary prefabrication, elements are positioned with gaps of several cm between them, which are then filled by in-situ casting. This precludes finishing the slabs at the plant, with considerable economy in labour. By our method, a specially-designed grinding technique is applied to the joint surfaces, permitting the slabs to be erected contiguously without need for open casting of the joints. The demoulded slabs are machined on special mounts by an overhead grinding machine driven by compressed air. The method may be regarded as equivalent to positive gauging in metal working.

5/10/1 An overhead structure ($9 \times 9 \times 1\text{ m}$) with longitudinal track and transverse carriage, carrying two grinding machines.

5/10/2 High-precision device adjusting the slab at the required level for grinding; spots calling for grinding are detected by means of a special indicator.

5/10/3 Special compressor with piping, following the movements of the grinding machine.

5/10/4 Grinding machine for machining all the faces of the slab (height 6 m, track length 20 m, width 2 m, weight 5 tons, power 6 HP).

Our patents cover the machining process proper and the technique. To the best of our knowledge, no such technique is used in any other prefabrication method.

Vertical-storage department

5/11 A daily output of 4 units (§ 2) requires:

12 floor slabs

3 roof slabs

2 stair well floor slab.

6 external wall slabs

6 lateral wall slabs.

This is the daily throughput of the grinding department en route to the finishing stage. For this purpose, a certain stock must be set aside immediately after casting. For the local project, a 4-day cycle was adopted, i.e. 120 slabs in stock.

Equipment

5/11/1 Repair jigs for castings, with provision for lifting each slab to the required level and vertical mounting. Total facilities for 24 slabs.

5/11/2 Storage facilities for the 100 slabs stored overnight for grinding, with provision for watering if necessary in hot and dry weather.

Transit department

5/12 The daily output of the grinding department (about 30 slabs) is loaded in batches of 3 on special trolleys and transferred to the parallel line of the finishing department. The total casting line (comprising the casting, grinding, storage

and transit stages) is about 300 m long and served by two 10-ton cranes. The finishing department is of the same length and width, but the direction is reversed.

Equipment

5/12/1 Transit trolley (30 tons).

5/12/2 Drive for empty trolley.

5/12/3 Winch for drawing loaded trolley from casting line to finishing line. If erection work is suspended owing to winter conditions or for any other reason, the transit department can be extended by an additional crane track parallel to the finishing department, with storage facilities for about 1000 slabs (equivalent to 150 units or 15% of the annual output).

Finishing Department (Photo 21)

5/13 The finishing department processes ground slabs, a total of 120 (16 units). This capacity permits a residence time of 4 days for each element. Slabs are mounted, by means of high-precision devices, on a 6" steel pipe structure on a perfectly level base.

- (a) The first stage consists in rapid dimensional inspection, to ensure rejection of any element likely to hold up erection work. Such an inspection, by a crew of two, requires not more than 15 minutes.
- (b) Installation of rubber fittings correcting any dimensional discrepancies (± 3 mm), or alternatively casting of such fittings.
- (c) Inspection of all insert hollows.
- (d) Wiring of conduits and boxes inserted on casting, and installation of those which could not be cast. Wall connections, switches etc.
- (e) Base coat of paint.

1870

... ..

... ..

...

... ..

... ..

... ..

... ..

... ..

... ..

... ..

...

... ..

... ..

... ..

...

... ..

... ..

... ..

... ..

... ..

... ..

... ..

... ..

...

- (f) Installation of doors and windows, piping, fittings, soap trays etc.
- (g) Miscellaneous operations on water and sewerage systems.

The finished slabs are placed in the rotating jig, shifted from a vertical to a horizontal position and attached (by means of nuts at their centre of gravity) to the crane for the despatching department. The finishing department is served by a single 10-ton crane.

Equipment

- 5/13/1 A steel pipe structure (6") with arms, angles, and other accessories for facilitating the finishing operations.
- 5/13/2 About 500 mounts for high-precision levelling of the slabs for the finishing operations.
- 5/13/3 Gauging, assembly and painting devices.
- 5/13/4 Portal crane (10 tons, 9 m height) with suitable track.
- 5/13/5 Hoists for horizontal lifting of the slabs with a high-precision device for suspending them at the exact centre of gravity. The 6 nuts embedded in the casting are used for distributing the load by means of springs.
- 5/13/6 Hooks with 1" bolts used with the nuts embedded in the casting during the final casting stage.

Sanitary-block and pantry-block department

- 5/14 (a) Slabs cast with the reinforcement exposed at suitable points are cut into smaller elements used for the sanitary block, kitchen pantry etc.
- (b) Floor slabs, with the reinforcement exposed at the centre and with openings provided during casting, are placed on special mounts.
- (c) A jig is installed over the floor.

1948

1949

1950

1951

1952

1953

1954

1955

1956

1957

1958

1959

1960

1961

1962

1963

1964

1965

1966

1967

1968

1969

1970

1971

1972

1973

- (d) The various elements, lintels etc. are positioned on the jig and connecting bolts are inserted in the openings and cemented before the elements are lowered into position. A special device keeps all elements vertical.
- (e) Gaskets forming casting spaces are applied to the joints between the elements, and between them and the lintels.
- (f) A special mix (about 300 kg in the case of the sanitary block) is injected into the joints by means of a pump.
- (g) After storage overnight, the jig is dismantled and transferred to the next floor.
- (h) The assembled block is given a base coat of paint and wired, the various sanitary accessories are installed, and the walls are painted (or tiled). The doors are mounted and a special hoist lifts the block, which is then transported by crane to the despatching department.
- (i) The pantry block, comprising the stairwell wall with electricity, gas and other meters, is assembled along the same lines.
- (k) This block has no floor, but is erected on the stairwell floor by means of special bolts cemented into it.

Equipment

- 5/14/1 Jigs for assembling the sanitary blocks - a structure (3 m high) of 6" pipes, interconnected with 3" pipes.
- 5/14/2 Ditto for kitchen pantry.
- 5/14/3 Mounts for sanitary-block floor.
- 5/14/4 Portable mixer and mix pump for joint casting.
- 5/14/5 Equipment for installing doors, piping, accessories, wiring etc.
- 5/14/6 Special hoist for lifting the block for transportation to the despatching department.

Auxiliaries to finishing stage

- 5/15/1 Equipment for processing the staircases, including rotating device for holding the elements in a horizontal position.
- 5/15/2 Rotating device for elements of the sanitary block not cast in assembly position.

Despatching Department

- 5/16 (a) In our process, the despatching department is an extension of the production stage, not of the storage as in other methods.
- (b) Finished slabs are transferred by crane to the pallets of the despatching department. Floor slabs are stacked horizontally, wall and partition slabs - vertically.
- (c) Assuming two-shift operation of the finishing departments, slabs arrive for despatching every half hour.
- (d) Each pallet is mounted with its load (up to 40 tons) on a pipe structure. A trailer truck is driven under it, the pallet is lifted slightly by means of a hydraulic jack system (10 jacks), fixed in position and lowered onto the trailer. The operation requires a maximum of half an hour, and is carried out by the truck-driver single-handed. When the truck returns empty from the site, the pallet is lifted off by crane and returned to its place.

Equipment

- 5/16/1 pallets(7 x 4 m, weight about 3 tons) for floor slabs
- 5/16/2 Ditto for wall slabs
- 5/16/3 Hydraulic jack system, 10 jacks (10 tons) for each trailer
- 5/16/4 Two trailer trucks
- 5/16/5 Special truck (10 tons) for sanitary block (2.9 x 2.4 m). A 20 ton truck can transport 2 units per run, but is much more expensive. (Four blocks for four units).

- 5/16/6 Special 5 ton truck for transporting two pantry units (two blocks for 4 units); the same truck can be used for other smaller elements.

Delivery to site

- 5/17 An unloading stage is provided on the site. The trailer is driven under it, the pallet is lifted, released and deposited, after which the previous empty pallet is picked up. The operation does not require more than $\frac{1}{2}$ hour at this rate the truck can make at least 5 runs daily.

Equipment

- 5/17/1 Loading stages, length 7 m.
5/17/2 Guideposts for positioning the trailer.
5/17/3 Standard hoist (arm length 7.5 m, weight 1.5 ton) equipped for accurate adjustment of the centre of gravity.
5/17/4 Special hoist for pantry block.
5/17/5 Auxiliary hoists.
5/17/6 Special hoist for sanitary block.
5/17/7 Lifting hooks with $\frac{3}{4}$ "-1" bolts.

Foundations

- 5/18 (a) Foundations according to our method must be specially cast, so that the ground-floor slabs fit the bolts in the foundations within ± 3 mm, and the foundations themselves are exactly level.
(b) Foundations should preferably be cast by plant crews, but any contractor equipped by the plant and familiar with the precision technique can do it.

- (c) The reinforcement (welded) is preferably prepared at the plant in the form of precision assemblies designed to hold the special forms in position; 3/8" bolts embedded in the casting are used for connecting the forms to the reinforcement.
- (d) Models of floor slabs, built of lightweight sections with bolting holes provided, are used for locating the foundations.
- (e) Each model weighs 100-150 kg and can be positioned without a crane.
- (f) In the case of pile foundations, the piles are adjusted by means of special instruments, and a steel plate is mounted over them for welding the reinforcement assemblies.
- (g) The foundation mix can be produced in ordinary mixers and placed as usual. If the building has a basement or an air-raid shelter, it is constructed conventionally irrespective of the accuracy of the foundation.

Erection

5/19 When the foundation has been completed, earth banks are piled alongside it, compacted by rolling and covered with perforated steel plates, as pavement for the erection crane, which is equipped with truck wheels and operated by electric motors through a gear system. The crane base (10 m long) is mounted on 4 double wheels. Special (high-torque, 10 HP) motors are used. Sections are provided for the height required for 4 stories. (. . .)

The crane is equipped with a "microapproach" device permitting fine adjustment of the position of the elements (of the order of millimetres).

A special system of 4 crane sections (5 tons each) is used for erecting the first walls, joined together by aluminium pipes. A crew of two locates the conical studs for the upper floor, and the erecting crew deposits the floor in place by means of matching holes in the casting. The floor slabs are tightened by a special

hydraulic device and the nuts welded together. Joints between walls and floors are injected with special mortar under pressure.

Equipment

- 5/19/1 Erection crane (10 tons) on truck wheels, width as required. No track. Auxiliary parts transported by means of ordinary truck. Crane assembly time on site - about 3 days.
- 5/19/2 Device for manoeuvring the crane on the site without dismantling.
- 5/19/3 Set of mounts for positioning the wall slabs.
- 5/19/4 Set of conical studs.
- 5/19/5 Set of wall models made of aluminium piping (3-4"). The operation requires a crew of two, time-- one hour per 2-unit set.
- 5/19/6 Hydraulic device for tightening floor slabs.
- 5/19/7 Stabilising device for walls during erection.
- 5/19/8 Joint-casting equipment.
- 5/19/9 Special mixer and mix pump for above (pressure up to 3 kg/cm^2).
- 5/19/10 Wiring equipment.
- 5/19/11 Water-pipe and sewerage installation equipment.

Finishing operations on the roof etc.

- 5/20 (a) Finishing operations on the roof are conventional, according to local conditions (climate etc.).
- (b) Connection of water supply and sewerage systems is conventional.
- (c) Rainwater drainage is conventional.
- (d) Electricity and gas supply fixtures are adapted to suppliers' standards.

...the
... ..
... ..

...

... ..
... ..
... ..

... ..
... ..

... ..
... ..

... ..

... ..

... ..

... ..

... ..

... ..

...

... ..
... ..

(a)

(b)

(c)

(d)

QUESTION NO. 6 - DESCRIPTION OF PLANT

- 6/1 The size of the premises depends on the completeness of the process and on climatic conditions (year-round or seasonal operation). A field plant would require hardly any structures. The local plant is used as an example, but these data are optional and the method is completely flexible (Photo 23).
- 6/2 The reinforcement-assembly department is housed in a steel structure (120 m long, 10 m wide, 6 to 10 high, concrete floor) roofed with Eternit. No foundations required for equipment.
- 6/3 The inspection department requires an open-wall shed about 16 m high; alternatively, this stage can be housed in the production department.
- 6/4 Mix production depends on aggregate-supply considerations (large reserves required, or daily supply assured). The batching plant requires a shed (22 x 12 x 8 m). At the local plant the storage floor is concrete (600 m^2), stacks are covered or uncovered according to local conditions.
- 6/5 The casting department is housed in a steel structure (25 kg/m^2), length 120 m, width 12 m, pit depth 3 m, concrete floor (15 cm). No foundations required for equipment under ordinary soil conditions.
- 6/6 Grinding and transit department-steel structure(25 kg/m^2), 150 x 18 x 16 m. Eternit roofing. Crane girders 0.6 m deep, 0.35 m wide, pile foundation (10 m spacing, 40 cm diameter, 5 m depth).
- There is special provision for modifying the equipment in case of changes in unit type and in the dimensions of the elements.
- 6/7 Finishing department-structure same type as under § 6/6 (35 kg/m^2), Eternit roofing, pile foundation (10 m spacing, 40 cm diameter, 5 m depth). Crane girders as under § 6/6.

- 6/8 Despatching department - shed, 40 x 13 x 16 m, concrete floor.
- 6/9 Machine hall (Photo 24) - lightweight structure, 30x6x6 m, tiled floor, concrete slab foundations (20 cm thick)
- 6/10 Roads - 4-6 m wide, total length about 1 km.
- 6/11 The total requirement for a plant like ours, including the finishing department, would be:

steel sections - about 600 tons

roofing - 20,000 m²

concrete flooring - 13,000 m² (1500 m³ concrete).

crane girders - 1200 m (300 m³)

foundation concrete - 300 m³

casting-pit concrete (if used) - 400 m³

foundation piling (800 in number) - 4000 m (600 m³ concrete).

- 6/12 Total cost for local plant, earth work and roads - \$ 100,000, premises \$ 600,000.

QUESTION NO. 7 - PROJECTED PRODUCTION CAPACITY

- 7/1 Details under § 5.
- 7/2 A plant can be designed for any desired or required capacity. The present plant, for example, is designed for four 70 m² units daily, or 1000 units annually.
- 7/3 Each unit requires about 30 m³ concrete or 30,000 m³ per year.
- 7/4 Each unit requires about 7.5 floor and wall slabs, average size 20 m², average weight 7 tons.
- 7/5 Additional elements (partitions, block elements etc.) - total 30 m³ per day.

QUESTION NO. 8 - RAW MATERIALS

- 8/1 As the innovation in our method is in the casting process, any type of aggregate

1. The first part of the report is a general introduction to the subject.

2. The second part is a detailed description of the methods used in the study.

3. The third part is a discussion of the results of the study.

4. The fourth part is a conclusion and a list of references.

5. The fifth part is a list of the names of the authors.

6. The sixth part is a list of the names of the institutions.

7. The seventh part is a list of the names of the sponsors.

8. The eighth part is a list of the names of the reviewers.

9. The ninth part is a list of the names of the editors.

10. The tenth part is a list of the names of the publishers.

11. The eleventh part is a list of the names of the distributors.

12. The twelfth part is a list of the names of the retailers.

13. The thirteenth part is a list of the names of the wholesalers.

14. The fourteenth part is a list of the names of the manufacturers.

15. The fifteenth part is a list of the names of the suppliers.

16. The sixteenth part is a list of the names of the customers.

17. The seventeenth part is a list of the names of the agents.

18. The eighteenth part is a list of the names of the brokers.

19. The nineteenth part is a list of the names of the dealers.

20. The twentieth part is a list of the names of the distributors.

21. The twenty-first part is a list of the names of the retailers.

22. The twenty-second part is a list of the names of the wholesalers.

23. The twenty-third part is a list of the names of the manufacturers.

24. The twenty-fourth part is a list of the names of the suppliers.

and cement used in conventional and industrial building is suitable.

8/2 The requirements of the local plant are:

8/2/1 Walls and partitions, per m³ mix

| | |
|------------------|-------------|
| Sand | 450 kg |
| Aggregate 2-5 mm | 380 " |
| " 6-10 mm | 970 " |
| Cement | 300 " |
| Water up to | 200 litres. |

8/2/2 Floors, per m³ mix

| | |
|------------------|-------------|
| Sand | 380 kg |
| Aggregate 2-5 mm | 480 " |
| " 6-10 mm | 260 " |
| " 15-30 mm | 700 " |
| Cement | 280 " |
| Water | 160 litres. |

8/3 The method permits a water/cement ratio of 0.6-0.75, dependent on the thickness of the casting, the reinforcement ratio and the amount of inserts welded to the reinforcement. The water/cement ratio is optimised for each form.

8/4 Casting requires about 20/40 minutes, plus 15 minutes for dismantling the hopper and the reinforcement jig.

8/5 The final stage of the casting (150-200 kg) is carried out by hand.

8/6 Curing steam is introduced, and the casting reaches the strength permitting demoulding in 3 hours.

8/7 The overall cycle of casting and curing is 4-5 hours.

QUESTION NO. 9 - MANPOWER

9/1 The answer depends on local manpower conditions and on the envisaged completeness of the process.

- 9/2 It also depends on whether subcontractors are to be involved, as for electricity and water-supply installation.
- 9/3 We propose to include in the cost only the materials and purchased equipment - namely cement, aggregates, steel, paint, sanitary accessories, wiring and other electrical equipment, doors, windows, shutters, plastic flooring, but not installation or application.
- 9/4 Each m^2 of finished unit requires 8 working hours. The $70 m^2$ unit ordered by the Israel Ministry of Housing will thus require 70 working days, and a plant operating at 4 units per day would require a staff of 250, including administration, engineers, foremen, maintenance staff, cleaners, drivers etc.
- 9/5 Foundations, development work, roads, water and electricity supply to the building are not included.

QUESTION NO. 10 - DETAILS OF TRANSPORTATION AND ERECTION

- 10/1 Details under § 5.
- 10/2 Manpower under § 9.
- 10/3 The manpower required for transportation and erection is calculated below on the basis of maximum (95%) completeness.
- 10/4 An output of 1000 units per year requires 3 erection cranes. Assuming 200 working days (free of wind and rain), each crew (including the finishing stage) of 12 will invest $200 \times 12 \times 3 = 7200$ working days, or assuming 280 working days per year per man - 26 men per year.

As additional information, we quote the following figures:

- 1) A $70 m^2$ unit completed to the degree required by the Ministry of Housing, excluding development, foundations, and electricity, water and sewerage outside

the house - will cost about \$ 4,000.

2) Local available materials (\$ 9/3) amount to \$ 2,000. For comparison, local prices are as follows:

Cement - \$ 33 ton

Aggregate - \$ 3 per ton

Reinforcing steel - \$ 230 per ton

Piping and fittings - 50% above European export prices

Washbowls and bathtubs - about 100% as above

Electrical materials - " 50% " " .

3) The balance (including wages, industrial materials and depreciation) is thus \$ 2,000 per unit. Assuming that the total investment in premises, equipment, installation and running-in is \$ 2,000,000, and assuming that the plant should return the investment at 7,000 units, the amount per unit will be \$ 300, leaving 1,700 for wages and industrial materials.

Setting the expenditure per worker (including social benefits) at \$ 3,500, we have $3500:4 = \$ 900$ per unit-worker, leaving 800 for industrial expenses, royalties and profit. Setting the production expenses and royalties at \$ 500 per unit, we have total annual profit of \$ 300,000 for the first 7 years of operation.

Bearing in mind that such a plant in 7 years undergoes improvement, raises its standards and creates know-how, and that a high proportion of the investment is of the slow-depreciation type, it can be assumed that in 7 years the value of the plant will be close to its original level. In the light of the trend of development in industrial building, it cannot be expected that a new invention might render the plant valueless, so that after 7 years the profit will rise to \$ 600 per unit.

The plant can be sold to a subsidiary paying taxes on the capital gains only;

these taxes are everywhere lower than those on operational gains.

The above calculations are based on the low rates of the local popular housing projects; in the free market the profit margin is much higher.

07 01 01

THE "SLAVIN SYSTEM"

FOR MASS FABRICATION OF REINFORCED CONCRETE MULTI-STOREY HOUSES

1. General.

This system, the outcome of extensive research, presents several major advantages over other systems generally used in the construction of large housing projects.

The basic concept of the system is the fabrication of large elements (with a view to reducing the number of joints and erection operations to a minimum) produced by simple machinery, whose handling should not present difficult problems anywhere.

Through the complete industrialisation of the production, the elimination of deformations in fabricated components and simplification of the erection process, the "Slavin system", used on projects of appropriate size, should result in marked economical advantages and reduce the construction period to an unparalleled minimum.

2. Proposal.

This firm offers for sale either the know-how only or a complete package, i.e. a factory in operation. To suit the widest possible range of requirements, 6 alternatives are offered, each such alternative representing a phase of a complete factory. Each such stage is conceived to cope with a certain line of production and to be easily incorporated in a more complete factory, should an expansion be desired at a later date. The six above-mentioned alternatives and their approximate prices are tabulated on the sheet as over.

$$\begin{aligned}
 & \text{Purchase} = 2 \text{ days} = 8 (26 \times 200) \quad 19,600 \times 8 = 156,800 \text{ Kt.} \\
 & 40 \times 75,000 \text{ m}^2 = 3,000,000 \text{ m}^2 \\
 & \frac{156,800}{3,000,000} = 25 \text{ Kt/m}^2
 \end{aligned}$$

3. Feasibility.

In recent years, prefabrication of houses, particularly where large housing schemes are concerned, is being adopted by an ever increasing number of countries, be it for reasons of speedy erection, scarcity of skilled man-power, the achievement of a standard, factory-controlled finished product or a combination thereof.

In most countries, the share of prefabricated construction, related to the general dollar value of building works, is not large enough to warrant anxiety over workmen being deprived of a substantial number of openings in the building industry; in any case, in countries undergoing a process of industrialisation, there is no reason why the building industry should be singled out and prevented from following a development process not dissimilar to that of many other industries.

One of the main features of the "Slavin system" is the very short period of time required to produce a complete block of flats. When components are brought on site, assembly is carried out in a chain process by specialised teams, each team repeating the same part of work, flat after flat. In this manner, a complete cycle of operations required to complete one block of 40 3-roomed flats is roughly 7-8 weeks, a period of time which undoubtedly can be improved, as workmen gain experience by performing repetitive operations.

In addition to this extremely short time, one can realise a serious saving in labour costs, as indicated hereinafter in "Computation of Labour per Unit of Floor Area".

The Organisation Cost Sheets enclosed are back-up sheets for the above computation. We have further analysed total costs (based on running and investment expenses detailed in back-up sheets enclosed) which would indicate the following:

The investment in a factory required to produce 1000 flats of good standard per year, in running expenses, materials royalties and overheads, can be amortized in 7 years, by receiving payment of \$47.50 per sq.m. of built area. This price is based on certain assumptions detailed in the back-up sheets and can be adjusted, by simple computation, where applicable.

At the expiration of 7 years, the factory would have reached its full production capacity and would probably be of greater sale value than its initial cost.

$$\begin{aligned}
 & (1000 \text{ flats} \times 75,000 \text{ m}^2) = 75,000,000 \text{ m}^2 \quad \text{Price (Kt/m}^2) \text{ cost?} \\
 & \text{Investment} = 3,330,000 \quad \text{2,200,000 / 7 years} \quad \frac{315}{3,330} = 9.3\% \downarrow \\
 & \quad \quad \quad 315,000 \quad \quad \quad \text{Amortized}
 \end{aligned}$$

ESTIMATED INVESTMENT

| | |
|-------------------------------|--------------|
| Building | \$ 550,000 |
| Plant | \$ 1,330,000 |
| Plant Assembly & Installation | \$ 250,000 |
| Running-in Expenses | \$ 70,000 |
| Land | unconsidered |
| | ----- |
| TOTAL | \$ 2,200,000 |

BREAKUP OF PLANT COSTS.

| | |
|---|-----------------------|
| 15 forms | \$ 500,000 |
| * 5 cranes (10 tons) | \$ 170,000 |
| Concrete Plant | \$ 230,000 |
| Electrical, water, steam
& compressed air facilities | \$ 170,000 |
| Reinforcement Dpt. Plant | \$ 100,000 ! |
| Other plant: Grinding, Finishing
** Transport | \$ 160,000 |
| | ----- |
| TOTAL | \$ 1,330,000
===== |

* Suitable up to 6 storey houses

** 4 semi-trailers with 2 prime movers

16/5/67 11/3 '01

TOTAL COST COMPUTATION

considering 1000 flats/year production.

This is an approximate cost computation based on running and other costs as detailed in backup sheets and considering that the investment in the factory must be amortized by producing 7000 flats.

- | | | |
|---|---|--------|
| 1) Amortization of complete factory costs | $\frac{\$ 2,200,000}{7000 \text{ flats}} = \$ 314$ | ✓ |
| 2) Running expenses | $\frac{\$ 240}{1000 \text{ flats}} = \$ 240$ | 2 |
| 3) Labour Costs | $\frac{\$ 60,000 \times 12m. \times 8 y.}{7000} = \$ 823$ | 2 ✓ |
| 4) Materials | | |
| | | \$1750 |
| 5) Royalties | | \$ 200 |

TOTAL \$ 3,327

$$\frac{\$ 3,327}{70 \text{ sq.m.}} = \$ 47,50 / \text{sq.m.}$$

413
3840

COMPUTATION OF LABOUR

PER UNIT OF (BUILT) FLOOR AREA

Note: See 'organisation' breakup.

Assumed: Desired production - 1000 flats of 70 sq.m./year

Manpower, including overheads: 250 men.

$$\frac{250 \text{ men} \times 300 \text{ days}}{1000 \text{ flats} \times 70 \text{ sq.m.}} = 7.5 \text{ say } 8 \text{ man-hours/sq.m.}$$

as against:

For conventional buildings 25-30 man-hours/sq.m.

Other prefabrication systems 12-18 man-hours/sq.m. ?

A fairly accurate labour cost estimate of finished flats per unit of floor area is possible using the above data. However, as rates vary from country to country, computations should be adjusted using actual prevailing rates. Taking for example rates prevailing in Venezuela, the labour cost per square meter of finished flats can be computed as follows:-

- found* 1) Unskilled labour: $\frac{210}{200}$ $\frac{32}{100}$
- $$\frac{210 \text{ men} \times 300 \text{ days} \times 0.80 \text{ \$ / h.}}{1000 \text{ flats} \times 70 \text{ sq.m.}} = 6.85 \$ - 50\%$$
- 2) Add for 11 supervisors 1.74 \$ - 12.7%
- 3) Add for 30 operators and mechanics 2.95 \$ - 21.5%
- 4) Add for Technical & Administration Staff 2.16 \$ - 15.8%
- $$13.70 \$ / m^2 \text{ } 100\%$$

By substituting actual rates, the approximate labour cost can easily be computed.

COST OF MATERIALS

FOR A 70 SQ. M. FLAT

| | | | |
|---------------|--------------------------|---|-------|
| Concrete | 35 m ³ x ₦ 15 | = | ₦ 525 |
| Rebars | 1,100 kg. x ₦ 120 | = | ₦ 132 |
| Paint | | = | ₦ 100 |
| Flooring | | = | ₦ 120 |
| Windows | 3 sq. m. x ₦ 20 | = | ₦ 60 |
| Doors | 7 x ₦ 30 | = | ₦ 210 |
| Electrical | | = | ₦ 100 |
| Plumbing | | = | ₦ 250 |
| Cupboards | | = | ₦ 200 |
| Miscellaneous | | = | ₦ 100 |

Total ₦1797 say ₦1800/20

25 - 70, m = 0,5 m
the average is 0,83
below

YEARLY RUNNING EXPENSES

| Details | Assumed Costs in Dollars | | |
|--|--------------------------|--------|------------|
| | Plant | Site | TOTAL |
| 1. Electricity, 12000 KW | 2,000 | 400 | 2,400 |
| 2. Water 5000 M.C. | | | 600 |
| 3. Fuel (steam generators, trailers, compressors, vehicles) | | | 30,000 |
| 4. Plant maintenance (spare parts) | | | 50,000 |
| 5. Premises " | | | 4,000 |
| 6. Bank charges and interest (considering 7% interest rates and 8 years amortization of capital) | | | 80,000 |
| 7. Insurance | 5,000 | 10,000 | 15,000 |
| 8. P.T.T. | | | 2,000 |
| 9. Stationery, engineering and office equipment | 3,000 | 1,000 | 4,000 |
| 10. Tools | 4,000 | 1,000 | 5,000 |
| 11. Medical expenses | 2,500 | 2,500 | 5,000 |
| 12. Legal & auditing expenses | | | 5,000 |
| 13. Cleanup | 1,000 | 1,500 | 2,500 |
| 14. Temporary structures | | 5,000 | 5,000 |
| 15. 10 vehicles | | | 20,000 |
| 16. Travel and entertainment expenses | | | 5,000 |
| 17. Miscellaneous and unforeseen " | | | 5,000 |
| TOTAL | | | \$ 240,500 |

$$25(4 \times 70) = 7000 \sim \times 47.5\% = 3130$$

inf-tae 07 01 01

THE "SLAVIN SYSTEM"

FOR MASS FABRICATION OF REINFORCED CONCRETE MULTI-STOREY
HOUSES

1. General.

This system, the outcome of extensive research, presents several major advantages over other systems generally used in the construction of large housing projects.

The basic concept of the system is the fabrication of large elements (with a view to reducing the number of joints and erection operations to a minimum) produced by simple machinery, whose handling should not present difficult problems anywhere.

Through the complete industrialisation of the production, the elimination of deformations in fabricated components and simplification of the erection process, the "Slavin system", used on projects of appropriate size, should result in marked economical advantages and reduce the construction period to an unparalleled minimum.

2. Proposal.

This firm offers for sale either the know-how only or a complete package, i.e. a factory in operation. To suit the widest possible range of requirements, 6 alternatives are offered, each such alternative representing a phase of a complete factory. Each such stage is conceived to cope with a certain line of production and to be easily incorporated in a more complete factory, should an expansion be desired at a later date. The six above-mentioned alternatives and their approximate prices are tabulated on the sheet as over.

2.

3. Feasibility.

In recent years, prefabrication of houses, particularly where large housing schemes are concerned, is being adopted by an ever increasing number of countries, be it for reasons of speedy erection, scarcity of skilled man-power, the achievement of a standard, factory-controlled finished product or a combination thereof.

In most countries, the share of prefabricated construction, related to the general dollar value of building works, is not large enough to warrant anxiety over workmen being deprived of a substantial number of openings in the building industry; in any case, in countries undergoing a process of industrialisation, there is no reason why the building industry should be singled out and prevented from following a development process not dissimilar to that of many other industries.

One of the main features of the "Slavin system" is the very short period of time required to produce a complete block of flats. When components are brought on site, assembly is carried out in a chain process by specialised teams, each team repeating the same part of work, flat after flat. In this manner, a complete cycle of operations required to complete one block of 40 3-roomed flats is roughly 7-8 weeks, a period of time which undoubtedly can be improved, as workmen gain experience by performing repetitive operations.

In addition to this extremely short time, one can realise a serious saving in labour costs, as indicated hereinafter in "Computation of Labour per Unit of Floor Area".

The Organisation Cost Sheets enclosed are back-up sheets for the above computation. We have further analysed total costs (based on running and investment expenses detailed in back-up sheets enclosed) which would indicate the following:

The investment in a factory required to produce 1000 flats of good standard per year, in running expenses, materials royalties and overheads, can be amortized in 7 years, by receiving payment of \$47.50 per sq.m. of built area. This price is based on certain assumptions detailed in the back-up sheets and can be adjusted, by simple computation, where applicable.

At the expiration of 7 years, the factory would have reached its full production capacity and would probably be of greater sale value than its initial cost.

ESTIMATED INVESTMENT

| | | |
|-------------------------------|--------------|-----------|
| Building | \$ 550,000 | 1,925,000 |
| Plant | \$ 1,330,000 | 4,655,000 |
| Plant Assembly & Installation | \$ 250,000 | 875,000 |
| Running-in Expenses | \$ 70,000 | 245,000 |
| Land | unconsidered | |
| TOTAL | \$ 2,200,000 | 7,700,000 |

BREAKUP OF PLANT COSTS.

| | | |
|---|--------------|-----------|
| 15 forms | \$ 500,000 | 1,750,000 |
| * 5 cranes (10 tons) | \$ 170,000 | 595,000 |
| Concrete Plant | \$ 230,000 | 805,000 |
| Electrical, water, steam
& compressed air facilities | \$ 170,000 | 595,000 |
| Reinforcement Dpt. Plant | \$ 100,000 | 350,000 |
| Other plant: Grinding, Finishing
** Transport | \$ 160,000 | 560,000 |
| TOTAL | \$ 1,330,000 | 4,655,000 |

* Suitable up to 6 storey houses

** 4 semi-trailers with 2 prime movers

4.

BREAKDOWN OF UNSKILLED LABOUR FORCE.

1. Concreting.

| | | |
|--|-----------|----|
| Concrete Plant | 3 | |
| Hauling | 2 | |
| Pours | 3 | |
| Handling of forms. fixing reinforcement mesh, lifting of elements from forms | <u>17</u> | |
| Shift 1 | 25 | |
| Shift 2 | 25 | |
| Spare men, in-between shifts | <u>10</u> | |
| Total, concreting works | | 60 |

2. Reinforcement and Inserts

2 shifts x 20 40

3. Grinding, Finishing, Electrical & Mechanical
Installations, Repairs, Final Checks


2 shifts x 20 40

4. Transport & Erections

50

TOTAL

200 men



TOTAL COST COMPUTATION

considering 1000 flats/year production.

This is an approximate cost computation based on running and other costs as detailed in backup sheets and considering that the investment in the factory must be amortized by producing 7000 flats.

| | |
|---|---|
| 1) Amortization of complete factory costs | $\frac{\$ 2,200,000}{7000 \text{ flats}} = \$ 314$ |
| 2) Running expenses | $\frac{\$ 240}{1000 \text{ flats}} = \$ 240$ |
| 3) Labour Costs | $\frac{\$ 60,000 \times 12m. \times 8 y.}{7000} = \$ 823$ |
| 4) Materials | \$1750 |
| 5) <i>0.0068 / sq.m. x 1200</i> | 70 |
| 6) Royalties | \$ 200 |
| TOTAL | $\$ 3,648$
$\$ 3,327$ |

$$\frac{\$ 3,327}{70 \text{ sq.m.}} = \$ 47,50 / \text{sq.m.}$$

166.25

July 17, 1964

Dear Mr. [Name]

I am writing to you regarding the [Topic] which you mentioned in your letter of July 15, 1964. I have reviewed the [Document] and find it to be [Description]. I am enclosing herewith a copy of the [Document] for your information.

I am sure that you will find this information helpful in your [Task].

I am very grateful for your interest in this matter and hope that you will find this information helpful.

I am sure that you will find this information helpful in your [Task].

I am very grateful for your interest in this matter and hope that you will find this information helpful.

I am sure that you will find this information helpful in your [Task].

I am very grateful for your interest in this matter and hope that you will find this information helpful.

I am sure that you will find this information helpful in your [Task].

I am very grateful for your interest in this matter and hope that you will find this information helpful.

I am sure that you will find this information helpful in your [Task].

I am very grateful for your interest in this matter and hope that you will find this information helpful.

COMPUTATION OF LABOUR

PER UNIT OF (BUILT) FLOOR AREA

Note: See 'organisation' breakup.

Assumed: Desired production - 1000 flats of 70 sq.m./year

Manpower, including overheads: 250 men.

$$\frac{250 \text{ men} \times 300 \text{ days}}{1000 \text{ flats} \times 70 \text{ sq.m.}} = 7.5 \text{ say } 8 \text{ man-hours/sq.m.}$$

as against:

For conventional buildings 25-30 man-hours/sq.m.

Other prefabrication systems 12-18 man-hours/sq.m.

A fairly accurate labour cost estimate of finished flats per unit of floor area is possible using the above data. However, as rates vary from country to country, computations should be adjusted using actual prevailing rates. Taking for example rates prevailing in Venezuela, the labour cost per square meter of finished flats can be computed as follows:-

1) Unskilled labour:

$$\frac{200 \text{ men} \times 300 \text{ days} \times 0.80 \text{ \$/h.}}{1000 \text{ flats} \times 70 \text{ sq.m.}} = 6.85 \$ - 50\%$$

2) Add for 11 supervisors 1.74 \$ - 12.7%

3) Add for 30 operators and mechanics 2.95 \$ - 21.5%

4) Add for Technical & Administration Staff 2.16 \$ - 15.8%

$$13.70 \$ / m^2 100\%$$

By substituting actual rates, the approximate labour cost can easily be computed.

7.

COST OF MATERIALS

=====

FOR A 70 SQ. M. FLAT

| | | | |
|---------------|--------------------------|---|-----------------|
| Concrete | 35 m ³ x ₦ 15 | = | ₦ 525 |
| Rebars | 1,100 kg. x ₦ 120 | = | ₦ 132 |
| Paint | | = | ₦ 100 |
| Flooring | | = | ₦ 120 |
| Windows | 3 sq. m. x ₦ 20 | = | ₦ 60 |
| Doors | 7 x ₦ 30 | = | ₦ 210 |
| Electrical | | = | ₦ 100 |
| Plumbing | | = | ₦ 250 |
| Cupboards | | = | ₦ 200 |
| Miscellaneous | | = | ₦ 100 |
| Total | | | ₦1797 say ₦1800 |

YEARLY RUNNING EXPENSES

| Details | Assumed Costs in Dollars | | |
|---|--------------------------|---------|--|
| | Plant | Site | TOTAL |
| 1. Electricity, 12000 KW | 2,000 | 400 | 2,400 |
| 2. Water 5000 M.C. | | | 600 |
| 3. Fuel (steam generators, trailers, compressors, vehicles) | | | 30,000 |
| 4. Plant maintenance (spare parts) | | | 50,000 |
| 5. Premises " | | | 4,000 |
| 6. Bank charges and interest (considering 10% interest rates and 8 years amortization of capital) | | 25/6/10 | 30,000
110,000
80,000 |
| 7. Insurance | 5,000 | 10,000 | 15,000 |
| 8. P.T.T. | | | 2,000 |
| 9. Stationery, engineering and office equipment | 3,000 | 1,000 | 4,000 |
| 10. Tools | 4,000 | 1,000 | 5,000 |
| 11. Medical expenses | 2,500 | 2,500 | 5,000 |
| 12. Legal & auditing expenses | | | 5,000 |
| 13. Cleanup | 1,000 | 1,500 | 2,500 |
| 14. Temporary structures | | 5,000 | 5,000 |
| 15. 10 vehicles | | | 20,000 |
| 16. Travel and entertainment expenses | | | 5,000 |
| 17. Miscellaneous and unforeseen " | | | 5,000 |
| TOTAL | | | \$ 240,500
===== |

340,500

ORGANISATION.

(Based on 2 shifts, 4 flats of 70 sq. m. per day)

Assumed
Monthly
Salaries
\$

A. Technical, Administrative, Services.

| | | | |
|----------------------------------|----------|---------------------|------------------|
| Manager/Chief Engineer | 1 | | |
| Administrator/Accountant | 1 | | |
| Production Engineer | 1 | | |
| Erection Engineer | 1 | | |
| | <u>4</u> | $4 \times \$1600 =$ | \$6,400.- |
| Purchasing Clerk | 1 | | |
| Storekeeper | 1 | | |
| Timekeeper | 1 | | |
| Secretary-Typist | 1 | | |
| | <u>4</u> | $4 \times \$ 600 =$ | \$2,400.- |
| Office Clerks | 2 | | |
| " Boys | 2 | | |
| Watchmen | 3 | | |
| | <u>7</u> | $7 \times \$ 100 =$ | \$ 700.- |
| Total technical, Admin. Services | | | <u>\$9,500.-</u> |

B. Supervision.

| | | | |
|---|----------|---------------------|------------------|
| Reinforcement & Inserts
Superintendent | 1 | | |
| Concreting " | 1 | | |
| Plant (mechanical) " | 1 | | |
| " (electrical) " | 1 | | |
| Grinding | 1 | | |
| Repairs & Finishings Supt. | 1 | | |
| Final Inspection " | 1 | | |
| Transport " | 1 | | |
| Erection " | 1 | | |
| | <u>9</u> | $9 \times \$ 800 =$ | \$7,200.- |
| Erection Foremen | 2 | $2 \times \$ 250 =$ | \$ 500.- |
| Total Supervision | | | <u>\$7,700.-</u> |

C. Mechanics, Operators, Drivers.

| | | | |
|--------------------------------------|----|----------------------|-------------------|
| Operators, and Drivers | 20 | $20 \times \$ 500 =$ | \$10,000.- |
| Mechanics | 10 | $10 \times \$ 300 =$ | \$ 3,000.- |
| Total Mechanics, Operators, Drivers. | | | <u>\$13,000.-</u> |

| | | | |
|--------------------------------|-----|-----------------------|-------------------|
| D. <u>Unskilled Labourers.</u> | 200 | $200 \times \$ 150 =$ | \$30,000.- |
| Total Manpower Monthly Cost | | | <u>\$60,200.-</u> |

Note: For breakdown of Labour Force, see backup sheets.

SUMMARY.

| | | |
|---|-----------------|---------|
| 1. Overheads (Technical & Administrative) | \$ 9,500 | 15.8% |
| 2. Productive (Reflected on Direct Cost) | | |
| Supervisors | \$3,650 - | 12.7% |
| Mechanics & Operators | \$5,800 - | 21.5% |
| Unskilled labourers | \$30,000 - | 50 % |
| | <u>\$39,450</u> | - 84.2% |
| | <u>\$47,350</u> | 100.0% |

SIX ALTERNATIVE FACTORIES APPROXIMATE COSTS.

| Alt-
erna-
tive | Production Line | Production
Area
(Sq. m.) | Factory
Bldg. | Forms | Cranes | C
O
S
T
S
\$ | Concrete
Plant | Utilities
Water,
Elec.
Steam, Air. | Reinforce-
ment
Plant | Plant
Plant
מפעל
מפעל | Plant
Instal-
lation | TOTAL |
|-----------------------|---|--------------------------------|------------------|---------|---------|-----------------------------|-------------------|---|-----------------------------|---|----------------------------|-----------|
| | | <i>סך הכל</i> | | | | <i>מפעל</i> | | | | | | |
| 1 | On site, slabs only | 3,000 = | 80,000 | 200,000 | 66,000 | 3 | 133,000 | 82,000 | 50,000 | 50,000 | 116,000 | 777,000 |
| 2 | Same as above, but
stationary factory | 3,000 | 150,000 | 200,000 | 66,000 | | 133,000 | 82,000 | 50,000 | 50,000 | 116,000 | 847,000 |
| 3 | On site, all elements,
no factory finishing | 7,000 | 170,000 | 500,000 | 166,000 | | 235,000 | 170,000 | 100,000 | 72,000 | 250,000 | 1,663,000 |
| (1) 4 | Same as above but
stationary factory | 7,000 | 350,000 | 500,000 | 166,000 | | 235,000 | 170,000 | 100,000 | 148,000 | 250,000 | 1,917,000 |
| (2) 5 | Stationary, all
elements, factory
semi-finished | 8,000 | 400,000 | 500,000 | 166,000 | | 235,000 | 170,000 | 100,000 | 154,000 | 250,000 | 1,975,000 |
| (3) 6 | Stationary, all
elements, factory
finished | 11-13,000 | 550,000 | 500,000 | 166,000 | | 235,000 | 170,000 | 100,000 | 164,000 | 250,000 | 2,135,000 |

משרד השיכון
לשכת החברות - היחידה הכלכלית

אומדן מחוקן של הוצאות והכנסות ב- 8 שנות פעילות של מפעל
לבניה טרומית בהתאם ל"שיטת סליבין"
(בדולרים)

| שנים
8 - 3 | שנה
2 | שנה
1 | |
|---------------|-----------|-----------|-----------------------------|
| 1,000 | 667 | 333 | היקף ייצור (ביו"ד) |
| | | | <u>הוצאות</u> |
| 314,000 | 209,440 | 104,560 | 1. מחת |
| 300,000 | 300,000 | 300,000 | 2. הוצאות שוטפות |
| 888,000 | 888,000 | 888,000 | 3. עבודה |
| 1,750,000 | 1,165,500 | 582,750 | 4. חומרים |
| 70,000 | 46,700 | 23,300 | 5. הוצאות תכנון טיפוס חדש |
| 200,000 | 133,200 | 66,600 | 6. חטלובים |
| 3,522,000 | 2,742,840 | 1,965,210 | סה"כ הוצאות |
| 3,520 | 4,110 | 5,900 | הוצאה ממוצעת ליו"ד |
| | | | סה"כ הכנסות (לפי 4,200 דולר |
| | | | ליו"ד ורווח של 15% בממוצע |
| 4,200,000 | 2,801,400 | 1,398,600 | ליו"ד) |

UNITED STATES
DEPARTMENT OF AGRICULTURE

UNITED STATES DEPARTMENT OF AGRICULTURE
BUREAU OF PLANT INDUSTRY
WASHINGTON, D. C.

| | 1900 | 1901 | 1902 |
|---------------|------|------|------|
| Wool (all) | 100 | 100 | 100 |
| Wool (all) | 100 | 100 | 100 |
| 1. Wool | 100 | 100 | 100 |
| 2. Wool (all) | 100 | 100 | 100 |
| 3. Wool | 100 | 100 | 100 |
| 4. Wool | 100 | 100 | 100 |
| 5. Wool | 100 | 100 | 100 |
| 6. Wool (all) | 100 | 100 | 100 |
| 7. Wool | 100 | 100 | 100 |
| 8. Wool | 100 | 100 | 100 |
| 9. Wool | 100 | 100 | 100 |
| 10. Wool | 100 | 100 | 100 |
| 11. Wool | 100 | 100 | 100 |
| 12. Wool | 100 | 100 | 100 |
| 13. Wool | 100 | 100 | 100 |
| 14. Wool | 100 | 100 | 100 |
| 15. Wool | 100 | 100 | 100 |
| 16. Wool | 100 | 100 | 100 |
| 17. Wool | 100 | 100 | 100 |
| 18. Wool | 100 | 100 | 100 |
| 19. Wool | 100 | 100 | 100 |
| 20. Wool | 100 | 100 | 100 |
| 21. Wool | 100 | 100 | 100 |
| 22. Wool | 100 | 100 | 100 |
| 23. Wool | 100 | 100 | 100 |
| 24. Wool | 100 | 100 | 100 |
| 25. Wool | 100 | 100 | 100 |
| 26. Wool | 100 | 100 | 100 |
| 27. Wool | 100 | 100 | 100 |
| 28. Wool | 100 | 100 | 100 |
| 29. Wool | 100 | 100 | 100 |
| 30. Wool | 100 | 100 | 100 |
| 31. Wool | 100 | 100 | 100 |
| 32. Wool | 100 | 100 | 100 |
| 33. Wool | 100 | 100 | 100 |
| 34. Wool | 100 | 100 | 100 |
| 35. Wool | 100 | 100 | 100 |
| 36. Wool | 100 | 100 | 100 |
| 37. Wool | 100 | 100 | 100 |
| 38. Wool | 100 | 100 | 100 |
| 39. Wool | 100 | 100 | 100 |
| 40. Wool | 100 | 100 | 100 |
| 41. Wool | 100 | 100 | 100 |
| 42. Wool | 100 | 100 | 100 |
| 43. Wool | 100 | 100 | 100 |
| 44. Wool | 100 | 100 | 100 |
| 45. Wool | 100 | 100 | 100 |
| 46. Wool | 100 | 100 | 100 |
| 47. Wool | 100 | 100 | 100 |
| 48. Wool | 100 | 100 | 100 |
| 49. Wool | 100 | 100 | 100 |
| 50. Wool | 100 | 100 | 100 |
| 51. Wool | 100 | 100 | 100 |
| 52. Wool | 100 | 100 | 100 |
| 53. Wool | 100 | 100 | 100 |
| 54. Wool | 100 | 100 | 100 |
| 55. Wool | 100 | 100 | 100 |
| 56. Wool | 100 | 100 | 100 |
| 57. Wool | 100 | 100 | 100 |
| 58. Wool | 100 | 100 | 100 |
| 59. Wool | 100 | 100 | 100 |
| 60. Wool | 100 | 100 | 100 |
| 61. Wool | 100 | 100 | 100 |
| 62. Wool | 100 | 100 | 100 |
| 63. Wool | 100 | 100 | 100 |
| 64. Wool | 100 | 100 | 100 |
| 65. Wool | 100 | 100 | 100 |
| 66. Wool | 100 | 100 | 100 |
| 67. Wool | 100 | 100 | 100 |
| 68. Wool | 100 | 100 | 100 |
| 69. Wool | 100 | 100 | 100 |
| 70. Wool | 100 | 100 | 100 |
| 71. Wool | 100 | 100 | 100 |
| 72. Wool | 100 | 100 | 100 |
| 73. Wool | 100 | 100 | 100 |
| 74. Wool | 100 | 100 | 100 |
| 75. Wool | 100 | 100 | 100 |
| 76. Wool | 100 | 100 | 100 |
| 77. Wool | 100 | 100 | 100 |
| 78. Wool | 100 | 100 | 100 |
| 79. Wool | 100 | 100 | 100 |
| 80. Wool | 100 | 100 | 100 |
| 81. Wool | 100 | 100 | 100 |
| 82. Wool | 100 | 100 | 100 |
| 83. Wool | 100 | 100 | 100 |
| 84. Wool | 100 | 100 | 100 |
| 85. Wool | 100 | 100 | 100 |
| 86. Wool | 100 | 100 | 100 |
| 87. Wool | 100 | 100 | 100 |
| 88. Wool | 100 | 100 | 100 |
| 89. Wool | 100 | 100 | 100 |
| 90. Wool | 100 | 100 | 100 |
| 91. Wool | 100 | 100 | 100 |
| 92. Wool | 100 | 100 | 100 |
| 93. Wool | 100 | 100 | 100 |
| 94. Wool | 100 | 100 | 100 |
| 95. Wool | 100 | 100 | 100 |
| 96. Wool | 100 | 100 | 100 |
| 97. Wool | 100 | 100 | 100 |
| 98. Wool | 100 | 100 | 100 |
| 99. Wool | 100 | 100 | 100 |
| 100. Wool | 100 | 100 | 100 |

אברהם עקביה, רואה חשבו

A. AKAVIA, B.Sc., F.C.C.S., Certified Public Accountant

Haifa, 65, Ha'azmaout Rd., Tel. 531055


Tel-Aviv, 15, Carlebach St., Tel. 36121
38620

חיפה, דרך העצמאות 65, טל. 531055

תל-אביב, רח' קרליבך 15, טל. 36121
38620

חיק מס' 205

חיפה, י"א בחמוז השכ"ז
19 ביולי 1967



לכבוד
מר מ. לפיד
מנהל - "שבח" חברה לייצור בתים להרכבה בע"מ
תל-אביב

מר לפיד היקר,

הנדון: השקעות בנכסי החברה ליום 31.3.65

בהמשך לשיחתנו ביום 16.7.67, הנני שמח להמציא לך בזה פרטים על השיטה לפיה נקבעו ההשקעות בנכסים שהועברו לחברה ביום 31.3.65.

כיסוד לפעולה יש לראות את המסמכים הבאים:

א. חוזה בין ח. סלבין לבין משרד השיכון מיום 30.6.64 (ראה במיוחד סעי' 9 א', עמ' 5).

ב. דו"ח וועדת ישי (נתמנתה לפי תנאי החוזה הנ"ל) מיום 2.9.65.

ג. החלטות הדירקטוריון של החברה.

לאור ההחלטות הנ"ל נערך הדו"ח שלי על השקעות החברה ליום 31.3.65.

מצב החשבון של חברת "שבח" עם ח. סלבין ליום 31.3.65, כפי שאושר ע"י הדירקטוריון של החברה, הוא בהתאם לדו"ח הר"ב (אושר ע"י הדירקטוריון).

אשמח להמציא לך כל אינפורמציה נוספת שתידרש.

בכבוד רב,

אברהם עקביה


מר ח. סלבין
מר ע. שילוני

העתק: מר ה. אשכנזי
מר ש. לברון

11200 N. 1st, Suite 100
A. AKAVIA, B.Sc., F.C.C.S., Certified Public Accountant

30000
30000
30000

30000
30000
30000



30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

30000

מצב החשבון של "שבח" עם מר ח. סלבין
ליום 31 במרס 1965

השקעות

ס"ה לפי דו"ח רואה החשבון
(ליום 31.3.65)
תוספת (לסעיף הוצאות כלליות)

2,288,585
62

2,288,647
145,237

מקדמה שונות

ס"ה אקטיב המועבר לחברה

2,433,884 ל"י

מסורות (זכאים)

מדינת ישראל - משדד השיכון
תוספת כנ"ל

1,899,938
62

1,900,000

1,007 הועבר לחשבון מניות המייסדים

1,898,993
177,862

2,076,855
357,029

חברת "שבח"

היתרה - לזכות ח. סלבין

ס"ה זכות

2,433,884 ל"י

יחד עם הסכום של 400,000 ל"י מחשבון המדינה (משדד השיכון)
עומד לזכותו של ח. סלבין ביום 31.3.65 סכום של 757,029 ל"י כחשולם
ע"ח מניות.

STATE OF NEW YORK

IN SENATE

January 1, 1901

REPORT OF THE

COMMISSIONER OF THE LAND OFFICE

FOR THE YEAR 1900

ALBANY:

WHEAT, BARNES & COMPANY, PRINTERS

CONTENTS

ANNUAL REPORT OF THE COMMISSIONER

OF THE LAND OFFICE

REPORT OF THE COMMISSIONER OF THE LAND OFFICE

FOR THE YEAR 1900

ALBANY: WHEAT, BARNES & COMPANY, PRINTERS

THE STATE OF NEW YORK, 1901, has the honor to acknowledge the receipt of the report of the Commissioner of the Land Office for the year 1900, and to express its appreciation of the thoroughness and accuracy of the same.

סלח
דין והשכון של ועדה לענין קביעת בסיס להתחייב מחירי הציוד
למפעל "שבח" ליצור בוצים סרומיים.

הרכב הועדה

הועדה הוקמה והרכבה נקבע בהחלט לסעיף 9 של החוזה בין ממשלת ישראל המיוצגת ע"י משרד השכון
ובין מר חיים סלבין מיום 30.4.1964.

מר ח. סלבין נאמחן בועדה באופן אישי
מר מ. יבנאלי מונה ע"י משרד השכון
מר ש. ישי מונה ע"י מנהל מכון החקנים.

הפקידים

בהחשב בסוג הציוד שהוכנן ונבנה ע"י מר סלבין, אומיו המיוחד, הגורמים הקשורים במחוחו,
העובדה שלא קיימים פריטי-ציוד דומים אחר ניתן להשוותו אתם וכן בהחשב בצורת התייעוד
המתחם לייצורו של הציוד הנ"ל, לא ראתה הועדה כאפשרי לקבוע בצורה חד-משמעית את שוים של
פריטי הציוד כמבוקש בסעיף 9 של החוזה בין הממשלה ומר סלבין מיום 30.4.1964 ובסעיף (א)-2-א
של הפרטי-כל מישיבת מועצה מנהלים של "שבח" מיום 3.1.1965.

הועדה הצטמצמה איפוא בעבודתה לתפקידים כדלקמן כמבוקש במסמכים הנ"ל :

(א) קביעת דמי שמוש בשירותי בית המלאכה והציוד הפרטי של מר סלבין
בתקופת 31.3.1965 - 1.4.1960.

(ב) קביעת גובה דמי הכנון ומקוח מקצועי על ייצור הציוד הנ"ל בתקופת דלעיל;

(ג) קביעת ערך שעה עבודה אקווילנסיית עבור עבודות מהבט דומות בהנחה של בצוע קבלני
בחנאי "רג"י.

מסקנות

(א) דמי שמוש בשירותי בית מלאכה והציוד המוחקן בו

חברי הועדה בקרו בבית המלאכה של מר סלבין בצרימין וסקרו את הציוד המוחקן ואה השירותים
המצויים בו. הועדה סומכת את ידיה על האומדן הבטיטי של דמי שמוש שנהיים בשירותים הנ"ל
המבוססים על ערך הציוד בהנאים של היום ודמי השכרה מקובלים בתעשיה בסך 44,500 ל"י
(כמפורט בנספח א'). בהחשב בערך הבטיטי הנ"ל, בשנויים שחלו במחירים בסך ההקומה
1960-1965 ובמדה הנצול של בית המלאכה בשנים הנ"ל נראים המספרים הניהנים כנספח א'
כסבירים והועדה מאשרת את הסכום הכולל של 142,000 ל"י כסך 5 השנים הנ"ל המומיע בסיוטת
הסיכום של החשבונות "שבח" - סלבין (נספח למכתבו של אברהם עקביה מיום 9.6.1965).

7/1
0/39

THE CASE

On the 1st day of January, 1900, the following case was presented to the court for its consideration:

The case was presented to the court for its consideration, and the court, after hearing the evidence, found that the facts were as follows:

THE FACTS

The facts of the case were as follows: On the 1st day of January, 1900, the following case was presented to the court for its consideration: The case was presented to the court for its consideration, and the court, after hearing the evidence, found that the facts were as follows:

The facts of the case were as follows: On the 1st day of January, 1900, the following case was presented to the court for its consideration:

(1) The case was presented to the court for its consideration, and the court, after hearing the evidence, found that the facts were as follows:

(2) The case was presented to the court for its consideration, and the court, after hearing the evidence, found that the facts were as follows:

(3) The case was presented to the court for its consideration, and the court, after hearing the evidence, found that the facts were as follows:

THE OPINION

The court, after hearing the evidence, found that the facts were as follows:

The court, after hearing the evidence, found that the facts were as follows: On the 1st day of January, 1900, the following case was presented to the court for its consideration: The case was presented to the court for its consideration, and the court, after hearing the evidence, found that the facts were as follows:

(ב) דמי הכנון ומקום מקצועי

הועדה קבלה את ההנחה שהעבודה אשר נעשתה ע"י מר סלבין עד 1960 ושעבודה קבל המורה בשותפות בחברה "שבח" כללה קביעה כללית של הטכנולוגיה, עבודות פיתוח ונסוי לשם קביעת סוגים וגודל של הציוד המכני, עבוד הגחונים הבסיסיים האלה, והכנון כללי של בית החרושה. התכנון המפרט של הציוד אשר נבנה ע"י מר סלבין במשך השנים 1960-1965 נעשה במקביל עם ייצורו. במשך המקומה הנ"ל הכין מר סלבין שרטוטי-עבודה, תרשימים, פיקה על הבצוע מנקודה ראיה טכנית וגם ניהל את עבודות הייצור (דבר אשר אינו נכלל כרגיל בשירותים הניהוגים ע"י מהנדס מתכנן-מבצע).

נהוג לבטא את דמי התכנון והפקוח המקצועי באחוזים של ערך ההוצאה הכוללת לייצור של הציוד (חברים, רכש של חלקי ציוד מכני הנכללים בציוד הנבנה, שכר עבודה, שכירות שירותים וציוד עבודה). האחוזים הנ"ל נקבעים כרגיל בהתחשב במדת הסכום של הציוד, מספר האלמנטים החוזרים והמשקל של האלמנטים הנבנים במיוחד לעומת חלקים טנדרטיים הנרכשים והנכללים בבניהו.

אם-כי לא ניתן עתה לערוך בדיקה מדויקת של הגורמים הנ"ל, נלקחו הגורמים האלה באופן כללי בחשבון ע"י הועדה בקביעת ההמורה הנאותה המגיעה למר סלבין עבור שירותי התכנון המפרט, הפקוח והנהול כנ"ל. הועדה הגיעה למסקנה שההמורה הנ"ל צריכה להיות בסדר גודל של 10%, היינו (בהתבסס על סיכום החשבונות המופיעים בדו"ח אברהם עקביה מיום 9.6.1965):

| | |
|-------------------------|---------------|
| שכר עבודה 1960/1 | 628,077 ל"י |
| ציוד וחברים בתקומה הנ"ל | 658,264 " |
| שכירות בית-מלאכה וציוד | 142,000 " |
| | <hr/> |
| | 1,428,341 ל"י |

10% מהסך הנ"ל : 142,834 ל"י לעומת הסך 114,258 ל"י המופיעים בסכום של אברהם עקביה והסבוסטים על המורה בסך 8% מערך הציוד בהתאם לחשבונות של מר סלבין. (הערה : המספרים דלעיל הם לפני בקורה, כפי שצוין על ידי אברהם עקביה בסיכומיו הנ"ל).

ההמורה כנ"ל בגובה של 10% מבוססת על ההוצאות למעשה לבניה הציוד כמסומר לעיל חוץ הנחה שבצוע עבודות ייצור בהתאם לתכנון של מר סלבין הושלמו ברובן, כמפורט בנספח ה". הועדה לא ראתה מתפקידה לבדוק אם ובאיזו מדה יהיה צורך בעבודות השלמה ו/או שנויים ומה עלול להיות היקף עבודות התכנון הקשורות בכך.

אין איחוא ליחס את ^לקביעת התכנון ומקום כנ"ל למדת השלמה הציוד ואין לראות בקביעות הועדה הבעה דעה כל שהיא ביחס לטעיף 10א" של החוזה המכתיב שהציוד צריך להמסר לחברה ע"י הממציא "במצב טוב וחקיך וראוי לשמוש מיד".

(ג) החשיבים המבוססים על הנחה של בצוע ע"י קבלני-חוץ

(1) עבודות בחנאי "רג"י" (ז.א. על בסיס של שכר לשעה עבודה של קבלן) מבוצעות כיום לרוב רק במקרים של עבודות בהיקף קטן שקשה להגדירן מראש ובמקרים של השלמות ושנויים. עבודות בהיקף רחב מבוצעות לרוב על בסיס קבלני ולא על בסיס של השלום דמי שעה.

(2) המחירים עבור עבודות מתכת בחנאי "רג"י" כנ"ל נעים בגבולות רחבים. בו בזמן שמפעלי המתכת הגדולים מחשבים כיום עד 10 ל"י עבור שעה עבודה, אפשר לבצע עבודות בבתי מלאכה קטנים בסיב שזה ובמחירים של 5-6 ל"י לשעה.

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...
...the ... of the ...

(3) בהתחשב בכך שלא כל העבודות היו מחייבות בצו ע"י מפעלים גדולים ושחלק ניכר מהן אפשר היה לבצע בבתי מלאכה בינוניים וקטנים, קבלה הועדה כמחיר ממוצע בתנאי היום את המחיר של 7.50 ל"שעת עבודה. ברם, מחיר זה מתייחס לעבודות בלתי רצופות בהיקף מוגבל. בהתחשב בהיקף העבודות ורציפותן, טביר להניח שהמחיר היה לפחות 10 אחוז יותר נמוך, היינו 6.75 ל"ש בתנאים של היום.

בהתאם לכך ובהתחשב בהתיקרויות שחלו בסך 5 השנים האחרונות, בטטה הועדה את תחשיביה על המספרים כדלקמן:

| | |
|--------------|-----------|
| 4.30 ל"ש שעה | 1960/1961 |
| " " 4.50 | 1961/1962 |
| " " 4.95 | 1962/1963 |
| " " 5.65 | 1963/1964 |
| " " 6.75 | 1964/1965 |

(4) בהסתמכו על המספרים המופיעים בחשבונות שהוגשו על ידו, הביע מר סלבין בדיוני הועדה את הדעה שבמקרה של בצו העבודות ע"י קבלן, חלק מעבודות ההכנה והשרותים הבלתי ישירים שלא סווגו על ידו כ"שעות קבלנותיות" היה נרשם ע"י הקבלן כשעות קבלנות ישירות והיה נדרש עבורן תשלום.

לעומת זאת כולל מחיר שעה-רג"י במקרה של בצו ע"י קבלן הוצאות נהול עבודה, אשר התמורה עבורן במקרה של מר סלבין נכללה בסך של 142,834 ל"ש המומלץ ע"י הועדה בסעיף (ב) דלעיל. כמו-כן כולל המחיר של קבלני-חוץ הוצאות מימון, אשר לא היו למר סלבין.

לדעת הועדה מתאזנים שני הגורמים האלה.


בהתחשב בהנ"ל החליטה הועדה לבסס את תחשיבי ההשוואה על ההנחה שמספר שעות העבודה המושקע ע"י הקבלן היה שווה למספר שעות העבודה ה"קבלנותיות" המופיע ברשומים של מר סלבין.

(5) התחשיבים למקרה של בצו ע"י קבלני-חוץ והשוואתם עם מחירי הבצוע לפי הרשומים של מר סלבין ניתנים בנספחים ג' ו-ד.

ההפרש לזכותו של מ. סלבין בין הסך 1,147,000 ל"ש המתקבל כנ"ל ובין 770,000 ל"ש המבוסס על הרשומים של מר סלבין עבור בצו העבודה חוץ שמוש בבית המלאכה שלו הוא 377,700 ל"ש ובהתאם לסעיף (א)-3 של הפרטי-כל של ישיבת מועצה המנהלים של "שבח" מיום 3.1.1965 שמורה למר סלבין הזכות לתבוע תשלום ההפרש הנ"ל מחוץ רוחיה של החברה בעת שרוחיה כאלה ייווצרו.


 ש. ש. ישי
 מהנדס
 רחוב מרדכי 15
 תל-גנים, רמת-גן


 מ. יבניאלי
 מהנדס
 רחוב פיכמן 13
 תל-אביב


 ח. סלבין
 מהנדס
 רחוב פרישמן 43
 תל-אביב

2 בספטמבר, 1965.

1. The first part of the report deals with the general situation of the country and the progress of the work during the year. It is divided into two main sections: the first section deals with the general situation and the second section deals with the progress of the work.

2. The second part of the report deals with the results of the work during the year. It is divided into two main sections: the first section deals with the results of the work and the second section deals with the conclusions.

| Year | 1951 | 1952 | 1953 | 1954 | 1955 |
|------|------|------|------|------|------|
| 1951 | 100 | 100 | 100 | 100 | 100 |
| 1952 | 100 | 100 | 100 | 100 | 100 |
| 1953 | 100 | 100 | 100 | 100 | 100 |
| 1954 | 100 | 100 | 100 | 100 | 100 |
| 1955 | 100 | 100 | 100 | 100 | 100 |

3. The third part of the report deals with the conclusions of the work during the year. It is divided into two main sections: the first section deals with the conclusions and the second section deals with the recommendations.

4. The fourth part of the report deals with the recommendations of the work during the year. It is divided into two main sections: the first section deals with the recommendations and the second section deals with the conclusions.

5. The fifth part of the report deals with the conclusions of the work during the year.

6. The sixth part of the report deals with the conclusions of the work during the year. It is divided into two main sections: the first section deals with the conclusions and the second section deals with the recommendations.

7. The seventh part of the report deals with the conclusions of the work during the year. It is divided into two main sections: the first section deals with the conclusions and the second section deals with the recommendations.

8. The eighth part of the report deals with the conclusions of the work during the year. It is divided into two main sections: the first section deals with the conclusions and the second section deals with the recommendations.



9. The ninth part of the report deals with the conclusions of the work during the year.

נספח א'

תיאור הצורך וכתי המלאכה של מר סלבין וקביעה דמי השימוש עבורם

הערה : דמי השימוש אינם כוללים הוצאות אחזקה שוטפות וחיקונים.

דמי שימוש שנתיים בסיסיים

תיאור הצורך

| | |
|------------|---|
| | <p>1.0 בית מלאכה מכני</p> <p>שטח 500 מ"ר גובה עד 6 מ"ר
חיבורי חשמל עד 200 אמפר
חיבורי מים 3"
מחסן סגור בבית המלאכה</p> |
| 10,000 ל"י | |
| | <p>2.0 עבורן שער 10 טון</p> <p>כושר הרמה 10 טון
רוחב 11.5 מטר
גובה הרמה 6 מטר
אורך נסיעה 300 מטר
הפסים מבוססים על קורות בטון
וקלונסאות ביטוס כל 3 מטר</p> |
| 22,000 " | |
| | <p>3.0 מעבר להרכבת תבניות</p> <p>הא בנוי מבטון בעומק 1.8 מטר
וברוחב 11 מטר ביסוס לתבניות
ואספקה אויר וחשמל</p> |
| 3,000 " | |
| | <p>3.0 משרד-מחסן</p> <p>מבנה בנוי מבטון ארוטי</p> |
| 1,000 " | |
| | <p>4.0 ציוד מכני</p> <p>4.1 3 מחדשות
4.2 4 מקדחות
4.3 1 משור מהכת מכני
4.4 1 מקצוע (שמינג)
4.5 3 מקדחות עם בסיס מגנטי "3/4", "1", "1 1/4"
4.6 1 מכונת ליטוש
4.7 ציוד עזר</p> |
| 6,000 " | |
| | <p>5.0 20 טרנספורטורים לריהוט</p> <p>הכמות מתייחסת לשנהיים האחרונות. בחישוב
דמי השימוש נלקחו בחשבון 50% מטספר זה
כמסוצע לכל החקופה.</p> |
| 2,500 " | |

CHAPTER 1. THE HISTORY OF THE
UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

THE HISTORY OF THE UNITED STATES OF AMERICA

נספח א* (המשך)

6.0 גורטורים לריכוך

| | | |
|-----|---------------|----------|
| 6.1 | 1 דיזל גורטור | 250 אמפר |
| 6.2 | 1 גורטור | 400 " |
| 6.3 | 1 גורטור | 300 " |
| 6.4 | 1 גורטור | 250 " |

בם כאן נחונה התמונה של השימוש בציוד בשנהלים
האחרונות.

בחישוב דמי השימוש נלקחו בחשבון 50%
ממספר זה כסומצע לכל התקופה

3,000 ל"י

7.0 מכשירי עבודה שונים

כלי-יד
עגלות טרנספורט
מכשירי ריתוך אוטוגנים
מכשירי הידראולי-יד 50 טון
מדחס אוויר
מנופי יד

2,000 "

8.0 סיכום

סה"ה דמי שימוש בסיסיים לשנה

49,500 ל"י

בהתחשב בגורמים המפורטים ל ט"ו
הגענו לחיוב ממשי עבור השימוש בבתי המלאכה ובציוד כדלקמן :

| השנה | ערך החיוב ל |
|--|------------------|
| 1. 1960/1961 | 12,000 ל"י |
| 2. 1961/1962 | 24,000 " |
| 3. 1962/1963 | 36,000 " |
| 4. 1963/1964 | 42,000 " |
| 5. 1964/1965 (עבור הציוד הטכנולוגי בלבד) | 28,000 " |
| | <u>142,000 "</u> |

סה"כ

1. General

- 1.1. Object
- 1.2. Scope
- 1.3. References
- 1.4. Definitions

The purpose of this document is to provide a clear and concise description of the project and its objectives.

The scope of the project is limited to the development of a new software application.

The references listed in this document are for information only and do not constitute a part of the project.

2. Project Description

- 2.1. Background
- 2.2. Objectives
- 2.3. Requirements
- 2.4. Deliverables
- 2.5. Timeline

3. Conclusion

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

- 1. Object
- 2. Scope
- 3. References
- 4. Definitions
- 5. Deliverables
- 6. Timeline

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

The project is expected to be completed by the end of the year.

פירוט הצירוף הסכנונולוגי

כללי

רצונה למטה רשימה, כפי שנמסרה ע"י מר סלביץ, של הצירוף השייך לתהליך הסכנונולוגי ושיועבר למפעל במקומו החדש.

הרשימה והערות לרשימה נכונים לתאריך 1.4.1965.

ברשימה זו נכלל צירוף שנבנה ע"י מר סלביץ, כולל חלקים שנרכשו מוכנים ובין צירוף שנקנה לפני 1960 ושינואל במפעל החדש.

ההערות בסוף כל סעיף ביחס למדה הגמר של הצירוף ליום 1.4.1965 מהיחסות למצב הבצוע המבוטס על הסכנונו של מר סלביץ. אין לראות בהן נסיון של הכעת דעה אם ובאיזו מדה מוכן הצירוף להרצה או להפעול סדיר, אם יהיה צורך בעבודות השלמה או שנויים ומה יהיה היקפן.

1.0 מחלקת יציקה

| | | |
|-----|---------------------------------------|---------|
| 1.1 | תבניות רצפה | 2 קומפ' |
| 1.2 | " קירות רוחב + רצפה מדרגות | " 2 |
| 1.3 | " קיר חוץ מונוליטי + רצפה | " 1 |
| 1.4 | " קירות מחוללים כולל סידורי הפעלת מ"מ | " 1 |
| | גרעינים | " 1 |
| 1.5 | " מחיצות 4 גופים | " 1 |
| 1.6 | " תא סניטרי 4 מחיצות | " 1 |

התכנית כוללת : ביטוס, מערכת קפיצים, מסגרת הוץ עם הבסיס, החתיות גוף ביניים עם קונוסים, 2 גופי הזזה, צינורות הזזה עם החלקה עליונה ותחתונה, סגרי אורך, גופי סוגרה, קשרי מסדרים פניאומטים, מסדרים הידראולים, קובעי גופי הזזה ליציקה, פנים ומסגרות, מערכת קבלה וקביעה של המשפך היברציוני, סידור חימום בקיטור וסידורי ניקוז מי קונדנסט, סידור רחיצה לחץ נטון וגבוה, סידורים לויברציה ע"י אויר דחוס, מעברים משפך ויברציוני, סידורי הפרדה המשפך בגמר היציקה, סגרי גמישות גופי הזזה.

1.7 כרכת רחיצה עם משאבה "3 6 אס" עם מסננים וכיטור

1.8 דוד קיטור 1 טונה לשעה, ברכות להורדה לחץ לאינסטלציה

1.9 ברכת טולר 10 מ"ק

1.10 3 מערכות ברכות ניקוז עם משאבות למי קונדנסט.

הערות : (1) 4 מחוך התכניות המוזכרות למעלה גמורות. עבור ארבעת הנוהרים יש חומר אולם יש להשקיע בהן עוד כ-50% עבודה.

(2) ישנם 6 גופי סוגרה מוכנים. שאר השקים יש לבנות.

נספח ב' (המשך)

2.0 ויברציה

| | | |
|---------|---|-----|
| 40 כו"ס | 2 ויברטורים חשמליים | 2.1 |
| " 30 | " " | 2.2 |
| " 5 | " " | 2.3 |
| | בא"ר עם סידורי קשירה לחבניה | 2.4 |
| | משמך לברציוני עם מערכת קשירה לחבניה וסידורי קבלה ל-4 ויברטורים חשמליים. | 2.5 |

3.0 פניאומטיקה

| | |
|--|-----|
| 8 קומפ" כ"א להפעלה 10 צילנדרים אויר באורך 25 ס"מ | 3.1 |
| 2 קומפ" כ"א להפעלה 20 " " " 25 ס"מ | 3.2 |

כל קומפלט בנוי ממסגרת עליונה ותחתונה, 2 מערכות הזזה ו-10 מקומות קביעה לצילנדרים האויר וכן מערכת צנורות וברזים להפעלה הצילנדרים.

- הערות:
1. ~~כ"א~~ 50% מס"ה הצילנדרים הדרושים ~~הצנרת~~.
 2. הצנרת ~~הברזים~~ להפעלה עדין חסרים.

4.0 מסדר אגרגטים

4.1 מסדר אגרגטים מס' 1 הבנוי עם 3 מאזנים של 1 מ"ק כל אחד עם נפוח. 2 סילוסים + 2 קונביירים הנוטעים על חסי ברזל.

סילו למלס עם חלזון מזון.

4.2 מסדר אגרגטים מס' 2 - כולל מיכל קבלה, קונבייר ראשי, קונבייר עזר ונפה.

4.3 מאזני גשר לשקילה 40 טון (בהזמנה).

4.4 מערכת נסיעה לציוד הנ"ל

4.5 2 מובילי בטון 6 מ"ק כ"א

4.6 מכונת בטון על מערכת זחלים 1×2 מ"ק עם קונבייר הגשה.

4.7 2 קונביירים מסחובבים על גלגלים להגשה בטון עם מערכת חשמל.

4.8 דיזל גנרטור 215 קו"א להפעלת הויברטורים.

- הערות:
1. מאזני הגשר הם רק בהזמנה
 2. מובילי הבטון ללא מרכב
 3. הקונביירים להגשה ללא סידורי הנעה ומערכות חשמל.

1. Introduction

- 1.1. The purpose of this study is to investigate the effects of the proposed system on the performance of the system.
- 1.2. The study is organized as follows: Chapter 2 describes the system architecture. Chapter 3 describes the experimental setup. Chapter 4 presents the results of the experiments. Chapter 5 discusses the conclusions and future work.

2. System Architecture

- 2.1. The system architecture is shown in Figure 1.
- 2.2. The system consists of the following components:

The system is designed to be modular and scalable. It can be configured to run on a single machine or on a distributed system.

- 2.3. The system is implemented in Java.
- 2.4. The system is tested using the JUnit framework.

3. Experimental Setup

- 3.1. The experiments are conducted on a Windows 10 machine.
- 3.2. The system is tested using the JUnit framework.

The results of the experiments are presented in Chapter 4.

- 3.3. The system is tested using the JUnit framework.
- 3.4. The system is tested using the JUnit framework.

The results of the experiments are presented in Chapter 4.

The results of the experiments are presented in Chapter 4.

The results of the experiments are presented in Chapter 4.

The results of the experiments are presented in Chapter 4.

The results of the experiments are presented in Chapter 4.

The results of the experiments are presented in Chapter 4.

4. Results and Discussion

- 4.1. The results of the experiments are presented in Table 1.
- 4.2. The results of the experiments are presented in Table 2.

5.0 מנופים

- 5.1 מנוף יצור מס' 1
- 5.2 מנוף יצור מס' 2
- 5.3 מנוף הקמה
- 5.4 3 מנופים מסחובבים
- 5.5 מנוף מונוריל 2 טון למ"ח רשחות זיון
- 5.6 מנוף מונוריל 1 טון " " "

- הערות:
- 1. מנוף יצור מס' 1 עובד במפעל היטן
 - 2. מנוף יצור מס' 2 מורכב במפעל החדש
 - 3. אחד מהמנופים המסחובבים חסר כננה הרמה.

6.0 טרנספורט

- 6.1 3 יצולים
- 6.2 עגלה טרנזיט
- 6.3 2 טריילרים להובלה קירות
- 6.4 2 משטחי טרנספורט
- 6.5 1 מסדר סיבוב רצפה
- 6.6 1 מוביל T Diamond
- 6.7 2 יצולי עזר

- הערות:
- 1. הטרילרים להובלה נזקקים לשיפוץ כללי ומערכות צמיגים חדשות.
 - 2. המוביל T Diamond זקוק לשיפוץ כללי וצמיגים חדשים
 - 3. יצולי העזר - האחד גמור ובשני יש ^(האחד) חומרי ניש להשקיע עוד 50% מהעבודה.

7.0 מסדרים

- 7.1 מסדר השחזה הבנוי מעגלה השחזה ורטיקלים, עגלה השחזה עליונה ומסילת נסיעה.
- 7.2 מסדר עבודות גמר 200 קומפ'
- 7.3 מסדר איחסון ורטיקלי 500 קומפ'

- הערות:
- 1. מסדר עבודות גמר - כ-60% מוכן
 - 2. מסדר איחסון ורטיקלי - כ-50% מוכן

8.0 ציוד

- 8.1 מוכן מיט לקיטור
- 8.2 מעטים הדרואלי

9.0 הידראוליקה

- 9.1 הפעלה עגלה החללים כולל ברכה, משאבות ואינסטלציה
- 9.2 הפעלה טברי אורך
- 9.3 הפעלה התנועות בהבניה המחיצות

הערות : 1. סעיף 9.2 - בוצע רק 50%
2. סעיף 9.3 - עדין לא בוצע

10. יצור רשתות זיון

- 10.1 מסדר של אלקו לריחוף בקורות של רשתות זיון
- 10.2 6 קומפ' של מסדרי בנ' גופים מרחביים של הזיון
- 10.3 4 קומפ' של מתסניות לגופי זיון מרחביים

הערות : 1. סעיף 10.1 - בוצע כ-50% עדין חסר טרנספורמטור הריחוף
2. סעיף 10.2 - יש חומר וחלקים יש לבצע עבודת הרמבה
3. סעיף 10.3 - כל החומר ישנו, יש להשקיע עוד 25% מהעבודה.

Section 1

1. The first part of the document is a letter from the President of the United States to the Congress, dated January 3, 1863. It is a very important document, as it contains the President's message to Congress, and is one of the most important documents in the history of the United States.

2. The second part of the document is a letter from the Secretary of the War Department to the Secretary of the Navy, dated January 10, 1863. It is a very important document, as it contains the Secretary's report to the Navy, and is one of the most important documents in the history of the United States.

Section 2

3. The third part of the document is a letter from the Secretary of the War Department to the Secretary of the Navy, dated January 10, 1863. It is a very important document, as it contains the Secretary's report to the Navy, and is one of the most important documents in the history of the United States.

4. The fourth part of the document is a letter from the Secretary of the War Department to the Secretary of the Navy, dated January 10, 1863. It is a very important document, as it contains the Secretary's report to the Navy, and is one of the most important documents in the history of the United States.

נספח ג'

חישוב מחיר שעת עבודה יצרנית (קבלנותית) במפעלי שבת-שליון בשנים 1960-1965
בניה הציון הטכנולוגי בלבד

| <u>1964/65</u> | <u>1963/64</u> | <u>1962/63</u> | <u>1961/62</u> | <u>1960/61</u> | | |
|----------------|----------------|----------------|----------------|----------------|--|----------|
| 8,572 | 12,898 | 10,402 | 5,428 | 2,685 | ס"ה ימי עבודה ברוטו | 39,985 |
| 5,652 | 8,495 | 6,800 | 3,580 | 1,714 | ס"ה ימי עבודה קבלנותיים | 26,241 |
| 2,920 | 4,403 | 3,602 | 1,848 | 971 | ס"ה ימי עבודה שרותים | 13,744 |
| 164,025 | 220,114 | 144,133 | 61,846 | 37,320 | ס"ה הוצאות בל"י (פעובל)
(ראה הערה) | 62,113.8 |
| 28.9 | 25.9 | 21.2 | 17.3 | 21.8 | מחיר יום עבודה קבלנותי (נטו) | - |
| 28,000 | 42,000 | 36,000 | 24,000 | 12,000 | ס"ה הוצאות דמי שימוש בבתי מלאכה | 142,000 |
| 5.1 | 4.9 | 5.3 | 6.7 | 7.0 | הוצאות דמי השימוש בבתי מלאכה
ביום עבודה | - |
| 34.00 | 30.80 | 26.5 | 24.0 | 28.8 | מחיר יום עבודה קבלנותי (ברוטו) | - |
| 4.25 | 3.85 | 3.3 | 3.0 | 3.6 | מחיר לשעת עבודה ישירה | - |
| 20 | 30 | 24 | 13 | 6 | מספר המוצע של עובדים ישירים
ביום (מחושב בהתבסס על
280 ימי עבודה) | - |
| 192,025 | 261,546 | 180,200 | 85,900 | 49,583 | סה"כ החוב בשכ"ע (מוכפל במחירים
סה"כ ימים קבלנותיים) | 769,251 |
| 27.91 | 24.05 | 13.39 | 11.15 | 6.50 | סה"כ החוב להוצאות שכר בתי מלאכה
לפי הנהלה המבונה | 770,077 |
| 192,025 | 262,114 | 180,133 | 85,846 | 49,959 | | |

הערות: (1) סעיף 5 : בסעיף זה נכללו : ס"ה הוצאות שכ"ע והוצאות סוציאליות, חומרי העשיה, אחזקה בית המלאכה, אחזקת טכונות וחשמל, הוצאות כלליות, הוצאות טכנולוגיות והובלה.

(2) ההוצאות בטבלה אינן כוללות אחוזי התכנון וההשקעה

(3) כל המספרים בטבלה מחבטטים על נהונים שהוגשו ע"י מר סלביץ

STATE OF NEW YORK
IN SENATE
January 10, 1907.

| REPORT OF THE
COMMISSIONERS OF THE LAND OFFICE
ON THE PROCEEDINGS OF THE
LAND OFFICE IN THE YEAR 1906. | LANDS
ACQUIRED | LANDS
DISPOSED | LANDS
RENTED | LANDS
IMPROVED | LANDS
UNDER
CONTRACT |
|---|-------------------|-------------------|-----------------|-------------------|----------------------------|
| 1. Lands acquired by purchase. | 100 | 50 | 20 | 10 | 5 |
| 2. Lands acquired by donation. | 50 | 20 | 10 | 5 | 2 |
| 3. Lands acquired by lease. | 20 | 10 | 5 | 2 | 1 |
| 4. Lands acquired by other means. | 10 | 5 | 2 | 1 | 0 |
| 5. Lands disposed of by sale. | 50 | 20 | 10 | 5 | 2 |
| 6. Lands disposed of by lease. | 20 | 10 | 5 | 2 | 1 |
| 7. Lands disposed of by other means. | 10 | 5 | 2 | 1 | 0 |
| 8. Lands rented to the public. | 20 | 10 | 5 | 2 | 1 |
| 9. Lands improved by the State. | 10 | 5 | 2 | 1 | 0 |
| 10. Lands under contract for sale. | 10 | 5 | 2 | 1 | 0 |
| 11. Lands under contract for lease. | 10 | 5 | 2 | 1 | 0 |
| 12. Lands under contract for other means. | 10 | 5 | 2 | 1 | 0 |
| 13. Lands under contract for other means. | 10 | 5 | 2 | 1 | 0 |
| 14. Lands under contract for other means. | 10 | 5 | 2 | 1 | 0 |
| 15. Lands under contract for other means. | 10 | 5 | 2 | 1 | 0 |
| 16. Lands under contract for other means. | 10 | 5 | 2 | 1 | 0 |

THE COMMISSIONERS OF THE LAND OFFICE
ALBANY, N. Y., JANUARY 10, 1907.

נספח ד'

חישוב מחיר שעת עבודה אקויוולנטית למ"י המלאכה אל.ח. סלבין
וההפרשים לזכותו

1. חישוב הזכות לשעה בכל אחת מהשנים 1960-1964


| השנה | מחיר לשעה עבודה
ישיבה מפעלי שבת-
סלבין | מחיר לשעה עבודה
ממוצעת בענף | מחיר אקויוולנטי של
שעה בבצוע קבלני
פחות 10% | יחידת זכות לשעה
עבודה |
|-----------|--|--------------------------------|---|--------------------------|
| 1960/1961 | * 3.6 ל"י | 4.75 ל"י | 4.30 ל"י | 0.70 ל"י |
| 1963/1962 | * 3.0 " | 5.00 " | 4.50 " | 1.50 " |
| 1962/1963 | * 3.3 " | 5.50 " | 4.95 " | 1.65 " |
| 1963/1964 | * 3.85 " | 6.25 " | 5.65 " | 1.80 " |
| 1964/1965 | * 4.25 " | 7.50 " | 6.75 " | 2.50 " |

(* לפי נספח ג')

2. חישוב ס"ה הזכות לח. סלבין

| השנה | יחידת זכות לשעה עבודה | ס"ה שעות עבודה ישיבות בשנה | ס"ה זכות |
|---------|-----------------------|----------------------------|--------------------|
| 1960/61 | 0.70 ל"י | $13,700 = 8 \times 1714$ * | 9,600 ל"י |
| 1961/62 | 1.50 " | $28,600 = 8 \times 3580$ * | 42,900 " |
| 1962/63 | 1.65 " | $54,400 = 8 \times 6800$ * | 89,800 " |
| 1963/64 | 1.80 " | $68,000 = 8 \times 8495$ * | 122,400 " |
| 1964/65 | 2.50 " | $45,200 = 8 \times 5652$ * | 113,000 " |
| | | סה"כ | <u>377,700 ל"י</u> |

(* מספר ימי עבודה לפי נספח ג')



מס' 205

אברהם עקביה

רואה חשבון

חיפה, דרך העצמאות 65, טל. 523292

תל-אביב, רח' קרליבך 15, טל. 36121

מס' 205



תל-אביב, 8 ביוני 1965

לכבוד
חברי הדירקטוריון
"שבח" חברה לייצור בתים להרכבה בע"מ
תל-אביב

אדונים נכבדים,

הנדון: חשבונות ח. סלבין

בימים אלו קיבלתי מאת מר ח. סלבין מצב החשבונות עם החברה ליום 31/3/65. החשבונות כוללים הוצאות שנעשו במשך שנים רבות ומבוססים על אלפי מסמכים. ברור, כי הבדיקה של המסמכים הללו, קביעת השייכות של ההוצאות וכדו' מחיבת עבודה מרובה.

בינתיים ערכתי בעקבות מר סלבין חלוקה של החשבונות לפי השנים והסוגים העיקריים וריכוז התקבולים והתביעות. נראה לי כי ריכוז זה, המצורף למכתבי, יהיה לעזר לחברי הדירקטוריון בקשר לכל שאלה עקרונית שיש צורך לדון בה.

בכבוד רב,



אברהם עקביה

הצגתי את ד. א. א. ל
משרד השיכון

REPORT: CONFIDENTIAL

ד' תר"ג
חשבונות "שנה" - ספ"ן
(ב' ספ"ן צ"י מ' ח"ס ספ"ן)
אב תיקות

כ'ח' אדר א' עכ"ל

21143

2000 10/10/2000 10/10/2000 (4+1)

787655

$(5+2) \times 10/3 = 3$

1542241

2829896

(13) $p'1/e \quad p''12'3$

(15691)

2014205

מלכות ונחמה

(8) ע'כ'ב'ל קודם פ'ת מ'ע'ד'ה ו'צ'ו'

162000

(10 + 9) || 11201 2020

136092

298092

3/3 א/א כ"ק (15)

224400

150237

1890

2686934

31/3/65 p/15

מ'תקפ"ח פ' ח' ס' כ"ב

1869938

12100 228.4

1007

פחית: הוצב למעלה מן המסדר

1868931

"DZD, 'ZDN"

176820

परिचय दो

2045751

'5 641,183

מכתב לזכרון של מ. סלמן (ת"פ תשכ"ו) 31/3/65

מחיר: כלל של סכום זה, מרסל בין 15000 לקראת מפתח, זהו תשלום
מלא בדי"ר של 400,000 ש"ח בלבד.

2/6/65

חשבונית שנתית - סלגין
 (כפי שבאגסו י"א חזק חזק סלגין - לפני בקורת)
 ליונת ישראל

| ס"ב | 1964/65
(31.3.65 3+) | 1963/64 | 1962/63 | 1961/62 | 1960/61 | 31 (מ"ס)
1960 | | | |
|---------|-------------------------|---------|---------|---------|---------|------------------|------------------------------------|----|--|
| | | | | | | | <u>הוצאות</u> | | |
| 628177 | 164025 | 220114 | 144133 | 61846 | 37959 | 100 | שכר עבודה והוצ' סוכ'אלא - סכ'נאליה | 1 | |
| 693919 | 209853 | 291244 | 124132 | 26096 | 7039 | 25555 | 3/3 אומרים - סכ'נאליה | 2 | |
| 1322076 | 373878 | 511158 | 268265 | 87942 | 44998 | 35655 | | 3 | |
| 159478 | 159478 | | | | | | שכר עבודה והוצ' סוכ'אלא - אפר' חבס | 4 | |
| 548322 | 548322 | | | | | | אומרים - אפר' חבס | 5 | |
| 707800 | 707800 | | | | | | | 6 | |
| 2029896 | 1081678 | 511358 | 268265 | 87942 | 44998 | 35655 | ס"ה הוצאות (6+3) | 7 | |
| | | | | | | | <u>מסכ'ה נהגות</u> | | |
| 162000 | 48000 | 42000 | 36000 | 24000 | 12000 | | ד"ר שביטול חוב קי"מ-מאכר וצ"א | 8 | |
| 114258 | 32150 | 44265 | 24320 | 8960 | 9560 | | השגחה ותכנון - סכ'נאליה (18%) | 9 | |
| 21834 | 21834 | | | | | | השגחה ותכנון - אפר' חבס (3%) | 10 | |
| 298092 | 101984 | 86248 | 60420 | 22960 | 16510 | | ס"ה מסכ'ה | 11 | |
| 2327988 | 1183662 | 597626 | 329585 | 120000 | 61558 | 35655 | ס"ה הוצאות ומסכ'ה נהגות (11+7) | 12 | |
| (15691) | (11522) | (3370) | (799) | | | | <u>היבטים שונים</u> | | |
| 2312297 | 1172140 | 594256 | 327786 | 120902 | 61558 | 35655 | סך הכל (12-13) | 14 | |
| 224400 | | | | | | | צ"א אומרים (לפי ה"מ) | 15 | |
| 150237 | | | | | | | אפר' חבס | 16 | |
| 2686920 | | | | | | | סך הכל | 17 | |

הוצאות (השגחה ותכנון) חבס (לפי ה"מ) (סכ'ה)

ח. סלבין
מהנדס יועץ
H. SLAVIN
CONSULTING ENGINEER

22.1.1962

לכבוד
משרד השיכון ✓

לכבוד
חברת רסקו

א.ב.,

(1) רצוף רשימת הציוד שבהתאם לחוזה ביננו צריך לעבור לרשות החברה ליצור בתים להרכבה "שבח".

(2) הרשימה כוללת תיאור ותיפקוד טכנולוגי של כל מכונה ומכונה.

(3) מחיר הציוד מסתכם לסך של 413.100 לירות פחות 30.000 לירות שקבלתי עד 1.1.62 (25.000 ממשרד השיכון 5000 מרסקו), ז"א הזכות שלי עבור הציוד ~~הוא~~ היא 383.100 לירות.

(4) הרשימה כוללת מכונות ציוד וחמר המיועדים באפן בטוח וישר לצרכי בית החרושת וזה בהתאם לחוזה.

(5) במידה וישתמשו בחמר ציוד או מיכון גרוס, אגיש כל פעם להנהלה חשבון מתאים.

(6) בתור יוצא מהכלל חשבתי עבור חמרים שקבלתי בעצמי מאמריקה עוד לפני כשנתיים היות ולפני מספר חודשים התקבלו עוד חמרים מסוג זה ע"י הזמנת משרד השיכון ולא היה רצוי שלאותם החמרים יהיה סטטוס חשבוני ~~הוא~~

מחוץ לזה יש לי בטחון גמור שהחמרים אלה דרושים לבית החרושת.

(7) רשימת הציוד והחמרים שהתקבלו ע"י הזמנת משרד השיכון מצורפת.

בכבוד רב,

ח. סלבין

ריכוז רשימת הציווד שעובר לרשות בית חרושת שבה

| המספר
ברשימה | פ
ר
ט
י
ם | מחיר
לירות | הדף |
|-----------------|--|---------------|-----|
| 29 ✓ | מסדר הספקת אגרגטים למרכז השקילה | 22.000 | 1 |
| 3 ✓ | מרכז לשקילת אגרגטים | 11.300 | 1 |
| 4 ✓ | אוטו משא עם הופך הידורולי להספקת התערובת למכ. בטון | 3.000 | 1 |
| 1 ✓ | מכונת בטון נוסעת 3x2x1 בטון | 60.000 | 1 |
| 2 ✓ | קונוריר הספקת בטון למשפך ויברציאובי | 6.300 | 2 |
| 19 ✓ | משפך ויברציאובי | 19.000 | 2 |
| 18 ✓ | תבנית ויברציאובית לשתי פלטות רצפה 7,5 מטר אורך | 41.500 | 2 |
| 24 ✓ | גוף פוגות לרצפה | 2.800 | 3 |
| 25 ✓ | מכשיר ליצור גופי פוגות | 500 | 3 |
| 34 ✓ | מסדר פנומתי ל-15 צילינדרים אויר | 9.400 | 3 |
| 35 ✓ | צילינדרים אויר נוספים | 3.500 | 4 |
| 30 ✓ | 2 עגלות לגופי חללים של רצפה | 11.700 | 4 |
| 20 ✓ | תבנית יציקה ויברציאובית לשני קירות 8,5 מטר אורך | 6.700 | 4 |
| 31 ✓ | 2 עגלות לגופי חללים לקיר (עליונות) | 6.000 | 5 |
| 32 ✓ | 1 עגלת חללים לקיר (תחתונה) | 5.800 | 5 |
| 22, 37, 38 | תבנית ליציקת 4 פלטות בטון למחיצות 7,5 מטר אורך | 6.000 | 5 |
| 21, 23, 36, 39 | חלקים בודדים לצנין תבניות יציקה נוספות | 10.800 | 6 |
| 16, 33 ✓ | מסדר השחזה פלטות בטון | 5.000 | 6 |
| 9 ✓ | מנוף יצור 10 טון | 12.300 | 6 |
| 10 ✓ | מנוף "מונוריל" 2 טון | 6.000 | 7 |
| 45, 46 | מנוף הקמת בנינים 10 טון | 5.000 | 7 |
| 6 ✓ | מנוף על גלגלי גומי לורין 30 טונות-מטר | 36.000 | 8 |
| 44, 51, 58 | מנופי סעבוב | 3.200 | 8 |
| 5 ✓ | מזלג קלרק של 2 טון | 8.000 | 8 |
| 7 ✓ | אוטו משא, דימבור | 15.000 | 9 |
| 8 ✓ | 2 מרילרים רוזרס 40 טון | 20.000 | 9 |
| 11 ✓ | דיזל גברטור 250 קו"א | 27.000 | 9 |
| 14 ✓ | לוח חשמל לחלוקה ראשית 200 קו"א | 2.000 | 10 |
| 15 ✓ | 4 מזיזים להנעת ויברטורים | 5.600 | 10 |
| 12 ✓ | 2 ברכות לקיטור חימום התבניות 0,2 ק"ג/ס"מ | 2.000 | 10 |
| 13 ✓ | משאבת ווקום 15 כ"ס | 1.500 | 10 |
| 50 ✓ | מכונת בטון 200 ליטר | 1.000 | 11 |
| 59 ✓ | פטיש לבטוי בטון | 300 | 11 |
| 26 ✓ | פרס הידורולי ליצור קונסטרוקציות | 2.200 | 11 |
| 28 ✓ | שולחן סכינים לרתוך שלדי גופי תבניות | 2.400 | 11 |
| 27 ✓ | יצולים שונים | 2.000 | 11 |
| 40, 41, 43, 52 | חלקי מכונות טכנולוגיות | 4.000 | 12 |
| 53, 54, 56, 57 | תיכשור לבנין מכונות טכנולוגיות | 2.500 | 12 |
| 48, 60 | מכשירים | 1.200 | 12 |
| 47, 49 | חמרים | 7.600 | 12 |
| - | שרטוטים | 15.000 | 13 |
| | ב ס " ה | 413.100 | |
| | פחות סך שקבלת עד 1.1.62 | | |
| | ממסד השיכון | 25.000 | |
| | מרסקו | 5.000 | |
| | | 30.000 | |
| | | 373.100 | |
| | | ===== | |

מסדר הספקת אגרגטים למרכז השקילה מספר ברשימה 29

תיאור: על קרון עם יכולת העמסה של 15 טון מורכב בגבה מתאים סילו לחצץ.
על קרון דומה שני מורכב סילו לזיפזיף.
על 4 קרונות עם יכולת העמסה של 3 טון כ"א מורכבים בגבה מתאים 2 נפות, אחת לחצץ והשניה לזיפזיף, עם מוטורים של 3 כ"ס להנעתם.
על כל קרון מורכב קונויר כ-10 מטר אורך 60 ס"מ רוחב עם מוטור 3 כ"ס עם גירבוקס מתאים להספקת החצץ והזיפזיף מהסילו לנפות.

הפעולה
הטכנולוגית

קבלת אגרגטים מההחסנה ע"י כף מתרוממת מורכבת על טרקטור והספקתם למרכז השקילה אחרי בפורי מתאים.

המצב ליום
1.1.1962
על הקרונות מורכבים עמודי הסילו.
קונויר אחד מוכן מחוץ להנעה וגלילים, ~~מתקנת לזיפזיף~~ השני דורש הרמת חגורה וחטר מוטור וגירבוקס.
הנפות מוכנות להרכבה.
הקרונות עם עמודים וקורות מוכנות לקבלת הנפות.

המחיר: 22.000.- לירות.

מרכז ושקילת האגרגטים מספר ברשימה 3

תיאור: 3 קומפלקסים לשקילת האגרגטים וצמנט עד 5000 (כ"א) מורכבים על קונסטרוקציה של עמודים וקורות בגבה המתאים המאפשרת את קבלת האגרגטים אחרי הנפוי לארגזי השקילה והעמסת התערובת השקולה לאוטו להובלה למכונת בסון.

הפעולה
הטכנולוגית

שקילת האגרגטים חצץ זיפזיף וצמנט לתערובות של 1 מ3 בשביל מכונת הבסון.

המצב ליום
1.1.1962
הקונסטרוקציה וסדורי שקילה מוכנים.
פתיחת הארגזים להעמסת האוטו זמנית במנופי יד שיוחלפו להפעלה פנומטית. לא מוכנים שום סידורים לצמנט.

המחיר: 11.300.- לירות.

אוטו משא פורד עם הופך הידרולי מספר ברשימה 4

התיאור: אוטו משא לעמס של 3 טון עם הופך הידרולי.

הפעולה
הטכנולוגית

לקבל את התערובת של האגרגטים וצמנט ולהוביל אותה עד לכף קבלה של מכונת בסון ובעזרת ההופך ההידרולי להכניס את האגרגטים לכף של מכונת בסון.

המצב ליום
1.1.1962
עבר בהובלת פועלים לעבודה במשך שנהיים. עבודתו הופסקה בשנת 1954 אחרי בדיקה במוסך. הצמיגים במצב די טוב.
המחיר כולל סך של 1000 לירות עבור בדיקת האוטו והכנתו לפעולה. תיקוני צבע וקניית סוללה.

המחיר: 3000.- לירות אחרי בדיקה.
או 2000.- לירות כמו שהוא.

מכונת בסון נוסעת עם תוף קפול לשתי תערובות של 1 מ3 כ"א

מספר ברשימה 1

תאור: מכונת בסון של 4 בנסום עם דיזל בודה של 150 כ"ס ועם הפעלה הידרולית עם שרשרות לנסיעה של 1,5 קילומטר לשעה עם ברכת מים נוספת של 1000 גלון משקל כללי בערך 25 טון.

500000 000.00 500000.

[illegible]

amr 1000.00 1000.00

מאפשרים שנוי רצוי בממדי גופי הבטון.
גוף בינים וגופי הזזה מכוסים בפח משני הצדדים בכדי לאפשר
את אשפרת הבטון בחימום של קטור בלחץ של 0,2 ק"ג/ס"מ².

לקבל את הויברציות והמשפך הויברציאוי ולמסור אותם לבטון
בשביל יציקת 2 פלסות בטון עד 8 מטר אורך, 2,8 מטר רוחב או
גובה.
לחמם את הבטון עד 85⁰ בזמן האשפרה.
לאפשר קביעת פתחים חלונות ודלתות בפלסות הבטון.

הפעולה

המצב ליום
1.1.1962

הבסיס מוכן.
מסגרת התחתונה ומסגרת חוץ מוכנים.
קורה עליונה עם המופות הקוביות מוכנה.
שלד גוף בינים עם קובוסים תחתונים ועליונים מוכן.
שלד גוף הזזה אחד מוכן ומכוון לתנועה לכסוי פח ולקביעת
גוף הפוגות.
שלד גוף הזזה שני באיסוף על שולחן הסכיבים.
ארגונים וצנורות הזזה לגוף שני מוכנים אבל לא נקבעו במסגרת
חוץ. תחתית אחת קבועה השניה התחילו בחריטת הקובוסים.
סגרי האורך לא מוכנים.
כסוי הפח גמרו בכל הסידורים הדרושים להתחלת עבודה זו.

41,500.- לירות.

מחיר

גוף פוגות לרצפה מספר לפי הרשימה 24

בקונסטרוקציה של שני [10 מרותכים 6 זרועות של S באורך
של 1200 מ"מ כ"א.
זרועות אילו מותאמות:

תיאור

- 2 x 6 ברגים לקשירת הגופים המרחביים של הזיון;
- קונפוגורציה של פוגות הרצויה לאורך התבנית;
- השענת גוף הפוגות על גופי הזזה ובינים;
- צנור מיוחד באורך של כ-3 מטר עם 13 בוקסות;
להשענת הקצה של 26 צנורות חללים.

העברת והכנסת לתוך התבניות הגופים המרחביים של הזיון
והחזקתם בזמן היציקה החזקת קצי צנורות החללים.
יציקת הפוגות.
החזקת פתחים ביציקה אם יהיה צורך בדבר.

הפעולה
הטכנולוגית

גמור מחוץ לקביעת צנורא של 13 בוקסות.

המצב ליום
1.1.1961

2,800.- לירות.

המחיר

מכשיר ליצור גופי פוגות נוספים מס. לפי הרשימה 25

הדיקנות המופרות הדרושה לבנין גוף הפוגות דורשת מכשיר
מיוחד שמאפשר להבטיח שכל אחד מגופי הפוגות יהיה העתק
מדויק של השני.
מכשיר זה מאפשר את הכנת גופי הפוגות וקביעתם בתוך התבנית
לשם רתוך להחזקת הזרועות ולשם קביעת הקו של 3.000 +
בשלוני הגופים לפני הכסוי בפח.

תיאור

לא כולל I 10" 500.- לירות.

מחיר

מסדר פנומתי מספר לפי הרשימה 34

קונסטרוקציה באורך של 7,5 מטר הבנויה מ-6 עמודים של צנור
10" קשורים לקורות של C
2 דחפנים בנויים מ-C של 7,5 מטר אורך יכולים לזוז עד 250
מ"מ על מכוונות מיוחדות הקשורות לעמודים.
10 צילינדרים פנומתיים של 4" מפעילים את הדחפנים שמצדם
בעזרת פלסות מיוחדות מפעילים את 10 צנורות הזזה 6"

תיאור

and ~ 0.003 in K^{eff} .

4307 - .008.2 drop.

[illegible]

המרותכים בשלד של גוף הזזה של התבנית.
מחוץ לזה עוד 5 צילינדרים פנומתיים "4 סוגרים בעזרת פיגים
נגדיים את הקונוסים של המשפך.

הפעולה
הטכנולוגית

פתיחת התבנית ע"י הזזה גוף צד לשם רחיצה והכנסת גופים
מרחבים על ברזל הזיון.
סגירת התבנית עד לממדים הרצויים של יציקת פלסת בטון.
החזקת גוף הצד בזמן הויברציה.
פתיחת התבנית לשם הוצאת פלסת הבטון בגמר האשפורה.

המצב ליום
1.1.1962

הקונסטרוקציה גמורה.
פלסות דחיפה של צנורות הזזה גמורים.
התחילו בקביעת 10 צילינדרים פנומתיים לדחיפה.

המחיר
9,400.- לירות.

צילינדרים אויר מספר לפי הרשימה 35

מחוץ ל-10 צילינדרים שהורכבו יש עוד 5 צילינדרים קומפלקט
בשביל סגר המשפך וחלקים לעוד 25 צילינדרים כולל חלקים
מגמי ומלאים שהובאו מאמריקה.

מחיר
3,500.- לירות.

2 עגלות לחללי רצפה מס. לפי הרשימה 30

קונסטרוקציה בנויה מ-4 של 300 קשורה לבסיס כבד מאד למטה
ולמסגרת יותר קלה בחלק העליון.
מערכת שלמה של קשרים המאפשרים כוון מדויק של הקונסטרוקציה
משלימים את הטבנה.
4 גלגלים כבדים במיסבים מיוחדים מאפשרים את העברת העגלה
ממקום למקום.
מערכת של 52 חורים מדויקים בדימטר של 198 מ"מ.
מאפשרים את קביעת 26 גופי חללים באורך של 6 מטר.
בעזרת ביסוס גומי מיוחד המאפשרים את השענת תותבים מיוחדים
וכל זה בכדי לאפשר את עמידת העגלה בויברציות של היציקה.
מערכת שלמה של שנים חולצות מסודרים באופן מיוחד מאפשרת את
הוצאת צנורות החללים באפן הדרגתי מהבטון בעזרת 4 או יותר
צילינדרים פנומתיים "10 וששה של "4.
מערכת של קפיצים ומקבעים מחזירה את הצנורות למצב התחלתי של
פעולה.

תיאור

לקרב ולהכניס לתוך התבנית 26 חללים (באורך בבטון כ-3,8 מטר)
והשעינים בקצה הקדמי בתוך תותבים של גוף הפוגות.
להחזיק את החללים במצב נכון במשך כל היציקה.
להוציא את החללים בצורה הדרגתית מהבטון בגמר היציקה.
לחמם את פלסת הבטון מבפנים בזמן האשפורה.

הפעולה
הטכנולוגית

עגלה ראשונה גמורה בקונסטרוקציה החיצונית שלה.
הוכנו 26 תותבים.
6 גופי חללים במצב עבודה שונה.
מערכת שנים חולצות.
גופים של 4 צילינדרים "10.
צנור אחד לקפיצים.

המצב ליום
1.1.1962

בעגלה השניה גומרים את הקידוח של 4 ברזלי 300x
הכינו את המסגרת התחתונה.

מחיר
11,700.- לירות.

תבנית יציקה ויברציאונית לקורות מס. לפי הרשימה 20

תבנית דומה לזו של הרצפה אלא הבסיס שלה מסודר בצורה כזו
שמאפשר להכניס את צנורות החללים באופן מקביל לגבה של הקיר
ז"א דרך הבסיס שלה. אורך התבנית 8,5 מטר.

תיאור

הפעולה
הטכנולוגית

כמו בתבנית לרצפה, אלא, נתנה אפשרות לצקת חללים גם בכווני אורך וגם בכווני גובה כמו כן אפשר לצר פתחים לדלתות חלונות וכו' ופתחים בעבי הפלטה של בטון לדלתות וחלונות הזזה.

המצב ליום
1.1.1962

גמורה המסגרת החיצונית של 10 צנורות "16".
גמור הבסיס הבנוי מקורות "10" ו"10" עם פלטות מיוחדות המאפשרות לחללים לעבור את הבסיס מבלי להתנגש עם הבסיס כלעצמו.

מחיר 6,700.- לירות.

2 עגלות חללים עליונות לתבנית קיר מס. לפי הרשימה 31

תאור

עגלה בנויה ע"י 2 צנורות "16 מורכבים על בסיס של "10 מותאמת לבסיעה על פסים ברוחב 1300 ע"מ. ראש קונסטרוקטיבי מיוחד המעתיק את הסדור בעגלת החללים של הרצפה מאפשר להכניס להחזיק ולהוציא 2 גופי חללים של 6 מטר וזה באורך של הקיר. צילינדרים פנומתיים בותגים את הדחיפה הדרושה להוצאת החללים. סדור מיוחד מאפשר לקשור את סגרי האורך לעגלה ועל ידי זה מאפשר שבני אורך פלטת הבטון במשך דקות ספורות (בין יציקה ליציקה) סידור בוסף מאפשר לשני עגלות אילו לתרום בעזרת ווינצים את עגלת החללים התחתונה.

הפעולה
הטכנולוגית

לצור בתוך פלטת בטון של קיר 2 חללים בדיאמטר של 115 מ"מ חללים אילו יוצרים בתוך חלק עליון של הקיר קורה מחוללת בממדים של 400 מ"מ גבה 240 מ"מ רוחב. החלל העליון מיועד לאינסטלציה של החשמל. " התחתון " " " " " " " מחוץ לפעולות אלו משמשים העגלות בתור סידורי הרמה החזקה וקביעה של עגלת חללים תחתונה.

המצב ליום
1.1.1962

עגלה ראשונה גמורה לגמרי מחוץ לגופי חללים וסידורי הרמה של עגלה תחתונה.
בעגלה שניה גמורת והולכת מערכת הנסיעה, עמודי "16, ראש לצנורות חללים ככה שבגמר הגשמים אפשר להתחיל בהרכבתה.

המחיר 6,000.- לירות.

עגלת חללים תחתונה מס. לפי הרשימה 32

תיאור

3 ברזלי 300 הקשורים ביניהם במספצ מקומות בפלטות עבות, יוצרים את בסיס העגלה.
ברזל שטוח 100x15 באורך של 1 מטר יוצרים 72 תאים מדויקים מאד של 200x200 המשמשים לכוון, הכנסה, החזקה וקביעה של 72 גופי חללים ורטיקליים מתחת לקורה עליונה עד בסיס הקיר. סידור מיוחד של צנורות "10 מקושרים לבסיס מאפשרים הרמה, קביעה והורדה של עגלה זו בעזרת עגלות העליונות. סידור מיוחד מאפשר את ההוצאה הדרגתית של צנורות החללים וכמו כן נתנת אפשרות לא להכניס חללים במקומות המיועדים לחלונות ודלתות. הקונסטרוקציה מאפשרת גם יצור חללים בתוך הבטון לצרכי חלונות ודלתות הזזה.

הפעולה ייצור חללים ורטיקליים בקיר בזמן היציקה וכמו כן בשעת הצורך יצור חללים פנימיים לדלתות וחלונות.

המצב ליום 1.1.1962
העגלה כלעצמה מוכנה על כל 72 פתחים שלה וגלגלי הנסיעה מוכנים צנורות הרמה וקביעה אבל טרם הורכבו במקומם. נמצאים בקידוח 700 פלטות לכוון החללים.

המחיר 5,800.- לירות.

תבנית למחיצות מס. לפי הרשימה 22, 37, 38

תיאור

התבנית דומה בדרך כלל לתבנית רצפות באורך של 7,5 מטר. ההבדל הוא שסמקום 2 פלטות בטון מחוללות של 24 ס"מ עבי יוצקים מתבנית זו 4 פלטות בטון מלאות בעבי של 6 ס"מ ולכן יש בתבנית זו 2

that there are no other persons in the house at the time.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

Witness: I saw the person who was in the house at the time of the murder.

מנוף נוטע לורין 5 טון על 6 מטר 30 טונות
מספר לפי הרשימה 6

תיאור

מנוף של 3/4 מ"ט של לורין מורכב על מסגרת עומק 10 גלגלים
גומי עם דיזל בולינדר של 35 כ"ס להפעלת המנוף ומוטור
בנזין להסעתו.
עם זרוע מאלמנטים להרכבה עד 24 מטר אורך.

המצב ליום
1.1.1962

המנוף פורק לחלקים בשנת 1958 וקבל תקון כללי הכולל את
כל המערכת של הפעלה ובסיעה כולל החלפת מוטור בנזין להפעלה
על מוטור דיזל חדש של בולינדר ותקון כללי למוטור בנזין
להסעה.
מזמן זה עבד המנוף בחברת צנורות בהעמסת אוטומטית בצנורות
במשך שנת 1959, עד מאי 1960 ומזמן זה הוא לא עובד. יש
למנוף חלקים רובריים בסכום כ-500 לירות.

פעולה
טכנולוגית

הרכבת מנוף ההקמה (45) במקום הבנין
" הציוד הטכנולוגי.
פרוק והרכבה הציוד הטכנולוגי בזמן העבודה של בית חרושת
הספקת אגרגטים למסדר השקילה למקרה של קלקול בכף המדקטור.

המחיר

35,000.- לירות.
נוסף לזה עבור בקט של 1/2 מ"ט סך של 1,000.- לירות
בסה"כ 36,000.- לירות.

מנופים מצנורות 16" מספר לפי רשימה 44,51,58

תיאור

מנופים בנויים מצנורות 16" המסתובבים מסביב למרכז
הורטיקלי ע"י מנגנון מיוחד. ברזל I באורך הדרוש מאפשר
למרים וגלגלים מונעים להגיע לכל מקום דרוש ובגובה הדרוש.

פעולה

מנוף בגובה בערך של 7 מטר מורכב על אוטו משא עוזר להרכיב
את רשתות הזיון לגופים מרחביים של זיון.
מנוף בגובה כ-7 מטר ושני מנופים בגובה כ-5 מטר עוזרים לרתוך
הרשתות וגופים מרחביים במחלקת הזיון.
המנופים של 4-5 מטר עוזרים בהרכבת יחידות סניטריות
ואלמנטים של מורגות.

המצב ליום
1.1.62

סוכנים 2 צנורות 16" באורך של 7,3 מטר
" 4 " " 16" " " 3,3 מטר
12 מיסבי מרכז
11 קרוניות
4 גלגלי השענה (דרוש 8)
1 קומפלך סיבוב.

מחיר

3,200.- לירות.

מזלג 2 טון של קלרק לפי הרשימה מס. 5

תיאור

מזלג הרמה של 2 טון עם כף נוספת של 1/2 מ"ט להספקת אגרגטים
עם כל הטיפעול ההידרולי הדרוש.

פעולה
טכנולוגית

עזרה בתיקונים בציוד טכנולוגי.
פירוק והעברה למחסנים של ציוד הבתים כמו אמבטיות, ציוד
סניטרי וכו' במקרה של קלקול במרכז לשקילה או באוטו להובלת
אגרגטים. העברת אגרגטים ישר למכונת הבטון.

המצב ליום
1.1.1962

בקנה בשנת 1951 במשך השנים היה בעבודה כ-5 שנים.
יש לחשוב שבכל חודש עבד 10-20 שעות בעזרה בהרכבות.

המחיר

8,000.- לירות.

REPORT ON THE WORK OF THE COMMISSION FOR THE YEAR 1951
CHAPTER I - GENERAL

1. The Commission was established on 1 January 1951, in accordance with the provisions of the Convention on the High Seas, signed at Geneva on 29 April 1958. Its purpose is to study and report on the state of the high seas and to propose measures for their conservation and management.

2. The Commission has held three sessions to date, in 1951, 1952 and 1953. At each session, it has considered reports from its members and has adopted resolutions and recommendations.

3. The Commission has also conducted extensive research and has published several reports on the state of the high seas. These reports have provided valuable information on the distribution and abundance of marine resources and on the impact of human activities on the marine environment.

4. The Commission has also been active in promoting international cooperation and in organizing scientific expeditions to the high seas. These activities have helped to advance our knowledge of the marine environment and to ensure the sustainable use of its resources.

CHAPTER II - THE HIGH SEAS

1. The high seas are defined as those parts of the sea which are not under the sovereignty of any one State. They are the common heritage of all mankind and should be managed for the benefit of all.

2. The Commission has studied the state of the high seas and has found that there is a need for international measures to ensure their conservation and management. These measures should be based on scientific principles and should take into account the interests of all States.

3. The Commission has proposed several measures for the conservation and management of the high seas. These measures include the establishment of a system of international cooperation, the adoption of scientific principles, and the implementation of specific measures for the conservation of marine resources.

4. The Commission has also conducted extensive research and has published several reports on the state of the high seas. These reports have provided valuable information on the distribution and abundance of marine resources and on the impact of human activities on the marine environment.

CHAPTER III - THE COMMISSION

1. The Commission was established on 1 January 1951, in accordance with the provisions of the Convention on the High Seas, signed at Geneva on 29 April 1958. Its purpose is to study and report on the state of the high seas and to propose measures for their conservation and management.

2. The Commission has held three sessions to date, in 1951, 1952 and 1953. At each session, it has considered reports from its members and has adopted resolutions and recommendations.

3. The Commission has also conducted extensive research and has published several reports on the state of the high seas. These reports have provided valuable information on the distribution and abundance of marine resources and on the impact of human activities on the marine environment.

4. The Commission has also been active in promoting international cooperation and in organizing scientific expeditions to the high seas. These activities have helped to advance our knowledge of the marine environment and to ensure the sustainable use of its resources.

אוסו משא דימונד T מספר לפי הרשימה 7

תיאור אוטו עם דיזל 150 כ"ס היכול להוביל טרילר מעומס במשקל של 50 טון ברוטו במהירות של 25 קילומטר לשעה.

פעולה טכנולוגית להוביל את הטרילרים מעומסים בפלטות בטון של קירות ורצפות במשקל כ-30-35 טונות (משקל חצי דירה) מבית החרושת עד מקום הבנין.

המצב ליום 1.1.1962 הדימונט נרכש בשוויצריה בשנת 1951 ו⁸ הוכנס לעבודה עד שנת 1958. בשנה זו עשיתי בסיון למסור אותו לסולל בונה להובלת חצץ ואחרי חודשים של עבודה התברר שהמכונה לא בסדר. הכנסתי אותו לגרז והתחלנו בהחלפת מוטור אבל דבר אחרי דבר נעשה תקון יסודי גם במערכת הנסיעה הוכנס "בק-ווקס" חדש והרבה חלקים אחרים.

בגמר התיקון שנמשך יותר משנה הרצנו את המכונה כ-1000 קילומטר ומאותו הזמן היא לא עבדה יותר.

המחיר 15,000 לירות.

2 טרילרים רודזט על 24 גלגלים כ"א מס. לפי הרשימה 8

תיאור טרילר של 7 מטר אורך על 24 גלגלים שאפשר להעמיס אותו במשקל של 40 טון הגובה שלו כמטר אחד. העמסה בעזרת משטח עם 6-7 פלטות בטון. המשטח המעומס מורם ע"י דזקים הידרוליים.

הפעולה הטכנולוגית לקבל על עצמו להובלה מבית החרושת למקום השכון 6-7 פלטות הטכנולוגית בטון קבועים על משטח.

המצב ליום 1.1.1962 הטרילרים נרכשו ב-1952 בגרמניה ולא היו בעבודה, בודקו והוחלפו בהם טורים לחדשים בס"ה עם אילו שפוד נמצאים במחסן 24 בשנת 1958 נעשתה בהם בדיקה כללית לצרכי קבלת רשיון להובלה בדרכים.

הקונסטרוקציה הבנויה לא מתאימה עכשיו לשיטה החדשה של משטחי העמסה ויש לפרק אותה.

המחיר 2×10.000 לירות = 20,000 לירות.

דיזל-גנרטור 250 קו"א מספר לפי הרשימה 11

תיאור 2 דיזלים 130 כ"ס כל אחד קלטרק מס 18.000 מחוברים בעזרת "קלצים" לגנרטור של 400 וולט 3 פזות 250 קו"א עם מעורר מתאים על אותו הציר.

יש אפשרות לעבוד עם 2 הדיזלים ביחד או עם כל אחד לחוד תא חשמלי מיוחד עם מפסיקי זרם שמן מאפשר את חבור הגנרטור ויציאה תחת עמס עד 600 אמפר.

הדיזלים הגנרטור והתא מורכבים על נסיס משותף ולהרכבתו יש רק לקבוע מספר ברגים בבטון של הרצפה.

פעולה טכנולוגית לקבל את כל העמס של בית החרשת במשך 5 דקות במקרה של הפסקה בהספקת חברת החשמל במיוחד חשוב הדבר בזמן יציקה ויברציאונות. יציקה בלתי גמורה תעלה ביוקר רק ויכלה להפסיק את עבודת התבנית ומשפך ויברציאוני לזמן רב.

המצב ליום 1.1.1962 הדיזל גנרטור נרכש ישר מבית חרושת שיצר פלטות גבס והפסיק את עבודתו. דיזל אחד עבר 3000 שעות שני 5000 שעות.

עד שנת 1959 נמצאו הדיזלים בארגזים בשנה זו נפתחו פורקו בודקו ונמצאו שהם במצב טוב מאד, הוחלפו כל חלקי גומי פילטרים וכו' שמתקלקלים מהזמן כולל המסטרופים והדיזל גנרטור הועומס לעמס משא בעזרת התנגדות מים ע"י אנשי קלטרק תל-אביב.

בנה הנסיס מפרופילים משותף לדיזלים וגנרטור ותא חשמל.

המחיר 27,000 לירות.

UNITED STATES DEPARTMENT OF AGRICULTURE

1. The first of these is the fact that the total number of acres of land in the United States is approximately 2,000,000,000 acres. This is a very large area of land, and it is not possible to cultivate all of it. Therefore, it is necessary to select the best land for cultivation. This is done by the Government, and the best land is reserved for the use of the Government. The rest of the land is sold to private individuals, who then cultivate it. This is the way in which the land is managed in the United States.

UNITED STATES DEPARTMENT OF AGRICULTURE

2. The second of these is the fact that the total number of acres of land in the United States is approximately 2,000,000,000 acres. This is a very large area of land, and it is not possible to cultivate all of it. Therefore, it is necessary to select the best land for cultivation. This is done by the Government, and the best land is reserved for the use of the Government. The rest of the land is sold to private individuals, who then cultivate it. This is the way in which the land is managed in the United States.

UNITED STATES DEPARTMENT OF AGRICULTURE

3. The third of these is the fact that the total number of acres of land in the United States is approximately 2,000,000,000 acres. This is a very large area of land, and it is not possible to cultivate all of it. Therefore, it is necessary to select the best land for cultivation. This is done by the Government, and the best land is reserved for the use of the Government. The rest of the land is sold to private individuals, who then cultivate it. This is the way in which the land is managed in the United States.

לוח חשמל ראשי לחלוקה 400 אמפר 3 פזות 380 וולט

מספר לפי הרשימה 14

| | |
|---|-------|
| לוח חשמל ראשי לחלוקה בשביל הספקה של 200 קו"א | תיאור |
| מעגל הכניסה מפסיק זרם 3×400 אמפר עם ביטחונות מחברת החשמל | |
| " " מדיזל גנרטור ישר על הפסים | |
| " הקומפרטורים מפסיק זרם 3×200 אמפר | |
| " " הויברציה " " 3×200 | |
| " " המנופים " " 3×100 | |
| " " המשאבות " " 3×50 | |
| " " המאור " " 3×30 | |
| " " רזרבי " " 3×30 | |

חלוקת הספקת החשמל מחברת החשמל ומדיזל גנרטור
פעולה טכנולוגית

מוכן לעבודה יש רק להזמין מאמריקה את הטבטיחים.
המצב ליום 1.1.1962

המחיר 2000 לירות.

4 מזיזים להנעת מוטורים עד 150 כ"ס מט. לפי הרשימה 15

| | |
|--|-----------------|
| מזיזים לרוטור של מוטורים 3 פזות, עד 150 כ"ס בתונים בתוך
שמן עם הנעת יד. | תיאור |
| הנעת המוטורים של הויברטורים המורכבים על המשפך הויברציאונני. | פעולה טכנולוגית |
| $4 \times 1400 = 5600$ לירות. | המחיר |

2 ברכות לקיטור חימום בלחץ של 0,2 ק"ג/ס"מ

מספר לפי הרשימה 12

| | |
|--|--------------------|
| 2 ברכות בדיאמטר 1100 מ"ר ובאורך 2400 מורכבים על בסיס עם
פתחי כניסה ומערכת של ברזים מ 3" עד 1". | תיאור |
| הקיטור שנוצר בוודים הוא בלחץ של 6 ק"ג/ס"מ בעזרת מכשיר
להורדת לחץ משנים את הלחץ ל 0,2 ק"ג/ס"מ הברכות מרכזות את
הקיטור בלחץ זה ומשמשות מרכז ההספקה לתבניות.
במקרה של קלקול אפשר לעבוד עם ברכה אחת ולתקן את השניה. | פעולה |
| מוכן לפעולה אחרי צביעה ובירור. | המצב ליום 1.1.1962 |
| 2000 לירות. | המחיר |

משאבת ווקום מספר לפי הרשימה 13

| | |
|---|-------------------|
| משאבה לוקום תעשיתית עם מוטור של 15 כ"ס בנויה על פלטה
היצרן נש. | תיאור |
| מיועדת למרימי ווקום לאלמנטים קטנים שיצקו באופן הורייזונטלי
כמו מתאצות במחסן חדר מדרגות, תא סניטרי וכו'. | פעולה טכנולוגית |
| דורשת פירוק וניקוי היות ולא עבדו איתה כבר 4-5 שנים מגמר
הבסיונות את פלשות ווקום. עבדה בסדר בזמן בסיונות אלו. | מצב ליום 1.1.1962 |
| 1500 לירות. | מחיר |

מכונת בטון 200 ליטר מספר לפי רשימה 50

| | |
|---|--------------------|
| מכונת בטון מטיפוס של סיר ל-200 ליטר שמובעת ע"י מוטור חשמלי של 3 כ"ס. | תיאור |
| מכונת בטון של המעבדה בשביל קביעת תערובות שונות ביחס לארגמים מלא ומים בכדי לקבוע בין השאר גם את הנזילות הויברציאונת. | הפעולה הטכנולוגית |
| משומשת במצב עבודה. | המצב ליום 1.1.1962 |
| 1000 לירות. | המחיר |

מכשיר לנסוי בטון בנסיון לא דסטרוקטיבי מס. לפי הרשימה 59

| | |
|---|---------------|
| פטיש לנסוי בטון מס' 2 תוצרת שמיד בזל שויצריה. | תיאור |
| לקבוע את חזק הבטון במקומות שונים של פלטות מבלי לגרום להם נזק. | שמוש טכנולוגי |
| 300 לירות. | המחיר |

פרס הידרולי לישור קונסטרוקציות מספר לפי הרשימה 26

| | |
|---|--------------------|
| פרס לישור חלקי קונסטרוקציה עד ל-200 טון לחץ בנוי מפרופילים כבדים עם אפשרות של שנוי גבה מ-20 ס"מ עד ל-1.5 מטר עם מנוף יד להרמת קורות השענה וצילינדר הידרולי עד 80 טון. | תיאור |
| ישור פרופילים כבדים בשביל בנין ותיקון תבניות וקונסטרוקציות קשורות איתם. | פעולה טכנולוגית |
| מוכן לפעולה עם רכישת משאב יד הידרולית להפעלתו. | המצב ליום 1.1.1962 |
| 2200 לירות. | מחיר |

שולחן סכינים מספר לפי הרשימה 28

| | |
|---|--------------------|
| שולחן בנוי מברזל I בגודל של 10 מטר א 3 השולחן מצויד בסידור למתיחת חוטי פלדה לביקורת הקו הישר של השולחן. אא 11 סכינים בנויים בידקנות מברזל זווית ומכוונים לפי חוטי פלדה מבטיחים את הקו הישר של השולחן בדיקנות 1 מ"מ. ששה קורות עם ברגים 1 1/2 מקשרים את הקונסטרוקציה לשולחן. | תיאור |
| מקום לאיסוף וריתוך שלדי התבניות. הקו הישר של הסכינים מאפשר ביקורת מתמדת של הקווים הישרים של השלד שינויים ומתעקמים בזמן הרתוף. | הפעולה הטכנולוגית |
| קורות עם ברגים של 1 1/2 לא מאפשרים את התעקמות הקונסטרוקציה מהפרטי רתוף קטנים ואינם לבאים למרות כל ההשתדלות לספק חום של רתוף במקומות המביאים לדפורמציות בכוון מנוגד. | |
| למצא בעבודה ובווק לפני מספר שבועות. | המצב ליום 1.1.1962 |
| 2400 לירות. | המחיר |

יצולים מספר לפי הרשימה 27

| | |
|---|------------|
| יצול לסיבוב שלדי התבניות בזמן הרתוף המחיר | 800 לירות |
| יצול להרמת והעברת פח לכסוי תבניות | 200 " |
| חלקים ליצול היצור והקמה מיוחד לא נחשב | 1000 " |
| במחיר: 2x300 | 2000 לירות |
| בס"ה | |

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

SECRET 1945-1946, 1947, 1948, 1949, 1950

חלקי מיכון מספר לפי הרשימה 40, 41, 43, 52

| | |
|-------------------------------|--|
| לבנין מכונות לתהליך הטכנולוגי | |
| 40 | 2 גירבוקסים עם מוטורים 3 כ"ס ומעצורים
מבנטיים $2 \times 750 =$
(בשביל הסעת עגלות הרוחב של מנופי יצור
והקמה) |
| 41 | 1 גירבוקס עם מוטור 7,5 כ"ס להסעת עגלת
טרנזיט |
| 43 | 1 קרון 15 טון לעגלת טרנזיט |
| 52 | צילינדר הידורולי "5" 5 נסוי כח משיכה של
גופי חללים |
| 1500 לירות | |
| " 500 | |
| " 1000 | |
| " 1000 | |
| 4000 לירות | בס"ה |

תיכשור מספר לפי הרשימה 53, 54, 56, 57

| | |
|------------------|--|
| 53 | מכשיר לקידוח לפי מודל 215 |
| 54 | מכשירי סימון וקידוח לעגלת הרצפות |
| 56 | מכשירים לרתוך קונוסים במשפך |
| 57 | סרגלי סימון
מקודים לפינים של קונוסים
מכשירי סימון וקידוח לעגלת הרצפות
שולחן בנין רשתות זיון לדוגמא |
| 300 לירות | |
| " 200 | |
| " 200 | |
| " 300 | |
| " 500 | |
| " 500 | |
| " 1000 | |
| 2500 לירות | |

מכשירים מספר לפי הרשימה 48, 60

| | |
|------------|------------------------------------|
| 48 | מהדק פנומתי |
| 48 | 2 אתי חפירה אמריקאים לבורות עגולים |
| 60 | 2 ברכות ערוב וצביעה |
| 60 | 4 קומפלק של אקדוחי צביעה |
| 100 לירות | |
| " 100 | |
| " 500 | |
| " 500 | |
| 1200 לירות | |

חמרים מספר לפי הרשימה 47, 49

הערה: בדרך כלל לא הוכנסו לרשימה שום חמרים. חומרים אלו הוכנסו היות
ויש עוד חמרים מסוג זה שהוזמנו ע"י משרד השיכון.

| | | |
|--|------|------------|
| 500 מטר דקוויל קומפלקט פסים אדנים ופלסות
וברגי חבור משקל של בערך 26 ק"ג מטר בס"ה
כ-13 טון | (47) | 6000 לירות |
| חמרים מאטריקה:
צנור בלי תפר $\emptyset 195/170$ - 57 ק"ג/מטר
8 מטר 40 לירות בשביל
עגלות גופי החללים | (49) | 300 לירות |
| צנור בלי תפר 115/96 - 40 ק"ג מטר
35 מטר 20 | (49) | 700 " |
| 45 סכיני מים לרחיצת תבניות 8, 14 | " | 300 " |
| 70 טבעות גומי $6\frac{1}{2} \times 7$ | " | 100 " |
| חצי עגולים לפוגות $1\frac{1}{2} \times 1$, $3/8$, $3/4$, $2\frac{1}{4} \times 1\frac{1}{8}$ | " | 200 " |
| | | 7600 לירות |

TELEF. 066888 066888 066888 066888 066888

(Insert name, title, address and other data)

СЕРГЕЙ СЕРГЕЕВИЧ ДАВЫДОВ

שרטוטים של ציוד טכנולוגי שהוכנו במשך שלוש השנים האחרונות

ת ב נ י ת

| | | |
|---------------|--|------|
| ת"ק 3/1 | מסגרת תחתונה תבנית רצפה | (1) |
| " 31/1 | " " " קיר | (2) |
| " 3/2 | " עליונה תבניות רצפה וקיר | (3) |
| " 3/3 | תבנית למחיצות | (4) |
| " 3/5 | תחתית לתבנית רצפה | (5) |
| " 31/5 | " " " קיר | (6) |
| " 3/6 | גוף צד לתבנית רצפה | (7) |
| " 31/6 | " " " " קיר | (8) |
| " 3/7 | גוף בינים לתבנית רצפה | (9) |
| " 31/7 | " " " " קיר | (10) |
| " 3/8 | סגר האורך " רצפה | (11) |
| " 31/8 | " " " " קיר | (12) |
| " 3/9 | מסדר להפעלה פנומית מס' 1 | (13) |
| " " " " " " 2 | " " " " " " 2 | (14) |
| " 3/11 | בסיס תבנית לרצפה | (15) |
| " 3/12 | גוף הפוגות לרצפה | (16) |
| " 3/13 | חלונות | (17) |
| " | קונוסים | (18) |
| " | צילינדרים פנומתיים | (19) |
| | תבניות מיוחדות לחדר מדרגות ותא סביטרי. | (20) |

עגלות חללים

| | | | |
|-------------------|-----|----|------|
| עגלת חללי רצפה | 24 | תק | (21) |
| " " קיר עליונה | 241 | " | (22) |
| " " תחתונה | 242 | " | (23) |
| " תצנית מחיצות | 243 | " | (24) |
| עגלת בקורת ופירוק | 56 | " | (25) |

מ נ ר פ י ם

| | | | | |
|---|---------------|----|-----|------|
| 1 | מנוף יצוק מס' | 29 | תיק | (26) |
| 2 | " " " | 30 | " | (27) |
| | מנופי סיבוב | 19 | " | (28) |
| | יצול היצור | 32 | " | (29) |

ב ט ו ג

| | | | |
|---|------|-----|------|
| החסנת רשתות ברזל זיון | 10 | תיק | (30) |
| מחלקת ברזל זיון | 11 | " | (31) |
| הובלת רשתות זיון | 11/1 | " | (32) |
| עגלות רשתות זיון איסוף ורתוך אחמים | 15 | " | (33) |
| מחסנים לגופים מרחביים של זיון | 28 | " | (34) |
| מערכת עזר לרתוך חלקים בגוף מרחבי של זיון | 27 | " | (35) |
| סדור נסיעה לנפוי וחטיפת אגרגטים למרכז שקילה | 07 | " | (36) |

עבודות גמר

| | | | | |
|----|---|-----|-------|------------------------------|
| 37 | (| תיק | 61/11 | עגלת השחזה ל-4 פלסות בסון |
| 38 | (| " | 61/1 | מסור השחזה ל-4 פלסות " |
| 39 | (| " | 58 | החסנה ורטיקלית של פלסות בסון |
| 40 | (| " | 67 | קביעת פלסות לעבודות גמר |
| 41 | (| " | 76 | משטח טרנספורט |

72
בהתאם לחוזה שנערך בין הממשלה ומהנדס ח. סלבין להקמת חברה
"שבח" נקבע שתוקם ועדה מומחים אשר תעריך את הציוד שיועבר ע"י
המהנדס סלבין לחברה הנ"ל.

הנהלת החברה שהוקמה - החליטה על העקרונות לפיהן יוערך הציוד
כדלקמן:

- (א) ציוד וכלי עבודה השייכים למר סלבין ובאם יועברו לחברה - לפי
~~מחירי השוק~~ *מחירי* *השוק*
- (ב) ציוד שנרכש ע"י מר סלבין במשך השנים 1960-64 בכספי משרד השכונ
לפי מחירי הקניה בזמן קנייתם.
- (ג) ציוד שנרכש בחו"ל כנ"ל בסעיף ב'.
- (ד) ציוד שתוכנן ונבנה ע"י מר סלבין יקבע מחירו לפי:
1. חומר לפי מחירי הקניה או השוק בזמן הקניה.
 2. שכר עבודה בהתאם לכרטיסיות ורשום של מר סלבין.
על המומחים יהיה לקבוע מחיר לשעה עבודה לסוגים שונים, כולל
שימוש בציוד, הוצאות כלליות כגון: הנהלת עבודה, שכר דירה,
חשמל, מסים תנאים סוציאליים וכו'.
 3. הוצאות תכנון פקוח על ביצוע העבודה יחושבו בנפרד בהתאם
להעריף המקובל.
- (ה) באשר לעבודות הקשורות בתכנון פקוח והקמת המבנים למפעל החדש,
פתוח השטח, וכו' תעשה הערכה בנפרד.

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED

12. DATE PAID: FEB 27 1968 OR DATE PAID: MAR 1 1968

Ma / IT

-





THE "SLAVIN SYSTEM"

FOR MASS FABRICATION OF REINFORCED CONCRETE MULTI-STOREY HOUSES

1. General.

This system, the outcome of extensive research, presents several major advantages over other systems generally used in the construction of large housing projects.

The basic concept of the system is the fabrication of large elements (with a view to reducing the number of joints and erection operations to a minimum) produced by simple machinery, whose handling should not present difficult problems anywhere.

Through the complete industrialisation of the production, the elimination of deformations in fabricated components and simplification of the erection process, the "Slavin system", used on projects of appropriate size, should result in marked economical advantages and reduce the construction period to an unparalleled minimum.

2. Proposal.

This firm offers for sale either the know-how only or a complete package, i.e. a factory in operation. To suit the widest possible range of requirements, 6 alternatives are offered, each such alternative representing a phase of a complete factory. Each such stage is conceived to cope with a certain line of production and to be easily incorporated in a more complete factory, should an expansion be desired at a later date. The six above-mentioned alternatives and their approximate prices are tabulated on the sheet as over.

3. Feasibility.

In recent years, prefabrication of houses, particularly where large housing schemes are concerned, is being adopted by an ever increasing number of countries, be it for reasons of speedy erection, scarcity of skilled man-power, the achievement of a standard, factory-controlled finished product or a combination thereof.

In most countries, the share of prefabricated construction, related to the general dollar value of building works, is not large enough to warrant anxiety over workmen being deprived of a substantial number of openings in the building industry; in any case, in countries undergoing a process of industrialisation, there is no reason why the building industry should be singled out and prevented from following a development process not dissimilar to that of many other industries.

One of the main features of the "Slavin system" is the very short period of time required to produce a complete block of flats. When components are brought on site, assembly is carried out in a chain process by specialised teams, each team repeating the same part of work, flat after flat. In this manner, a complete cycle of operations required to complete one block of 40 3-roomed flats is roughly 7-8 weeks, a period of time which undoubtedly can be improved, as workmen gain experience by performing repetitive operations.

In addition to this extremely short time, one can realise a serious saving in labour costs, as indicated hereinafter in "Computation of Labour per Unit of Floor Area".

The Organisation Cost Sheets enclosed are back-up sheets for the above computation. We have further analysed total costs (based on running and investment expenses detailed in back-up sheets enclosed) which would indicate the following:

The investment in a factory required to produce 1000 flats of good standard per year, in running expenses, materials royalties and overheads, can be amortized in 7 years, by receiving payment of \$47.50 per sq.m. of built area. This price is based on certain assumptions detailed in the back-up sheets and can be adjusted, by simple computation, where applicable.

At the expiration of 7 years, the factory would have reached its full production capacity and would probably be of greater sale value than its initial cost.

ESTIMATED INVESTMENT

| | |
|-------------------------------|---------------------|
| Building | ₹ 550,000 |
| Plant | ₹ 1,330,000 |
| Plant Assembly & Installation | ₹ 250,000 |
| Running-in Expenses | ₹ 70,000 |
| Land | <u>unconsidered</u> |
| TOTAL | ₹ 2,200,000 |

BREAKUP OF PLANT COSTS.

| | |
|---|-----------------------------|
| 15 forms | ₹ 500,000 |
| * 5 cranes (10 tons) | ₹ 170,000 |
| Concrete Plant | ₹ 230,000 |
| Electrical, water, steam
& compressed air facilities | ₹ 170,000 |
| Reinforcement Dpt. Plant | ₹ 100,000 |
| Other plant: Grinding, Finishing
** Transport | ₹ 160,000 |
| TOTAL | <u>₹ 1,330,000</u>
===== |

* Suitable up to 6 storey houses

** 4 semi-trailers with 2 prime movers

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

1911-12

BREAKDOWN OF UNSKILLED LABOUR FORCE.

1. Concreting.

| | | |
|--|----|----|
| Concrete Plant | 3 | |
| Hauling | 2 | |
| Fours | 3 | |
| Handling of forms. fixing reinforcement mesh, lifting of elements from forms | 17 | |
| Shift 1 | 25 | |
| Shift 2 | 25 | |
| Spare men, in-between shifts | 10 | |
| Total, concreting works | | 60 |

2. Reinforcement and Inserts

2 shifts x 20 40

3. Grinding, Finishing, Electrical & Mechanical
Installations, Repairs, Final Checks

2 shifts x 20 40

4. Transport & Erections

50

TOTAL

200 men

1945

1946

1947

1948

1949

1950

1951

1952

1953

1954

1955

TOTAL COST COMPUTATION

considering 1000 flats/year production.

This is an approximate cost computation based on running and other costs as detailed in backup sheets and considering that the investment in the factory must be amortized by producing 7000 flats.

| | | | | |
|----|--|--|---|----------|
| 1) | Amortization of complete factory costs | $\frac{\$ 2,200,000}{7000 \text{ flats}}$ | = | \$ 314 |
| 2) | Running expenses | $\frac{\$ 240}{1000 \text{ flats}}$ | = | \$ 240 |
| 3) | Labour Costs | $\frac{\$ 60,000 \times 12m. \times 8 y.}{7000}$ | = | \$ 823 |
| 4) | Materials | | | \$ 1750 |
| 5) | Royalties | | | \$ 200 |
| | TOTAL | | | \$ 3,327 |

$$\frac{\$ 3,327}{70 \text{ sq.m.}} = \$ 47,50 / \text{sq.m.}$$

COMPUTATION OF LABOUR

PER UNIT OF (BUILT) FLOOR AREA

Note: See 'organisation' breakup.

Assumed: Desired production - 1000 flats of 70 sq.m./year

Manpower, including overheads: 250 men.

$$\frac{250 \text{ men} \times 300 \text{ days}}{1000 \text{ flats} \times 70 \text{ sq.m.}} = 7.5 \text{ say } 8 \text{ man-hours/sq.m.}$$

as against:

For conventional buildings 25-30 man-hours/sq.m.

Other prefabrication systems 12-18 man-hours/sq.m.

A fairly accurate labour cost estimate of finished flats per unit of floor area is possible using the above data. However, as rates vary from country to country, computations should be adjusted using actual prevailing rates. Taking for example rates prevailing in Venezuela, the labour cost per square meter of finished flats can be computed as follows:-

1) Unskilled labour:

$$\frac{200 \text{ men} \times 300 \text{ days} \times 0.80 \text{ \$/h.}}{1000 \text{ flats} \times 70 \text{ sq.m.}} = 6.85 \text{ \$} - 50\%$$

2) Add for 11 supervisors 1.74 \$ - 12.7%

3) Add for 30 operators and mechanics 2.95 \$ - 21.5%

4) Add for Technical & Administration Staff 2.16 \$ - 15.8%

13.70\$/m² 100%

By substituting actual rates, the approximate labour cost can easily be computed.

COST OF MATERIALS

=====

FOR A 70 SQ. M. FLAT

| | | | |
|---------------|--------------------------|---|-----------------|
| Concrete | 35 m ³ x ₦ 15 | = | ₦ 525 |
| Rebars | 1,100 kg. x ₦ 120 | = | ₦ 132 |
| Paint | | = | ₦ 100 |
| Flooring | | = | ₦ 120 |
| Windows | 3 sq. m. x ₦ 20 | = | ₦ 60 |
| Doors | 7 x ₦ 30 | = | ₦ 210 |
| Electrical | | = | ₦ 100 |
| Plumbing | | = | ₦ 250 |
| Cupboards | | = | ₦ 200 |
| Miscellaneous | | = | ₦ 100 |
| Total | | | ₦1797 say ₦1800 |

YEARLY RUNNING EXPENSES

| Details | Assumed Costs in Dollars | | |
|--|--------------------------|--------|----------------------------|
| | Plant | Site | TOTAL |
| 1. Electricity, 12000 KW | 2,000 | 400 | 2,400 |
| 2. Water 5000 M.C. | | | 600 |
| 3. Fuel (steam generators, trailers, compressors, vehicles) | | | 30,000 |
| 4. Plant maintenance (spare parts) | | | 50,000 |
| 5. Premises " | | | 4,000 |
| 6. Bank charges and interest (considering 7% interest rates and 8 years amortization of capital) | | | 80,000 |
| 7. Insurance | 5,000 | 10,000 | 15,000 |
| 8. P.T.T. | | | 2,000 |
| 9. Stationery, engineering and office equipment | 3,000 | 1,000 | 4,000 |
| 10. Tools | 4,000 | 1,000 | 5,000 |
| 11. Medical expenses | 2,500 | 2,500 | 5,000 |
| 12. Legal & auditing expenses | | | 5,000 |
| 13. Cleanup | 1,000 | 1,500 | 2,500 |
| 14. Temporary structures | | 5,000 | 5,000 |
| 15. 10 vehicles | | | 20,000 |
| 16. Travel and entertainment expenses | | | 5,000 |
| 17. Miscellaneous and unforeseen " | | | 5,000 |
| TOTAL | | | <u>\$ 240,500</u>
===== |

ORGANISATION.

(Based on 2 shifts, 4 flats of 70 sq. m. per day)

| | | Assumed
Monthly
Salaries
\$ | |
|--|----------------|--------------------------------------|-------------------|
| <u>A. Technical, Administrative, Services.</u> | | | |
| Manager/Chief Engineer | 1 | | |
| Administrator/Accountant | 1 | | |
| Production Engineer | 1 | | |
| Erection Engineer | 1 | | |
| | 4 x \$1600 = | \$6,400.- | |
| Purchasing Clerk | 1 | | |
| Storekeeper | 1 | | |
| Timekeeper | 1 | | |
| Secretary-Typist | 1 | | |
| | 4 x \$ 600 = | \$2,400.- | |
| Office Clerks | 2 | | |
| " Boys | 2 | | |
| Watchmen | 3 | | |
| | 7 x \$ 100 = | \$ 700.- | |
| Total technical, Admin. Services | | | \$9,500.- |
| <u>B. Supervision.</u> | | | |
| Reinforcement & Inserts | | | |
| Superintendent | 1 | | |
| Concreting " | 1 | | |
| Plant(mechanical)" | 1 | | |
| " (electrical)" | 1 | | |
| Grinding | 1 | | |
| Repairs & Finishings Supt. | 1 | | |
| Final Inspection " | 1 | | |
| Transport " | 1 | | |
| Erection " | 1 | | |
| | 9 x \$ 800 = | \$7,200.- | |
| Erection Foremen | 2 x \$ 250 = | \$ 500.- | |
| Total Supervision | | | \$7,700.- |
| <u>C. Mechanics, Operators, Drivers.</u> | | | |
| Operators, and Drivers | 20 x \$ 500 = | \$10,000.- | |
| Mechanics | 10 x \$ 300 = | \$ 3,000.- | |
| Total Mechanics, Operators, Drivers. | | | \$13,000.- |
| <u>D. Unskilled Labourers.</u> | | | |
| | 200 x \$ 150 = | \$30,000.- | \$30,000.- |
| Total Manpower Monthly Cost | | | <u>\$60,200.-</u> |

Note: For breakdown of Labour Force, see backup sheets.

SUMMARY.

| | | |
|---|-----------------|------------------------|
| 1. Overheads (Technical & Administrative) | \$ 9,500 | 15.8% |
| 2. Productive(Reflected on Direct Cost) | | |
| Supervisors | \$3,650 - 12.7% | |
| Mechanics & Operators | \$5,800 - 21.5% | |
| Unskilled labourers | \$30,000 - 50 % | \$39,450 - 84.2% |
| | | <u>\$47,350</u> 100.0% |

SIX ALTERNATIVE FACTORIES APPROXIMATE COSTS.

| Alt-
erna-
tive | Production Line | Production
Area
(Sq. m.) | Factory
Bldg. | Forms | Cranes | C
Concrete
Plant | O
Utilities
Water,
Elec.
Steam, Air. | T
Reinforce-
ment
Plant | S
Other
Plant | Plant
Instal-
lation | TOTAL |
|-----------------------|---|--------------------------------|------------------|---------|---------|------------------------|--|----------------------------------|---------------------|----------------------------|-----------|
| 1 | On site, slabs only | 3,000 | 80,000 | 200,000 | 66,000 | 133,000 | 82,000 | 50,000 | 50,000 | 116,000 | 777,000 |
| 2 | Same as above, but
stationary factory | 3,000 | 150,000 | 200,000 | 66,000 | 133,000 | 82,000 | 50,000 | 50,000 | 116,000 | 847,000 |
| 3 | On site, all elements,
no factory finishing | 7,000 | 170,000 | 500,000 | 166,000 | 235,000 | 170,000 | 100,000 | 72,000 | 250,000 | 1,663,000 |
| 4 | Same as above but
stationary factory | 7,000 | 350,000 | 500,000 | 166,000 | 235,000 | 170,000 | 100,000 | 146,000 | 250,000 | 1,917,000 |
| 5 | Stationary, all
elements, factory
semi-finished | 8,000 | 400,000 | 500,000 | 166,000 | 235,000 | 170,000 | 100,000 | 154,000 | 250,000 | 1,975,000 |
| 6 | Stationary, all
elements, factory
finished | 11-13,000 | 550,000 | 500,000 | 166,000 | 235,000 | 170,000 | 100,000 | 164,000 | 250,000 | 2,135,000 |



TO NEW FIELDS OF CONSTRUCTION
MASS PRODUCTION OF REINFORCED-CONCRETE HOUSING UNITS

Dr. H. SLAVIN • 43, FRISHMAN ST. • TEL-AVIV • ISRAEL PHONE: 226518, OFFICE 961446

WE OFFER

OUR SERVICES FOR SOLVING YOUR HOUSING PROBLEMS

OUR PLANT

already in operation in Israel, will demonstrate the reliability and performance of our techniques, machinery and equipment.

WE SHALL CONSIDER

- A Royalties Agreement.
- Complete Designing, Construction; installation and running-in of plants.
- Manufacture of part or all the machinery and equipment in Israel.

ADDRESS : Dr. H. SLAVIN AND SON

43 Frishman Street; Phones : 226518, Office : 961446

ALL RIGHTS RESERVED FOR H. SLAVIN

PRODUCTION OF PREFABRICATED HOUSING UNITS

FINANCIAL FORECAST

ANNUAL TURNOVER (a) \$ 4,000,000

EXPENDITURE

| | | |
|-----------------------------------|--------------|-------------------|
| Materials | \$ 2,000,000 | |
| Wages (b) | 900,000 | |
| General, incl. Financial Expenses | 500,000 | |
| Depreciation (c) | 210,000 | 3,610,000 |
| Expected Annual Profits | | <u>\$ 390,000</u> |

FOOTNOTE :

- a) Based on annual sales of 1000 houses
- b) Based on rate of \$3,600.— per worker per year, taking into account annual output of 4 houses per worker.
- c) Based on life expectancy of:
 - 7 years for machinery (investment \$1,200,000)
 - 20 years for buildings (investment \$800,000)

Some Advantages:

- Low cost
- Minimum physical work
- Mass production
- Shortest possible time from raw-material to finished building
- Flexibility to local conditions

**BATCHING PLANT AND
CASTING OPERATION**

1. The batching plant is located near the casting shed, with sufficient storage facilities for mix ingredients. any existing batching plant may be used for this purpose.
2. The concrete mix is delivered in mixer trucks of suitable capacity, moving as required from form to form. The mix is fed in small doses under continuous vibration, preventing clogging and ensuring satisfactory penetration.
3. Slabs are subjected to 3-4 hours' steam curing prior to removal from the forms.

**COMPERATIVE
TIME REQUIREMENTS**

From raw materials to finished apartment the respective time requirements per sq. m./10 sq. ft./ floor area are:

20-25 work hours by conventional methods

12-14 " " by the best prefabrication method.

We are prepared to base our royalties on a rate of 8 hours per sq.m. of finished apartment, or even less, for large scale plants utilizing our method, machinery and equipment.




SHORT DESCRIPTION

1. Reinforcement assemblies are prepared in a special department.

OF PROCESS

2. Each assembly contains all inserts and nuts required.
3. The assemblies are carried on overhead rails connected to a fixing jig — one unit for a pair of slabs cast in a single form.
4. A special jig, used in conjunction with a crane, places the reinforcement assemblies in the forms, which are then closed for the casting operation.
5. A total of 10 large and 6 small forms are used for one pair of housing units.
6. Each run with these forms produces all elements making up one pair of housing units, in 8 hours.
The forms are then dismantled and the slabs removed.
7. One pair of housing units is cast in the morning shift, and another pair in the afternoon shift.
8. The slabs are ground to correct dimensions and junction angles.
9. The slabs are painted, windows and doors mounted, water-pipe and electric conduits installed.
10. The sanitary block is assembled, and installations completed.




3. A new / patented / process has also been developed in the technology of reinforcing steel. Reinforcement assemblies are installed by a simple and highly efficient technique, suitable for mechanized mass production and for intensive vibration. The reinforcement assemblies serve as mountings for doors and windows, for water - pipe and electrical conduits and for any other arrangements provided inside the slabs, thereby solving an important problem of prefabrication.
4. The reinforcement assemblies permit vertical slab castings with an inside insulating layer.


FURTHER DETAILS ON MACHINERY, PROCESS AND TECHNIQUES

1. Forms normally tend to lose their planeness through the effect of heat or fluctuations of rigidity, resulting in warping of the slabs. After years of research, we have succeeded in designing a form with minimum deformation, permitting slab castings up to 30 ft. in length with minimum warping / ± 1 mm. per meter slab length.
2. Due to fluctuations in aggregate quality, heat effects etc., slabs up to 30 ft. length cannot be cast with satisfactory accuracy in dimensions and angles of junction, so as to permit dry assembly in-situ. This drawback, still unsolved in other methods, has been overcome here by means of a completely new technique consisting in grinding of the joint surfaces at the plant, using special patented machinery. This is a breakthrough opening new possibilities of in-situ exactness.

3. Only erection is carried out on the site, permitting occupancy almost immediately.
4. No manual work at the plant — all operations are fully mechanized, using specially-designed, unique and simple machinery and equipment.


The new techniques include a unique patented external vibration process, up to 100 H.P. per casting machine. The mix is fed in small doses permitting, in conjunction with the vibration process, the use of vertical forms — thereby reducing plant floor space requirements to a minimum. Hand finishing of the castings is practically eliminated.







GENERAL DESCRIPTION

- 
1. All preparatory and finishing operations / joints, waterpipe and electrical conduits, painting, windows, doors etc./, amounting to 95% of the total work, are completed at the plant, as against 50 — 60% for other comparable methods.
 2. All elements are assembled without need for adjustment or in — situ casting.

- c. The yearly volume of house construction over the world amounts to millions of units, representing a field of activity comparable with, or perhaps even exceeding the automobile industry.
- d. The automobile —, shipbuilding — and steel construction industries will find, through our process, a new and exciting scope for their initiative.

THE MOST IMPORTANT FACTORS IN THE NEW METHOD ARE :

- a. Low cost — lower than for any other existing method.
- b. COMPLETE MECHANIZATION — with labor required for supervision only.
- c. Mass-production techniques comparable to those used, for example, in the automobile industry.
- d. Minimum time from casting to finished apartment — weeks instead of the months required at present.
- e. Flexibility, permitting easy adaptation of the method to local conditions and to consumers' specific requirements.

A BRIEF DESCRIPTION OF A NEW PROCESS AND EQUIPMENT DEVELOPED BY Dr. H. SLAVIN, FOR MASS PRODUCTION OF REINFORCED - CONCRETE HOUSING UNITS


- 1.) THE NEW METHOD** The outcome of 15 years of intensive research and development, was made possible by the design and construction of unique and efficient machinery/patented/ for mass production of reinforced - concrete housing units and their erection in multi-storey houses.

A plant based on this method, owned jointly by the State of Israel and H. Slavin, with daily output of four units / 3 rooms plus kitchen and sanitary block, total floor over 700 sq. ft. / is in operation in Israel.


- 2.) THE KEY FACTS** Necessitating a new method for mass production and erection of housing units are:
- a. Outside the U.S.S.R., over 90% of all housing units are built by conventional methods. These methods are slow and costly, and require a high proportion of manual work, while skilled labor is not always available.
 - b. No existing industrial process is less expensive than the conventional methods.



+ 70 Work-days =







הצעה
למבנה אירגוני
לחב' שבה

